NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

Participant Handbook

Sector
Interiors, Furniture and Fixtures

Sub-Sector
Interior Design and Installation

Occupation
Interior Designing

Reference ID: **FFS/Q0203, Version: 3.0,**
NSQF Level: 4.5

Assistant Interior Designer

This book is prepared by

Furniture & Fittings Skill Council (FFSC)

Address: 407-408, 4th Floor, DLF City Court, Sikanderpur

Gurgaon 122002, Haryana, India

Email: info@ffsc.in

Website: www.ffsc.in

Phone: +91 124 4513900

All Rights Reserved

First Edition, December 2024

Under Creative Commons License: CC-BY-SA

Copyright © 2024

Attribution-Share Alike: CC BY-SA

This license lets others remix, tweak, and build upon the work even for commercial purposes, as long as they credit you and license their new creations under identical terms. This license is often compared to “copyleft” free and open-source software licenses. All new works based on these will carry the same license, so any derivatives will also allow commercial use. This is the license used by Wikipedia and is recommended for materials that would benefit from incorporating content from Wikipedia and similarly licensed projects.

Disclaimer

The information contained herein has been obtained from sources reliable to Furniture & Fittings Skill Council (FFSC). Furniture & Fittings Skill Council (FFSC) disclaims all warranties to the accuracy, completeness or adequacy of such information. Furniture & Fittings Skill Council (FFSC) shall have no liability for errors, omissions, or inadequacies, in the information contained herein, or for interpretations thereof. Every effort has been made to trace the owners of the copyrighted material included in the book. The publishers would be thankful for any omissions in the book being brought to their notice; which will be acknowledged as applicable in future editions of the same. No entity in Furniture & Fittings Skill Council (FFSC) shall be responsible for any loss whatsoever, sustained by any person who relies on this material. The material in this publication is copyrighted. No parts of this publication may be reproduced, stored or distributed in any form or by any means either on paper or electronic media, unless authorized by the Furniture & Fittings Skill Council (FFSC).

> Skilling is building a better India. If we have to move India towards development then Skill Development should be our mission.

Shri Narendra Modi
Prime Minister of India

Certificate

CURRICULUM COMPLIANCE TO
QUALIFICATION PACK – NATIONAL OCCUPATIONAL STANDARDS

is hereby issued by the

FURNITURE & FITTINGS SKILL COUNCIL

for

SKILLING CONTENT: PARTICIPANT HANDBOOK

Complying to National Occupational Standards of
Job Role/ Qualification Pack: 'Assistant Interior Designer' QP No. 'FFS/Q0203 NSQF Level 4.5'

Date of Issuance: August 31th 2023
Valid up to: August 31th 2026

* Valid up to the next review date of the Qualification Pack

Authorized Signatory
(Furniture & Fittings Skill Council)

Acknowledgements

Furniture and Fittings Skill Council (FFSC) would like to express its gratitude to all the individuals and institutions who contributed in different ways towards the preparation of this "Participant Handbook". Without their contribution it could not have been completed. Special thanks are extended to those who collaborated in the preparation of its different modules. Sincere appreciation is also extended to all who provided peer review for these modules.

The preparation of this handbook would without the Furniture & Fittings Skill Indutsry's support. Industry feedback has been extremely encouraging from inception to conclusion and it is with their input that we have tried to bridge the skill gaps existing today in the industry.

This participant handbook is dedicated to the aspiring youth who desire to achieve special skills which will be a lifelong asset for their future endeavours.

About this book

Welcome to the "Assistant Interior Designer" training programme. This PHB intends to facilitate the participants with detailed knowledge of the concept of industry, the occupation of Interior Designing, the role of Assistant Interior Designer and their functioning.

This Participant Handbook has been designed based on the Qualification Pack (QP) under the National Skill Qualification Framework (NSQF) and it comprises the following National Occupational Standards (NOS)/ topics as well as additional topics.

1. FFS/N0210: Assist in client servicing and on-site supervision during survey/recce
2. FFS/N0211: Assist in the development of interior concepts and designs
3. FFS/N0212: Assist in execution and monitoring of the interior design project
4. FFS/N0213: Assist in the procurement process and on-site installation
5. FFS/N8207: Supervise health and safety protocols for project designing at the workplace
6. DGT/VSQ/N0102: Employability Skills (60 Hours)
7. Elective 1: Residence - FFS/N0214: Assist in preparation and execution of interior design concepts/plans for residence projects
8. Elective 2: Kitchen - FFS/N0215: Assist in preparation and execution of interior design concepts/plans for kitchen projects
9. Elective 3: Commercial - FFS/N0216: Assist in preparation and execution of interior design concepts/plans for commercial projects
10. Elective 4: Hospitality - FFS/N0217: Assist in preparation and execution of interior design concepts/plans for hospitality projects
11. Elective 5: Academic Institutions - FFS/N0218: Assist in preparation and execution of interior design concepts/plans for academic institutions projects
12. Elective 6: Retail Fitout and Exhibition - FFS/N0219: Assist in preparation and execution of interior design concepts/plans for retail fitout and exhibition projects

Symbols Used

Key Learnings Outcomes

Unit Objective

Exercise

Tips

Notes

Activity

Summary

Table of Contents

S. No.	Modules and Units	Page No.
1.	**Introduction to the Role of Assistant Interior Designer (Bridge Module)**	**1**
	Unit 1.1: Interior Design Industry and Organizational Structure	3
	Unit 1.2: Roles & Responsibilities as Assistant Interior Designer	7
	Unit 1.3: Career Progression	14
2.	**Introduction to Various Types of Interior Projects, Products, Materials, and Accessories Chain (Bridge Module)**	**21**
	Unit 2.1: Interior Design Basics and Process Flow	23
	Unit 2.2: Furniture Trends and Interior Projects	74
3.	**Interpret and Analyze the Client Requirement (FFS/N0210)**	**87**
	Unit 3.1: Themes, Styles, Layouts Associated with Interior Design Projects	89
	Unit 3.2: Interpreting Site Layout/Drawings	98
4.	**Site survey/Recce for Interior Designing (FFS/N0210)**	**109**
	Unit 4.1: Site Surveys	111
	Unit 4.2: Measurement and Marking Activities	127
5.	**Client Deliberations and Market Research (FFS/N0211)**	**149**
	Unit 5.1: Conduct Market Research and Trend Analysis	151
	Unit 5.2: Client Deliberation	160
6.	**Project Budgeting and Execution Planning (FFS/N0211)**	**173**
	Unit 6.1: Project Planning and Timeline Management	175
	Unit 6.2: Need Assessment and Estimation	180
	Unit 6.3: Project Documentation and Approvals	189
7.	**Design Project Drafts, Mood Boards, and Models (FFS/N0211)**	**197**
	Unit 7.1: Mood Boards, 3D Renders, and Miniature Models Development	199
	Unit 7.2: Project Presentation and Change Request	215
8.	**Team and Task Management (FFS/N0212)**	**225**
	Unit 8.1: Task Delegation	227
	Unit 8.2: Management and Monitoring	233
9.	**Prepare and Validate the Design Drafts and Drawings (FFS/N0213)**	**243**
	Unit 9.1: Approved for Construction (AFC) Drawings	245
	Unit 9.2: SOP for Modification and Approvals	253
10.	**Procurement Management and Monitoring of on-Site Project Work (FFS/N8207)**	**263**
	Unit 10.1: Procurement and Tender Documentation	265
	Unit 10.2: Quality Check	273
	Unit 10.3: Project Installation and Handover	279

Table of Contents

S. No.	Modules and Units	Page No.
11.	**Health, Safety and Hygiene Protocols while Designing (FFS/N8207)**	**291**
	Unit 11.1: Health and Safety Protocols	293
	Unit 11.2: Hygiene, PPE and Worksite Practices	300
	Unit 11.3: Emergency Preparedness and Response	303
	Unit 11.4: Safety Signs	315
12.	**Material Conservation and Resources Optimization (FFS/N8207)**	**321**
	Unit 12.1: Resource Optimization	323
	Unit 12.2: Sources of Energy and Consumption	326
13.	**Employability Skills (DGT/VSQ/N0102) (60 Hrs.)**	**333**
	Employability Skills is available at the following location https://eskillindia.org/NewEmployability Scan the QR code below to access the ebook	
14.	**Technicalities in a Residence and Kitchen Project (FFS/N0216)**	**335**
	Unit 14.1: Business Development and Client Requirement Analysis for Residence and Kitchen Project	337
	Unit 14.2: Project Execution, Estimation, and Task Demarcation for Residence and Kitchen Project	354
15.	**Technicalities in a Commercial Project (FFS/N0216)**	**365**
	Unit 15.1: Business Development and Client Requirement Analysis for Academic Institution Project	367
	Unit 15.2: Project Execution, Estimation and Task Demarcation for Commercial project	381
16.	**Technicalities in Academic Institution Project (FFS/N0218)**	**391**
	Unit 16.1: Business Development and Client Requirement Analysis for Academic Institution Project	393
	Unit 16.2: Project Execution, Estimation and Task Demarcation for Academic Institution Project	403
17.	**Conduct Client Deliberation and Defining Scope of Work for Hospitality Project (FFS/N0217)**	**413**
	Unit 17.1: Business Development and Client Requirement Analysis for Hospitality Project	415
	Unit 17.2: Project Execution, Estimation and Task Demarcation for Hospitality Project	427
18.	**Technicalities in a Retail Fit-out and Exhibition Project (FFS/N0219)**	**435**
	Unit 18.1: Business Development & Client Requirement Analysis for Retail Fit-out and Exhibition Project	437
	Unit 18.2: Project Execution, Estimation and Task Demarcation for Retail Fit-out and Exhibition Project	448

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

1. Introduction to the Role of Assistant Interior Designer

Unit 1.1: Interior Design Industry and Organizational Structure
Unit 1.2: Roles & Responsibilities as Assistant Interior Designer
Unit 1.3: Career Progression

Bridge Module

Key Learning Outcomes

At the end of this module, the participants will be able to:

1. Outline on the various organizational structure, processes, code of conduct, reporting matrix and escalation hierarchy.
2. Define the scope and significance of the interiors industry.
3. Outline the occupational map of the Interiors industry-related job roles.
4. Identify the attributes and essential skill sets required for an Assistant Interior Designer.
5. Explain the role, responsibilities, and key result areas of for an Assistant Interior Designer.
6. List the various operations/activities that take place at the worksite and Assistant Interior designer role in the same.
7. Outline the career progression path for an Assistant Interior Designer.
8. List the regulatory authorities, laws, and regulations related to an individual while working.
9. Explain the importance of job cards and timely reporting to supervisors in employee performance evaluation.

Unit 1.1: Interior Design Industry and Organizational Structure

Unit Objectives

At the end of this unit, the participants will be able to:

1. Outline on the various organizational structure, processes, code of conduct, reporting matrix and escalation hierarchy.
2. Define the scope and significance of the interiors industry.
3. Outline the occupational map of the Interiors industry-related job roles.

1.1.1 Organizational Structure and Processes in India

The organizational structure of the interior design industry is diverse and multi-faceted, with companies operating in various segments, including residential, commercial and hospitality design. The industry includes small-scale interior design firms, large multinational companies, and even independent designers. The organisational structure is briefly explained in the following figure:

Small Firms and Freelancers	Many interior designers in India operate as independent consultants or in small teams. These firms may handle projects ranging from residential designs to boutique office spaces.
Medium to Large Firms	Larger firms have more structured hierarchical setups. They may include departments such as design, project management, procurement, and client relations.
Multinational Firms	Global companies involved in interior design in India tend to have a more complex organizational structure, including various specialized roles like CAD experts, designers, project managers, and even sustainability consultants.
Collaborative Processes	Most firms follow a collaborative design process, where designers work closely with architects, engineers, and clients.
Project Lifecycle	Interior design projects typically follow phases: conceptualization, design development, sourcing, implementation, and post-project evaluation.

Fig. 1.1.1: Organisational structure in the interior design industry

The interior design industry has witnessed rapid growth in recent years, driven by factors such as urbanization, increasing disposable incomes, and changing lifestyle preferences. They key aspects of this industry are:

- Urbanization and Real Estate Growth – With the rise of urbanization, there is a growing demand for both residential and commercial interior design services. Real estate projects, including residential complexes, retail spaces, offices, and hotels, have spurred demand for interior designers.
- Commercial and Hospitality Sector = Large companies, hotels, and resorts often require specialized interior design services to meet their branding and functionality needs. High-end brands and startups in the tech, finance, and hospitality sectors require professional interior designers to create modern and aesthetic workspaces.
- Technological Integration = The incorporation of technology such as smart home automation, 3D modelling, virtual reality, and sustainable design techniques is increasingly significant in the interiors industry.
- Market Size=According to industry reports, the Indian interior design industry's market size is expected to grow substantially, contributing significantly to the economy.

Cultural Significance = India's rich cultural heritage influences the interior design style in various regions, from traditional and ethnic designs to contemporary and minimalist aesthetics.

1.1.2 Occupational Map of the Interior Design Industry

The interior design industry in India offers a wide array of career opportunities, ranging from creative roles to technical and managerial positions.

Careers in Interior Design	**Interior Designer:** The core role involves conceptualizing and designing functional, aesthetic, and user-friendly interior spaces for residential, commercial, and hospitality sectors.
	Space Planner: Focuses on efficient space utilization and functional design. This role involves a lot of technical drawing and understanding of architectural principles.
	CAD Designer/Draughtsman: A technical role that involves creating detailed drawings, layouts, and models of interior spaces using Computer-Aided Design (CAD) software.
	Project Manager: Oversees the execution of interior design projects, ensuring they are completed on time, within budget, and to the desired quality standards.
	Lighting Designer: Specializes in creating lighting schemes that enhance the aesthetic and functional qualities of interior spaces.
	Furniture Designer: Designs custom furniture pieces to complement the interior design of a space, ensuring they are aesthetically pleasing and functional.
	Sustainability Consultant: Focuses on incorporating eco-friendly, sustainable materials and designs into interior projects.
	Visual Merchandiser: Often found in the retail sector, this role involves designing attractive and functional product displays and store layouts.

Fig. 1.1.2: Occupational map of the Interior design industry.

Some educational pathways that can be followed in this field are:

Bachelor's and Master's Degrees in Interior Design: These programs focus on both the creative and technical aspects of the profession.	Short-Term Diplomas and Certification: Shorter programs and certifications in CAD, 3D rendering, lighting design, etc., are common for those looking to specialize in certain areas.	Apprenticeships and Internships: Many interior designers begin their careers as interns or apprentices under established professionals to gain hands-on experience.

Fig. 1.1.3: Pathways for career growth

The interior design industry is evolving rapidly, with several emerging trends shaping the landscape of occupations within the field. Some of these trends reflect global influences, while others are unique to the Indian context. Some of the emerging trends in occupations in this field are:

Sustainability and Eco-friendly Design	There is a growing demand for sustainable interior design practices, including the use of eco-friendly materials, energy-efficient lighting, and water conservation systems.	
Smart Homes and Technology Integration	This includes the integration of lighting, security, and entertainment systems that can be controlled remotely. Designers who can offer technical solutions for incorporating IoT (Internet of Things) devices, automation, and other tech-forward solutions are becoming essential.	
Virtual and Augmented Reality (VR/AR)	Virtual and augmented reality (VR/AR) are transforming the way interior designers present their ideas. The demand for 3D rendering and visualization services is increasing, especially for high-end residential and commercial projects. Artists skilled in 3D design and virtual reality will be more prominent in the industry.	
Adaptive Reuse and Heritage Conservation	There is a growing emphasis on preserving the cultural heritage through interior design. Designers with expertise in adaptive reuse (repurposing old buildings for new purposes) and heritage conservation are becoming increasingly important.	

Health and Wellness-focused Design	Post-pandemic, health and wellness have become a priority in interior design. Wellness-focused interior designers who create spaces promoting physical and mental well-being are increasingly in demand.	
Modular and Flexible Design Solutions	With the rise of flexible workspaces, urban living, and small homes, there is a demand for modular designs that allow spaces to be easily adapted for various purposes.	
Inclusive and Universal Design	As accessibility becomes a more prominent concern, interior designers who specialize in creating universally accessible spaces are emerging. There is an increasing focus on designing spaces that cater to diverse populations, including elderly, differently-abled individuals, and people from various socioeconomic backgrounds.	
Commercial and Retail Design	Retail and commercial spaces are evolving into experience-driven environments. This could include designing retail environments that reflect a brand's identity or creating interactive environments in restaurants, offices, and hotels.	

Table 1.1.1: Emerging trends in occupations

Unit 1.2: Roles & Responsibilities as Assistant Interior Designer

Unit Objectives

At the end of this unit, the participants will be able to:

1. Identify the attributes and essential skill sets required for an Assistant Interior Designer.
2. Explain the role, responsibilities, and key result areas of for an Assistant Interior Designer.
3. List the various operations/activities that take place at the worksite and Assistant Interior designer role in the same.
4. List the regulatory authorities, laws, and regulations related to an individual while working.
5. Explain the importance of job cards and timely reporting to supervisors in employee performance evaluation.

1.2.1 Attributes and Essential Skill Sets

An Assistant Interior Designer plays a crucial role in the successful execution of interior design projects. The role demands a combination of technical, and soft skills to ensure smooth project delivery.

The key attributes of an assistant interior designer are:



Fig. 1.2.1: Key attributes of an assistant interior designer

Some essential skills required by an interior designer are:

- **Design and Visualization Skills –** An assistant Interior Designer must be able to visualise client needs into creative and functional design concepts. This includes creating mood boards, 3D renders, and layout drawings that align with the client's preferences, style, and budget. Visualizing the 3-D arrangement and aesthetics while ensuring practicality is a key part of the designer's role.
- **Technical Knowledge –** Proficiency in design software such as AutoCAD, SketchUp, and Photoshop is critical for preparing professional designs and construction-ready drawings. Additionally, understanding architectural terminologies, construction parameters, and MEP (Mechanical, Electrical, and Plumbing) integration is vital to align interior design with technical feasibility.

Fig. 1.2.2: Logos of software

- **Adherence to Execution Plan–** An Assistant Interior Designer must be able to adhere project timelines, work within estimated costs, and assist in defining the scope of work. This includes site recce, client interactions. Ensuring timely documentation and aligning the project phases from design approval to installation is a core skill.
- **Material Knowledge and Selection –** Selecting appropriate materials, finishes, and furnishings is a major responsibility. This involves understanding material properties, cost, availability, and aesthetics. Designers must also coordinate with vendors, evaluate quality, and approve samples such as tiles, fabrics, sanitary ware, and lighting fixtures.
- **Client Communication and Presentation Skills –** Effective verbal and visual communication is essential for discussing design ideas, presenting concepts, and incorporating feedback. The designer must maintain regular communication with clients, explain design rationale clearly, and ensure client satisfaction throughout the project cycle.

Fig. 1.2.3: Mood board sample used during client presentations

- **Team Coordination –** Assistant Interior Designers often assist seniors on-site, coordinate with contractors and vendors, and ensure quality control. They be able to work as per delegated tasks and adherence to timelines are integral to this role.
- **Problem-Solving and Critical Thinking** - The ability to think critically and analyse situations is essential for making informed decisions that impact the project's success. Creativity is crucial to solve design challenges, think outside the box, and come up with innovative solutions for design elements and spatial planning. Creativity in space planning, aesthetics, and function is fundamental. Assistant Interior Designers must be able to solve on-site issues, accommodate last-minute changes, and suggest alternate solutions without compromising design integrity. Thinking on their feet and making design decisions under pressure are valuable skills.
- **Organizational Skills -** An Interior designer must maintain thorough records of all aspects of the project, including contracts, design changes, material inventories, and progress reports. Managing and maintaining detailed records is crucial for project tracking. Assistant Interior Designers must be able to assist in managing design dockets, site survey reports, BOQs, vendor lists, and approval documents. Accurate and organized documentation ensures smooth communication with clients and vendors and supports project audits or future references.

  For reference, see Annexure 1 for sample formats of these records, including templates for BOQ, BOM, and sample NOCs.
- **Awareness of Safety and Sustainability –** Understanding occupational health and safety protocols is essential while visiting sites or supervising installation. Knowledge of eco-friendly materials, resource optimization techniques, and regulatory compliance ensures that designs meet safety and sustainability benchmarks.

  An Assistant Interior Designer plays a critical role in creating meaningful spaces that balance beauty, function, safety, and cost. These essential skills ensure smooth execution from concept to client handover.

The key responsibilities of an Assistant Interior Designer are:

Assist in Project Planning	Support the senior designer in preparing tentative and final scope of work, assisting in block estimates, and drafting timelines based on client inputs and team discussions.
Design Concept Development	Assist in creating design concepts, mood boards, and basic 3D visual references as per the client's brief and site conditions. Help present design ideas for internal review and client approvals.
Coordination with Teams	Coordinate with the design team, site supervisors, and vendors to ensure smooth communication and alignment of project objectives and design details.
Site Supervision:	Assist in site visits to observe implementation of approved designs, noting deviations and reporting them to the senior designer for corrective action.
Procurement Support:	Support the selection of materials and finishes by researching vendor options and preparing initial material lists as per project requirements.
Scheduling	Help track day-to-day progress of design-related activities. Inform the team of any delays and update the senior designer with revised timelines.
Quality Assurance	Assist in checking that the work on-site aligns with the design intent and specifications shared. Collect material samples and document quality checks as instructed.
Relationship Building with Clients	Join meetings with clients to note their inputs, update them on progress, and clarify basic queries under the guidance of the senior designer.
Documentation and Reporting	Maintain organized project folders including concept sketches, client feedback, material samples, and meeting notes for reference and reporting.
Risk Identification and Resolution	Identify and report site-level risks like delays or material mismatches. Suggest alternative materials or minor design modifications in consultation with senior designers.

Fig. 1.2.4: Key responsibilities of Assistant Interior Designer

The key result areas for an Assistant Interior Designer are:



Fig. 1.2.5: Key result areas of an Assistant Interior Designer

Operations and Activities at the Worksite

The operational activities at the worksite focus on translating design concepts into physical reality. These tasks are practical, action-oriented, and critical to the successful execution of interior design projects.

Some of the key operations undertaken in this job profile are:



Fig. 1.2.6: Key operations undertaken by Interior Designer

The key regulatory authorities are:

Bureau of Indian Standards (BIS)	The Bureau of Indian Standards (BIS) sets quality standards for materials used in interior design.
The National Building Code of India (NBC)	The NBC provides guidelines for construction and design, which must be followed in interior design projects.
Local Municipal Corporations	The interior design industry need to adhere to local building codes and zoning laws when planning and executing designs.
Fire and Safety Regulations	While building interiors. the industry person must comply with the fire safety norms defined by local authorities and the fire department.
Environmental and Sustainability Laws	Sustainable and eco-friendly interior designs are encouraged, and various green building certifications (e.g., LEED) may apply.

Fig. 1.2.7: The key regulatory authorities

Job Cards

Job cards and timely reporting are crucial tools for an Interior Designer to maintain effective coordination and oversight throughout a project. Job cards are used to document tasks assigned to various teams or workers on-site, such as electricians, plumbers, carpenters, and painters, ensuring that work is organized and tracked efficiently across trades.

Maintaining job cards and submitting timely reports to supervisors plays a vital role in evaluating an interior designer's performance at the worksite. Job card helps the interior designer in the following ways:

Fig. 1.2.8: Benefits of Job Card to an interior Designer

Unit 1.3: Career Progression

Unit Objectives

At the end of this unit, the participants will be able to:

1. Outline the career progression path for an Assistant Interior Designer.

1.3.1 Career Progression Path for an Assistant Interior Designer

The role of an Assistant Interior Designer can lead to significant career progression within the industry. With experience and skill development, individuals can advance to higher positions.

The career progress may look like as given in the following figure:



Fig. 1.3.1: Career Progression

The progression from one level to the next typically requires a combination of formal education, practical experience, and demonstrated competencies. Continuous professional development and upskilling are essential to advance in this career path.

The key factors for progression are gaining expertise in project management and client handling, mastery of industry-specific software tools, expanding knowledge in budgeting, scheduling, and procurement and building a strong professional network within the industry.

The interior design industry is regulated by various laws and standards that ensure the safety, quality, and functionality of design projects.

Summary

- The organizational structure of the interior design industry is diverse and multi-faceted, with companies operating in various segments, including residential, commercial and hospitality design.
- The industry includes small-scale interior design firms, large multinational companies and even independent designers.
- Educational qualifications needed in this field are a Bachelor's and Master's Degrees in Interior Design, Short-Term Diplomas and Certification in CAD etc., and Apprenticeships and Internships.
- Occupational trends reflect demand for sustainable, wellness-focused, modular, and inclusive design practices.
- The interior design industry in India is regulated by various laws and standards that ensure the safety, quality, and functionality of design projects.
- These regulatory authorities are Bureau of Indian Standards (BIS), The National Building Code of India (NBC), Local Municipal Corporations, Fire and Safety Regulations and Environmental and Sustainability Laws.
- Interior designers must master a blend of technical, creative, and managerial skills such as design software use, client communication, site coordination, and documentation.
- Key responsibilities include project planning, material selection, team supervision, vendor coordination, and ensuring compliance with client expectations.
- Job card is an important tool for tracking site tasks assigned to various trades and ensuring accountability and progress reporting.
- Timely reporting helps in transparent communication with supervisors and clients, aiding performance tracking and project efficiency.

Exercise

Multiple Choice Questions (MCQs)

1. Firms that may not have a hierarchical approach are_____.
   a. Small firms
   b. Medium firms
   c. Multinational firms
   d. Large firms

2. Which of these are not a type of technological integration in interior designing?
   a. 3D modelling
   b. Smart home automation
   c. Virtual Reality (VR)
   d. Automobile Integration

3. What is one common software used by interior designers?
   a. Excel
   b. Photoshop
   c. AutoCAD
   d. Tally

4. Why are job cards used in interior design projects?
   a. To play games on site
   b. To list office holidays
   c. To track assigned work and workers
   d. To decorate the wall

5. What is one benefit of timely reporting?
   a. Reduces paperwork permanently
   b. Helps skip site visits
   c. Keeps clients and seniors updated
   d. Avoids coordination with team members

6. Which of the following is part of the interior design industry?
   a. Road construction
   b. Retail and exhibitions
   c. Textile manufacturing
   d. Shipping and logistics

7. Which of these laws help ensure building safety in interior design?
   a. Indian Traffic Code
   b. National Building Code
   c. Forest Act
   d. Indian Penal Code

8. What is a growing trend in modern interior design projects?
   a. Ignoring local culture
   b. Using non-recyclable materials
   c. Designing flexible and modular spaces
   d. Avoiding use of technology

9. Which of the following contributes to the rapid growth of the interior design industry in India?
   a. Limited use of technology
   b. Decline in hospitality projects
   c. Urbanization and real estate growth
   d. Reduced client expectations

10. Which of the following is an emerging design trend in the interior design industry?
    a. Avoiding use of digital tools
    b. Creating spaces with no accessibility features
    c. Inclusive and universal design
    d. Using outdated materials only

Notes

Scan the QR codes or click on the link to watch the related videos

https://www.youtube.com/watch?v=QDdZ3P9IYf4

Introduction to FFSSC

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

2. Introduction to Various Types of Interior Projects, Products, Materials, and Accessories Chain

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

Unit 2.1: Interior Design Basics and Process Flow
Unit 2.2: Furniture Trends and Interior Projects

Bridge Module

Key Learning Outcomes

At the end of this module, the participants will be able to:

1. Define interior drafting, interior designing, and interior project management.
2. Illustrate the process flow of an Interior Designing project.
3. Classify different types of Interior Design projects in terms of space, theme, and styles.
4. List the various types of advanced raw materials and accessories used in an Interior Design project.
5. Differentiate between types of raw material as per the given checklist.
6. List the various categories of advanced architectural hardware and fittings used designing and their usage.
7. Identify the architectural hardware as per the type of application.
8. List the different types of furniture and their area of applications.
9. Outline the latest trends and advancements related to the interior designing process.
10. Analyze different Interior projects for categorization based on space, style, and themes.
11. Examine the Interior projects and define the theme and elements.
12. Explain the steps involved in the interior design project from client deliberations to project handover and signoff.

Unit 2.1: Interior Design Basics and Process Flow

Unit Objectives

At the end of this unit, the participants will be able to:

1. Define interior drafting, interior designing, and interior project management.
2. Illustrate the process flow of an Interior Designing project.
3. Classify different types of Interior Design projects in terms of space, theme, and styles.
4. List the various types of advanced raw materials and accessories used in an Interior Design project.
5. Differentiate between the different types of raw material as per the given checklist.
6. List the various categories of advanced architectural hardware and fittings used designing and their usage.
7. Identify the architectural hardware as per the type of application.
8. Analyze different Interior projects for categorization based on space, style, and themes.
9. Examine the Interior projects and define the theme and elements.
10. Explain the steps involved in the interior design project from client deliberations to project handover and signoff.

2.1.1 Interior Drafting, Interior Designing, and Interior Project Management

Interior Drafting

This is the technical part of interior design, involving the creation of scaled drawings and detailed plans that illustrate the dimensions and layout of a space. Interior drafting includes floor plans, elevations, sections, and construction drawings that help in translating a designer's vision into a tangible structure. Interior drafting is a crucial step, especially when working with local contractors to ensure all designs comply with building codes and construction standards.

The typical steps involved in Interior Drafting are explained in the following section.

Client Consultation and Design Briefing

Fig. 2.1.1: Client Consultation and Design Briefing

Objective: Understand the client's vision, requirements, and functional needs.

The drafter works with The APM to gather all essential information, including the size of the space, the purpose of the project (residential, commercial, or hospitality), budget, and the preferred style or theme.

Site Measurements and Dimensions

Fig. 2.1.2: Site Measurements and Dimensions

Objective: Ensure accurate representation of the existing space.

A precise measurement of the site is taken, either manually or with digital tools like laser measurers. This includes noting down the dimensions of rooms, doors, windows, ceiling heights, wall thicknesses, and other architectural features that need to be included in the design.

Furniture and Fixtures Layout



Fig. 2.1.3: Furniture and Fixture Layout (Top View)

Note: Check Annexure for enlarge image of the same

Objective: Specify the placement of furniture and fixtures in the space.

The furniture layout is detailed to show how different furniture pieces will fit within the space. This can include furniture arrangement for living rooms, dining areas, and workspaces. The drafting stage also includes detailed drawings for custom-built furniture and cabinetry.

Preliminary Space Planning



Fig. 2.1.4: Preliminary Space Planning

Objective: Organize the available space effectively.

Based on the client's needs, a preliminary layout plan is created, including the basic placement of walls, doors, windows, and furniture. This stage helps to visualize the use of space and how different areas of the room will function.

Creation of Floor Plans



Fig. 2.1.5: Creation of Floor Plan

Objective: Develop a visual representation of the space's layout.

The floor plan is drawn to scale, detailing the location of walls, doors, windows, furniture, and fixtures. This plan can be either hand-drawn or created using computer-aided design (CAD) software like AutoCAD or SketchUp. The floor plan serves as the backbone of the interior design project, guiding construction and material selection.

Elevations and Sections

Objective: Provide a vertical view of the space to depict walls, doors, and other features.

Elevations: Drawings of walls showing how each side of a room looks, including the positioning of doors, windows, and built-in features like shelves or cabinets.

Sections: Cut-through views of the space that show vertical dimensions, such as ceiling height, floor-to-ceiling measurements, and the placement of built-in furniture or other structural elements.

Detailed Design Elements and Specifications

Objective: Finalise the technical aspects of the design.

After the basic layouts and elevations are drawn, detailed elements such as custom furniture, wall treatments, finishes, lighting, flooring, and other materials are specified. This step ensures that every design choice is implemented accurately and precisely during construction.

Electrical and Lighting Plans



Fig. 2.1.6: Electrical and Lighting Plans

Objective: Plan electrical systems and lighting to enhance functionality and design.

A separate electrical plan is drafted, indicating the locations of outlets, switches, and light fixtures. For example, lighting plans would include the placement of ambient, task, and accent lighting, as well as the selection of light fixtures to complement the interior theme.

Material and Finish Specifications

Objective: Choose and specify materials for construction and finishes.

Detailed drawings specify the materials used for floors, walls, and ceilings. For example, in a apartment, the interior drafting might specify ceramic tiles for the kitchen floor, granite for countertops, and wooden paneling for the living room walls.

Sample: Material and Finish Specification Sheet

Project Name: Modern 2BHK Apartment
Location: ABC
Designer: [Your Name Here]
Date: [DD/MM/YYYY]

1. Flooring

Area	Material	Finish	Remarks
Living Room	Vitrified Tiles	Glossy	600x600 mm, beige shade
Kitchen	Ceramic Tiles	Matte	300x300 mm, anti-skid
Bedrooms	Wooden Finish Tiles	Matte	Porcelain, 195x1200 mm
Bathroom	Ceramic Tiles	Anti-skid Matt	300x300 mm, dark grey
Balcony	Terracotta Tiles	Textured	300x300 mm, earthy tone

2. Wall Finishes

Area	Material	Finish	Remarks
Living Room	Acrylic Emulsion Paint	Satin	Light grey, washable
Kitchen	Ceramic Tiles	Glossy	Up to 600 mm above countertop
Bedrooms	Wall Putty + Paint	Matte	Warm pastel colours
Bathroom	Ceramic Wall Tiles	Glossy	Full height, light tone

3. Ceiling Finishes

Area	Material	Finish	Remarks
Living Room	POP False Ceiling	Paint Finish	Recessed lighting integrated
Kitchen	Cement Board Ceiling	Emulsion Paint	Water-resistant
Bedrooms	POP Ceiling	Emulsion Paint	Cove lighting detail
Bathroom	Moisture-Resistant Board	Emulsion Paint	White, with exhaust cut-out

4. Countertops and Joinery

Element	Material	Finish	Remarks
Kitchen Counter	Granite	Polished	Black Galaxy
Bathroom Vanity	Quartz	Matte	White quartz
Wardrobe Shutters	MDF with Laminate	Matte	Woodgrain finish, soft-close hinges
TV Unit Panel	Plywood with Veneer	Natural Polish	Walnut tone

5. Fixtures & Hardware

Item	Material	Finish	Remarks
Door Handles	Stainless Steel	Brushed Steel	Sleek modern look
Cabinet Pulls	Zinc Alloy	Chrome	Ergonomic design
Faucet (Kitchen/Bath)	Brass	Chrome	Single lever, wall-mount type
Light Fixtures	Mild Steel + Glass	Matt Black	Pendant lights and recessed ceiling lights

Fig. 2.1.6: Electrical and Lighting Plans

Final Review and Approval

Objective: Ensure that all details are correctly included and meet client expectations.

Once the draft is complete, The APM and client review the plans together. Adjustments may be made based on client feedback or technical requirements. This step may involve going back and forth to ensure that the design is both aesthetically pleasing and functional.

Interior Designing

This is the creative and artistic process of planning and arranging spaces. It involves selecting and coordinating colour schemes, materials, furniture, lighting, and decor to create functional and aesthetically pleasing interiors. Designers consider client preferences, budget constraints, and cultural influences, which play a significant role in the interior design landscape. For example, a designer might incorporate traditional elements like wood carvings or brass lamps in a modern living room design.

The steps involved in interior designing are:



Fig. 2.1.7:

Initial Consultation with Client

Objective: Understand client needs, preferences, and ls.

Process: The Assistant Interior Designer along with the APM and senior Interior Designer meets with the client to discuss the purpose of the space, style preferences, budget, and any specific requirements or constraints. For example, in a home design project in Kolkata, the client may request a fusion of modern and traditional designs.

Outcome: The Assistant Interior Designer along with the APM and senior Interior Designer gets a clear understanding of the client's vision and expectations, which forms the foundation for the entire project.

Conceptual Design and Space Planning

Objective: Develop an initial concept and layout for the space.

Process: The APM along with senior Interior Designer creates mood boards, selects colour schemes, and proposes layout ideas for the space. This step may involve initial sketches or 2D plans that illustrate the space's zoning, like kitchen areas, living areas, and private zones. The focus is on optimizing space and making it functional while considering the client's preferences.

Outcome: A conceptual design or "theme" is established, incorporating the client's desires and making sure that the design complements the space's use.

Design Development and Visualization

Objective: Finalize the design choices and make visual representations.

Process: The Assistant Interior Designer along with the APM and senior Interior Designer refines the design, adding details such as furniture selection, materials, finishes, and fixtures. Using software like AutoCAD, SketchUp, or 3D rendering tools, The APM produces 3D visualizations of how the space will look. This allows the client to virtually experience the design and make any necessary changes.

Outcome: A more refined and realistic design, ready for client feedback and approval.

Material and Product Selection

Objective: Choose appropriate materials and finishes.

Process: The Assistant Interior Designer along with the APM and senior Interior Designer selects materials for the walls, floors, ceilings, furniture, fabrics, and accessories. For example, a designer working on a boutique may choose traditional Indian fabrics like silk or cotton for upholstery, paired with marble flooring. This phase may include product sourcing, obtaining samples, and reviewing vendor options.

Outcome: A finalized material list and product catalogue, including details on texture, colour, and type.

Detailed Design and Final Drawings

Objective: Create detailed drawings and technical specifications for contractors.

Process: The Assistant Interior Designer along with the APM and senior Interior Designer develops detailed drawings and provides specifications for furniture, lighting, flooring, and finishes. These drawings may include floor plans, elevations, lighting plans, and furniture layouts. While this phase may overlap with interior drafting, interior designing involves making decisions regarding the style, colours, and materials used, rather than just the technical dimensions.

Outcome: Clear, actionable documents that guide construction and installation.

Budgeting and Cost Estimation

Objective: Ensure the project remains within budget.

Process: The Assistant Interior Designer along with the APM and senior Interior Designer provides the client with a detailed cost estimate based on the materials, products, and furniture selected. The budget also accounts for labour costs, contractor fees, and any contingencies. This phase ensures that all design elements align with the client's financial expectations.

Outcome: A comprehensive cost breakdown for the entire project.

Contractor and Vendor Coordination

Objective: Oversee the procurement and installation process.

Process: The Assistant Interior Designer along with the APM and senior Interior Designer coordinates with contractors, vendors, and suppliers to ensure the correct materials are delivered on time. The Assistant Interior Designer along with the APM and senior Interior Designer may oversee the installation of furniture and fixtures, ensuring that everything aligns with the approved design.

Outcome: Smooth execution of the design, with proper materials and finishes being installed as planned.

Installation and Final Touches

Objective: Complete the physical transformation of the space.

Process: The installation of furniture, accessories, lighting fixtures, and decorative elements happens in this phase. Designers ensure that every aspect of the design is accurately implemented, with a final inspection of the space before handover.

Outcome: A fully furnished and functional space that aligns with the client's vision.

Handover and Client Walkthrough

Objective: Ensure client satisfaction.

Process: Once the space is completed, The Assistant Interior Designer along with the APM and senior Interior Designer conducts a final walkthrough with the client. This is the opportunity to make sure everything is in place, check the functionality of the space, and address any last-minute changes or concerns.

Outcome: Project sign-off, and the space is officially handed over to the client.

Post-Completion Support

Objective: Address any issues after project completion.

Process: In some cases, designers may offer post-completion services, such as adjustments, repairs, or re-arrangements. For example, in an apartment, if the client requests a minor change in furniture placement after living in the space for a few weeks, The APM may assist.

Outcome: Long-term client satisfaction and relationship maintenance.

While interior designing and interior drafting both play essential roles in transforming a space, they differ in their focus and purpose:

Focus	Creativity vs. Precision	Role in the Process
Interior Designing Focuses on the overall aesthetic, functionality, and mood of a space. Designers are responsible for selecting colour schemes, furniture, materials, and layouts to reflect the client's personality and needs.	**Interior Designing** Is a more creative process, involving the visualization and artistic arrangement of space. Designers consider furniture style, colour schemes, lighting, and accessories to create a unique and visually appealing environment.	**Interior Designing** Focuses on the overall aesthetic, functionality, and mood of a space. Designers are responsible for selecting colour schemes, furniture, materials, and layouts to reflect the client's personality and needs.
Interior Drafting Focuses on the technical aspects of the design. This includes creating precise floor plans, elevations, and sections that detail dimensions and construction requirements. It is the technical blueprint for the construction team.	**Interior Drafting** Is more technical and precise, focusing on the accurate representation of spatial dimensions, furniture placement, and structural components. Drafting provides the instructions necessary for construction.	**Interior Drafting** Takes the designer's concepts and translates them into detailed, scaled drawings that contractors and builders use to construct and implement the design.

Fig. 2.1.8:

The following the Checklist reflecting the differences between Interior Designing vs Interior Drafting:

Criteria	Interior Designing	Interior Drafting
Primary Focus	Creative & functional space planning	Technical drawings for execution
Nature of Work	Conceptual, aesthetic, user-experience driven	Precise, dimension-based, instruction-oriented
Tools & Software	SketchUp, Photoshop	AutoCAD (drafting mode)
Key Deliverables	Mood boards, layout concepts, 3D views, material board	Plans, elevations, sections, furniture details
Client Interaction	High – client-facing presentations and feedback	Low – supports internal team or consultants
Decision Making	Design decisions based on creativity and function	Drafts based on designer or architect instructions
Technical Accuracy	Moderate (visualization-oriented)	High (construction document-ready)
Understanding of Aesthetics	Essential	Supportive
Compliance Knowledge	Basic knowledge of codes & ergonomics	Strong understanding of building standards
Coordination With	Clients, contractors, consultants	Designers, architects, engineers
End Delivery	Delivering a complete design solution	Producing accurate drawings for implementation

Table 2.1.1:

2.1.2 Process Flow of an Interior Design Project

The process flow of an interior design project is systematic and involves several key phases that guide the project from initial consultation to the final handover. Each step is crucial to ensuring that the design vision is effectively executed while meeting client expectations, budget constraints, and timeline requirements.

Fig. 2.1.9: Process Flow of an Interior Designing Project

The detailed explanation of the process flow of an interior design project is given in the following section.

Initial Consultation with the Client

Objective: Understand client's needs, preferences, ls, and budget.

Process: The project begins with a meeting between The Assistant Interior Designer along with the APM and senior Interior Designer and the client. The APM discusses the purpose of the space (residential, commercial, hospitality), the client's aesthetic preferences, functional needs, lifestyle, and specific requirements. The APM also discusses the budget, timeline, and any limitations like building codes or structural constraints.

Outcome: The APM gets an understanding of the client's expectations, which forms the basis for all further decisions. A design brief is created at this stage.

Concept Development and Space Planning

Objective: Create an overall design concept and layout that fits the client's needs.

Process: The Assistant Interior Designer along with the APM and senior Interior Designer develops an initial design concept based on the client's preferences and the project's functional requirements. The design includes an initial space plan and visual concept that aligns with the client's.

For example, in a small apartment, the space plan may focus on maximizing every square foot by incorporating multifunctional furniture and an open-plan layout.

Mood boards and sketches are created to illustrate the design direction, such as colour schemes, material selections, and types of furnishings.

Outcome: A preliminary design concept is presented to the client for feedback. This step includes an initial layout and furniture arrangement plan.

Material and Product Selection

Objective: Select the materials, furniture, finishes, and accessories.

Process: Based on the approved design concept, The Assistant Interior Designer along with the APM and senior Interior Designer selects all materials required for the project. This may include flooring, paint colours, fabrics, countertops, and hardware.

The Assistant Interior Designer along with the APM and senior Interior Designer may source samples, visit suppliers, and present various options to the client for approval. Materials like locally sourced wood, marble, and traditional fabrics might be included to reflect the regional culture and style preferences. The Assistant Interior Designer along with the APM and senior Interior Designer also coordinates with furniture suppliers and vendors to ensure the quality and availability of items.

Design Development and Detailed Planning

Objective: Refine the design and make it more detailed.

Process: The design concept is refined based on the client's feedback from the initial presentation.

Designers provide detailed drawings of floor plans, elevations, and other design aspects, including materials and finishes. This stage also includes specifying custom furniture, lighting design, and placement of fixtures.

3D visualizations and renderings are created to give the client a realistic feel of how the space will look once completed. A project schedule is also established, which details the timeline for procurement, construction, and installation.

Outcome: A fully developed design that is presented to the client for approval. This includes a detailed floor plan, furniture layout, material finishes, and 3D visuals. The client may approve or request adjustments.

Procurement and Contractor Coordination

Objective: Acquire all materials and coordinate with the construction team.

Process: Once the design is approved, the procurement phase begins. The APM places orders for materials and furniture, ensuring that they are delivered on time and meet the required quality standards.

At this stage, The Assistant Interior Designer along with the APM and senior Interior Designer coordinates with contractors, electricians, plumbers, and other specialists to begin work on-site. Coordinating the various tradespeople is crucial, as contractors may have different work schedules, and site management can involve dealing with local regulations and guidelines.

Outcome: Materials are sourced, and work begins at the site. The Assistant Interior Designer along with the APM and senior Interior Designer ensures that the work is progressing according to the plan and that the contractors adhere to the design specifications.

Budgeting and Cost Estimation

Objective: Ensure the project is within financial constraints.

Process: The Assistant Interior Designer along with the APM and senior Interior Designer prepares a detailed cost estimate based on the material and product selection, contractor fees, and additional expenses.

The client is provided with a breakdown of costs, including materials, labour, furniture, decor, and other miscellaneous expenses. The Assistant Interior Designer along with the APM and senior Interior Designer may work with contractors and suppliers to get competitive quotes and ensure the project stays within the budget.

Outcome: A final cost estimate that aligns with the client's budget. If there are any discrepancies, The Assistant Interior Designer may need to adjust the scope or materials to remain within budget.

Construction and Installation

Objective: Implement the design and build the space.

Process: Construction work begins, including structural changes, painting, and installation of materials like flooring and walls. Furniture and fixtures are installed, including custom-designed pieces.

The APM regularly visits the site to ensure that the work is progressing as planned and that the design elements are being implemented correctly. Adjustments may be made on-site to address unexpected challenges. Electrical work, including lighting installation, and plumbing (if required) are carried out during this phase.

Outcome: The physical transformation of the space begins, with walls, floors, and ceilings being constructed and finished, followed by the installation of furniture and decor.

Final Touches and Styling

Objective: Add the finishing touches to complete the design.

Process: Once the primary construction and installations are complete, the Assistant Interior Designer along with APM and senior Interior Designer focuses on adding the finishing touches. This includes hanging artwork, arranging accessories, setting up furniture, adding soft furnishings like cushions and throws, and placing decorative items.

Designers sometime also work on the lighting effects, ensuring that the lighting is balanced to enhance the overall look and feel of the space.

Outcome: A fully furnished, functional, and aesthetically pleasing space, ready for client approval.

Handover and Client Walkthrough

Objective: Ensure client satisfaction and final sign-off.

Process: The APM conducts a final walkthrough with the client to inspect every detail of the project. Any issues or adjustments are discussed and addressed.

The client gives their final approval, and the project is handed over. Any final paperwork or documentation, such as warranties and maintenance guides, is provided to the client.

Outcome: The project is officially completed, and the space is handed over to the client. The APM ensures that all work is completed according to the agreed-upon specifications and that the client is happy with the result.

Post-Completion Support (Optional)

Objective: Address any remaining issues after the project is completed.

Process: After the space is handed over, the APM may provide post-completion support, which could include addressing minor changes, repairs, or re-arrangements.

In some cases, the APM might offer additional consultations to ensure the client is fully satisfied. Outcome: Ensures long-term client satisfaction and maintains a positive relationship for potential future projects.

2.1.3 Types of Interior Design Projects in Terms of Space, Theme, and Styles

Interior design projects can be categorized based on the space, theme, and style that defines the environment. Each type of project requires specific design principles, materials, and approaches to meet the unique needs of the space and the preferences of the client.

Types of Interior Design Projects by Space

Space refers to the type of environment or structure that is being designed. Different spaces have different functions and, therefore, require different design approaches to ensure the space is both functional and aesthetically pleasing.

Residential Projects - These projects are focused on designing homes, apartments, villas, and other residential spaces. The aim is to create a comfortable, functional, and personalised environment for the client and their family. The design is considered around family lifestyle, spatial planning, furniture selection, colour schemes, and functionality. In an apartment, an interior designer may create an open-plan living room that combines a kitchen, dining, and sitting area with modern furniture, using neutral tones to make the space feel larger.

Living cum Dining Room

Bed Room

Fig. 2.1.10: Residential Projects

Commercial Projects - Commercial interior design refers to the design of spaces used for business or public functions. These include offices, retail stores, , and shopping malls. The design is centred around branding, functionality, customer experience, and employee productivity. For a high-tech office, Assistant Interior Designer may create open workspaces with ergonomic furniture, modern lighting, and a contemporary design to boost creativity and collaboration among employees.

Worskstations



Conference Room

Fig. 2.1.11: Commercial Projects

Hospitality Projects - Hospitality projects involve designing spaces in hotels, resorts and spas restaurants. The focus is on providing a comfortable and aesthetically pleasing environment for guests while maintaining functionality for staff. The design is centred around comfort, ambience, durability, and alignment with the brand identity.

As part of hospitality industry restaurants and cafes are a growing business and often require comfortable and aesthetically pleasing environment.

Cafe

Reasturants

Fig. 2.1.12: Hospitality Projects

Healthcare Projects - This category includes designing spaces for healthcare facilities like hospitals, clinics, nursing homes, and wellness centres. The emphasis is on creating a healing, calm environment while ensuring the space is functional for medical staff and patients. The design is developed keeping parameters like hygiene, safety, accessibility, and patient comfort in mind. In a hospital in interior designers may use soothing colour palettes, comfortable waiting area seating, and efficient space planning to enhance patient comfort and staff workflow.



Clinic

Dental Clinic

Fig. 2.1.13: Healthcare Projects

Educational Projects - Educational interiors involve the design of schools, universities, training centres, and libraries. The design focuses on creating an engaging, functional, and educational environment. The key consideration while developing such designs should be flexibility, lighting, acoustics, and ergonomics. A modern classroom in a school might feature movable desks, vibrant colours, and wall-mounted interactive boards to encourage collaborative learning.



Montessori Classroom

School Library

Fig. 2.1.14: Educational Projects

Types of Interior Design Projects by Style

Style refers to the specific manner or approach in which the interior design is executed. Style dictates how the theme is translated into reality through the choice of materials, colours, and furniture.

Minimalist Style - The minimalist style embraces the “less is more” philosophy, focusing on simplicity, functionality, and clean lines. Design Characteristics: Neutral colours, simple forms, open spaces, and a lack of clutter. Example: In a small apartment, minimalist design may include sleek white walls, hidden storage solutions, and a few essential but elegant furniture pieces to create an airy and spacious feel.

Art Deco Style - Art Deco is a glamorous and bold design style from the 1920s, combining geometric shapes, rich colours, and luxurious materials.

The design characteristics of this style are bold, symmetrical patterns, metallic finishes, and the use of luxurious materials like marble, glass, and lacquered wood. Example: An art deco-style lobby in a high-end hotel might feature mirrored walls, geometric patterns in the flooring, and opulent lighting fixtures.

Scandinavian Style - Scandinavian design is characterized by simplicity, functionality, and a connection to nature. It is minimalistic but focuses on warmth and comfort.

The design characteristics of this style are light wood, neutral colours, clean lines, and a focus on functional furniture. Example: A Scandinavian-inspired living room in an apartment could include light wood furniture, white walls, and simple yet comfortable furniture pieces with a focus on natural light.

Mediterranean Style - Mediterranean style draws inspiration from countries like Greece, Italy, and Spain, featuring warm colours, textured walls, and a connection to the outdoors.

The design characteristics of this style are terracotta tiles, wrought iron furniture, natural stone, and vibrant colours like blue, green, and ochre. Example: A Mediterranean-style home in may feature terracotta flooring, wooden windows with arches, and sea-inspired colours for a calm, rustic feel.

Coastal Style - The coastal style reflects the laid-back, breezy atmosphere of beachside living. It incorporates light, airy elements with a focus on natural materials.

The design characteristics of this style are light woods, soft blues and whites, nautical elements, and the use of natural textures like linen and wicker. Example: A coastal-style home might have large windows that open up to the sea, whitewashed wooden furniture, and light fabrics like linen for a relaxed, beach-inspired ambiance.

2.1.4 Types of Advanced Raw Materials and Accessories Used in an Interior Design Project

In interior design, the selection of raw materials and accessories plays a critical role in determining the final look, feel, and functionality of the space. Advanced raw materials are modern, high-quality materials that enhance the durability, aesthetics, and sustainability of the design. Accessories, on the other hand, are used to add personality, elegance, and practical functionality to the space.

Raw Materials Used in Interior Design

Wood (Timber): Wood is one of the most versatile and timeless materials used in interior design. It can be used for flooring, furniture, panelling, cabinetry, and decorative elements.

Mahogany



Pine

Fig. 2.1.15:

Type	Applications	Advantages	Example
Teak	Furniture, doors, window frames, panelling	Water-resistant, durable, termite-resistant, high strength	Used in luxury home furniture and carved traditional doors
Oak	Flooring, cabinetry, furniture	Strong, resists warping, elegant grain patterns	Oak wood flooring in premium villas and cabinetry in modular kitchens
Mahogany	Furniture, decorative veneers, doors	Rich appearance, easy to polish, durable	Mahogany wood for antique-style beds and carved tables
Pine	Wall panelling, furniture, ceiling treatments	Lightweight, cost-effective, easy to work with	Pine used in Scandinavian-style interiors and cottage-themed décor
Engineered Wood	Flooring, modular furniture, cabinetry	Affordable, uniform, available in various finishes	MDF or HDF boards used in budget apartments for modular wardrobes
Bamboo	Flooring, blinds, furniture, partitions	Eco-friendly, fast-growing, strong tensile strength	Bamboo flooring in eco-resorts and dividers in sustainable office interiors

Table 2.1.2:

Stone: Natural stone such as marble, granite, and sandstone is used in interior design for its strength and elegance.

Type	Applications	Advantages	Example
Marble	Flooring, countertops, wall cladding, bathroom tiles	Luxurious, smooth finish, variety of colours	White marble in hotel lobbies and premium bathrooms
Granite	Kitchen countertops, stairs, floors	Scratch-resistant, durable, stain-resistant	Black granite used in modular kitchens and office staircases
Limestone	Flooring, wall cladding, garden paving	Soft tone, natural finish, good insulation	Used in boutique cafés for earthy-themed flooring
Sandstone	Wall cladding, outdoor paving, garden walls	Textured, natural colour variations, affordable	Widely used in Rajasthani homes for exterior wall treatments
Slate	Roof tiles, flooring, bathroom walls	Slip-resistant, earthy tones, low maintenance	Slate tiles used in rustic resorts and spa bathrooms
Quartz	Kitchen countertops, vanity tops, wall panels	Non-porous, low maintenance, consistent colours	Quartz countertops in contemporary apartments for stain-free kitchens

Table 2.1.3:



Marble

Sandstone

Fig. 2.1.16:

Glass: Glass is a versatile material used for creating modern and open spaces. It's used for windows, partitions, balustrades, and even furniture.



Stained glass

Glass window

Fig. 2.1.17:

Type of Glass	Description	Common Uses	Advantages
Tempered Glass	Heat-treated for extra strength and safety.	Shower enclosures, doors, partitions.	Shatter-resistant, safe, durable.
Laminated Glass	Made by sandwiching a layer of plastic between glass sheets.	Windows, skylights, balconies.	UV-resistant, holds together when broken.
Frosted Glass	Glass treated with acid or sandblasting for opacity.	Bathroom windows, partitions, cabinet doors.	Provides privacy, allows light.
Tinted Glass	Glass with color additives to reduce glare and heat.	Facades, windows, skylights.	Heat reduction, aesthetic appeal.
Mirror Glass	Glass with a reflective metallic coating.	Wardrobes, vanity units, wall decor.	Creates illusion of space, enhances lighting.
Textured/ Patterned Glass	Glass with embossed designs for visual and tactile appeal.	Cabinet doors, partitions, decorative panels.	Decorative, diffuses light, offers privacy.

Table 2.1.4:

Metals: Metals like stainless steel, brass, aluminium, and copper are commonly used in interior design for structural, decorative, and functional purposes.

Stainless steel Lights

Copper Handles

Fig. 2.1.18:

Type of Metal	Description	Common Uses	Advantages
Stainless Steel	Corrosion-resistant alloy with a sleek, polished look.	Railings, kitchen counters, fixtures.	Durable, rust-proof, modern finish.
Aluminium	Lightweight, corrosion-resistant metal.	Window frames, door frames, partitions.	Lightweight, weather-resistant, recyclable.
Brass	Alloy of copper and zinc with a golden finish.	Handles, light fixtures, décor accents.	Aesthetic, antimicrobial, durable.
Copper	Reddish metal with a natural patina over time.	Kitchen sinks, lighting, accents.	Malleable, antimicrobial, warm appearance.
Wrought Iron	Iron worked by hand into decorative forms.	Railings, gates, vintage-style furniture.	Strong, traditional charm, customizable.

Table 2.1.5:

Fabrics: Fabrics are essential in adding comfort, texture, and warmth to a space. They are used for upholstery, curtains, rugs, and other decorative accessories.

Velvet



Cotton

Fig. 2.1.19:

Type of Fabric	Description	Common Uses	Advantages
Cotton	Natural fiber known for softness and breathability.	Upholstery, curtains, cushions.	Comfortable, breathable, easy to dye.
Linen	Natural fiber with a crisp, textured look.	Drapery, upholstery, cushions.	Eco-friendly, cooling, elegant look.
Velvet	Rich, soft fabric with a luxurious sheen.	Sofas, accent chairs, curtains.	Luxurious feel, vibrant colors.
Leather (Natural/ Synthetic)	Durable and elegant material made from animal hides or PU.	Sofas, chairs, headboards.	Long-lasting, classic, easy to clean (faux leather too).
Polyester	Synthetic fabric used for durability and affordability.	Blinds, curtains, upholstery.	Wrinkle-resistant, colorfast, economical.

Table 2.1.6:

Concrete: Concrete is a strong and durable material used for modern, industrial designs. It can be polished for a sleek look or left in its raw state for a more industrial feel.

Type of Concrete	Description	Common Uses	Advantages
Polished Concrete	Smooth, glossy finish achieved by grinding concrete surface.	Flooring, countertops, accent walls.	Low maintenance, modern look, durable.
Exposed Aggregate Concrete	Surface where aggregates (stones, pebbles) are visible.	Driveways, patios, statement walls.	Textured, slip-resistant, decorative.
Precast Concrete	Concrete cast in reusable molds off-site and assembled later.	Wall panels, facades, modular furniture.	Consistent quality, quick installation.
GFRC (Glass Fiber Reinforced Concrete)	Lightweight composite reinforced with glass fibers.	Sculptures, cladding, sinks.	Strong, moldable, weather-resistant.
Stamped Concrete	Concrete that is patterned or textured to mimic other materials like stone or wood.	Floors, outdoor pathways.	Aesthetic flexibility, cost-effective alternative.

Table 2.1.7:

Other Materials

The following lists the other advanced material used in interior design projects:

Material	Description	Common Uses	Advantages
Acrylic Sheets	Lightweight plastic with a glass-like appearance.	Signage, tabletops, display units.	Shatter-resistant, easy to cut, UV-resistant.
PVC Panels	Polyvinyl chloride sheets used as decorative wall or ceiling panels.	Wall cladding, ceilings, bathrooms.	Water-resistant, lightweight, low-maintenance.
MDF (Medium Density Fibreboard)	Engineered wood made from wood fibers and resin.	Cabinets, wall panels, furniture.	Smooth surface, cost-effective, easy to shape.
HPL (High-Pressure Laminate)	Decorative laminate applied to surfaces.	Countertops, cabinets, wardrobes.	Scratch-resistant, heat-resistant, wide design range.
Corian (Solid Surface)	Composite material made of acrylic and natural minerals.	Kitchen counters, sinks, seamless surfaces.	Non-porous, repairable, seamless finish.
Glass Fiber Reinforced Concrete (GFRC)	Composite material of cement and glass fibers.	Wall panels, sculptures, facade cladding.	Lightweight, strong, moldable into shapes.

Table 2.1.8:

Accessories Used in Interior Design

Lighting Fixtures

Type of Fixture and Mounting Style	Mounting Style - Image	Description	Common Applications	Advantages
Chandeliers - Ceiling-mounted (suspended)		Ornate lighting with multiple light bulbs, often a centrepiece.	Dining rooms, foyers, large living rooms.	Decorative, focal point, ambient lighting.

Pendant Lights - Ceiling-mounted (hanging)		Single-bulb lights suspended by a cord or chain.	Kitchens (over islands), bedrooms, dining spaces.	Focused lighting, modern aesthetic, space-saving.
Wall Sconces - Surface-mounted (wall)		Wall-mounted lights used for accent or task lighting.	Hallways, bathrooms, bedroom headboards.	Space-saving, decorative, task lighting.
Floor Lamps - Freestanding		Tall, movable lamps that stand on the floor.	Living rooms, reading corners, bedrooms.	Portable, focused lighting, flexible placement.
Recessed Lighting - Flush-mounted (ceiling)		Lights installed into a hollow opening in the ceiling.	Kitchens, hallways, modern commercial spaces.	Minimalist look, broad coverage, space-saving.
Track Lighting - Surface-mounted (ceiling/wall)		Adjustable lights attached to a continuous track system.	Galleries, kitchens, studios.	Flexible direction, sleek design, good for focused lighting.
LED Strip Lights - Surface-mounted (versatile)		Flexible LED strips adhered to surfaces, often hidden in grooves.	Under cabinets, staircases, cove lighting.	Energy-efficient, customizable, modern.

Ceiling Flush Mounts - Flush-mounted (ceiling)		Lights that are mounted flush against the ceiling surface.	Bathrooms, corridors, utility areas.	Space-efficient, bright general lighting.
Semi-Flush Mount Lights - Semi-flush (ceiling)		Slightly extend below ceiling, offering a bit of style without hanging low.	Bedrooms, dining rooms, entryways.	Decorative, suitable for low ceilings.

Table 2.1.9:

Wall Art and Decorative Items

Wall art refers to any artistic item or decoration that is applied, hung, or mounted on interior walls to enhance the aesthetics, theme, and emotional appeal of a space. It plays a vital role in completing a room's design, reflecting the owner's personality, and creating visual interest or a focal point.

Some common and impactful types of wall art used across traditional, modern, and eclectic interiors are:

Paintings

Type of Painting	Example	Description	Common Style/ Examples	Used In
Abstract		Non-representational, focuses on shapes and colors.	Geometric, expressive, free-form	Modern homes, offices

Realism/ Naturalism		Represents real-life scenes in lifelike detail.	Portraits, still life, landscapes	Classic interiors, formal rooms
Folk/Tribal Art		Traditional and cultural art forms rooted in Indian heritage.	Warli, Madhubani, Tanjore, Pattachitra	Ethnic homes, hallways, niche spaces
Portraits		Depictions of individuals, stylized or realistic.	Royal portraits, modern silhouettes	Bedrooms, gallery walls, lounges
Modern/ Minimalist Art		Clean, simple compositions with minimal details.	Line art, monochromes, color blocks	Scandinavian, contem-porary settings

Religious/ Spiritual Art		Sacred or devotional paintings.	Tanjore paintings, Buddha art	Puja rooms, meditation spaces
Mixed Media		Combines paint with materials like thread, wood, or paper.	Textured art, collages	Art galleries, statement walls
Calligraphy/ Typography		Uses stylized text, letters, or quotes as the main design.	Inspirational quotes, Sanskrit shlokas	Entryways, workspaces, kitchens

Table 2.1.10:

Murals

Murals are large-scale artworks that are either hand-painted or printed directly onto walls, making them an integral part of the interior space. These artworks are often used to create dramatic visual impact and to reflect cultural, natural, or thematic elements within a room.

Murals can depict a variety of styles, including nature-inspired scenes such as landscapes or forests, religious themes showcasing deities or spiritual symbols, and bold, urban street art styles that bring an edgy, contemporary vibe. They are commonly featured in prominent areas like hotel lobbies, restaurants, children's rooms, or as statement accent walls in homes or offices, adding character and storytelling to the environment.



Fig. 2.1.20:

Wall Decals and Stickers

Wall decals and stickers are pre-designed vinyl graphics that can be easily applied to and removed from walls without causing damage. They offer a flexible and affordable way to personalize spaces without the permanence of paint or wallpaper. Available in a variety of styles, such as inspirational quotes, floral motifs, and cartoon characters, these decals cater to diverse aesthetic preferences. They are especially popular in children's rooms where easy installation and removability are important. Wall decals are a quick and creative solution to enhance visual appeal with minimal effort.

Fig. 2.1.21:

Sculptural Wall Art (3D Art)

Sculptural wall art, also known as 3D wall art, refers to three-dimensional decorative pieces or panels that are mounted directly on interior walls. Unlike flat paintings or prints, these artworks physically protrude from the wall, creating a sense of depth and dimension. They are typically crafted from materials such as wood, resin, metal, or ceramic, offering a variety of textures and finishes. Commonly used on feature walls or within niches, sculptural wall art enhances the visual interest of a space, making it more dynamic and expressive. It serves both an aesthetic and architectural function, blending art with spatial design.

Fig. 2.1.22:

Textile and Tapestry Art

Textile and tapestry art refers to decorative fabric pieces that are woven, embroidered, or printed and displayed as wall hangings. These artworks not only serve as visual accents but also bring a tactile, soft quality to the room. Styles range from tribal patterns and traditional Indian crafts like Kalamkari, Kantha, or Phulkari, to modern and abstract weaves that suit contemporary interiors. Often used in bedrooms, living rooms, or lounge areas, textile art adds warmth, cultural depth, and a handcrafted appeal to the space while also contributing to acoustic comfort.

Fig. 2.1.23:

Mirrors as Wall Art

Mirrors as wall art serve a dual purpose in interior design by combining functionality with aesthetic appeal. These mirrors are often crafted with artistic frames—ranging from ornate and vintage to abstract or modern sunburst designs—that make them standout decorative elements. Apart from reflecting beauty, they play a strategic role in enhancing natural light and creating the illusion of a larger space. This makes them a popular choice in foyers, hallways, and living areas where brightness and spaciousness are desired. Mirrors as art not only add elegance but also bring balance and symmetry to a room's overall design.

Fig. 2.1.24:

Photographic Prints or Posters

Photographic prints or posters are a popular and budget-friendly form of wall art, consisting of enlarged photographs or digital images that are framed or mounted directly onto walls. These prints come in a wide variety of themes, including travel destinations, urban cityscapes, natural landscapes, and portraits of cultural icons. Their visual clarity and emotional relatability make them especially suitable for modern homes, youth bedrooms, cafés, and creative office spaces. Easy to update and rearrange, photographic posters offer a quick way to reflect personality, interests, or seasonal moods without permanent changes to the décor.

Fig. 2.1.25:

Graffiti / Street-Style Wall Art

Graffiti or street-style wall art is a bold and expressive form of artwork often created using spray paint, stencils, or markers. Known for its vibrant colours, raw energy, and urban aesthetic, this type of art emerged from street culture and now finds a place in interior design, particularly in spaces seeking a youthful, edgy, or industrial vibe. It often features abstract forms, typography, or socially relevant themes, making it a dynamic and conversation-starting addition. Commonly used in start-up offices, gaming lounges, creative studios, or art cafés, graffiti wall art brings an element of rebellion, individuality, and cultural flair to modern interiors.

Fig. 2.1.26:

Decorative Wall Panels

Decorative wall panels are architectural surface treatments designed to enhance the aesthetics of a wall while also serving as a durable covering. These panels come in a wide range of textures, patterns, and finishes and are used to create accent walls, add dimension, or replicate the look of materials like wood, stone, leather, or metal.

Types of Decorative Wall Panels:

Type of Painting	Example	Description	Common Style/ Examples	Used In
3D Wall Panels		Feature raised textures and geometric patterns for visual depth.	PVC, MDF, gypsum	Feature walls, TV backdrops, hotel lobbies

Wood Panels		Offer warmth and texture, available in planks or slats.	Teak, plywood, veneer	Bedrooms, living rooms, offices
PVC Panels		Lightweight, water-resistant, and easy to install.	PVC plastic	Bathrooms, kitchens, commercial areas
Fabric/ Leatherette Panels		Soft-touch panels often used for luxury and acoustic control.	PU leather, fabric over foam	Headboards, theatres, boardrooms
Metallic Panels		Glossy or brushed metal surfaces used for a modern or industrial look.	Aluminium, steel, copper	Kitchens, high-end commercial interiors

Stone/Brick Veneer Panels		Replicate real stone or exposed brick aesthetics without the weight.	PU composites, ceramic	Rustic spaces, cafes, accent walls
Gypsum CNC Cut Panels		Custom laser-cut patterns on gypsum boards for modern 3D visuals.	Gypsum	Living room, temple niches, feature walls

Table 2.1.11:

Wall Clocks and Decorative Plates

Description: Functional items presented with aesthetic value.

Usage: Adds character to kitchens, hallways, and balconies.

Fig. 2.1.27:

Rugs and Carpets

Description: Rugs and carpets add warmth, comfort, and texture to a space. They can also define areas in open-plan layouts.
Types: Wool, Silk, Jute, Synthetic, Shaggy, Persian Rugs.
Applications: Living rooms, bedrooms, entryways, and offices.
Advantages: Comfort, insulation, and aesthetic value.
Example: A silk rug in a luxury living room or a jute rug in an eco-friendly home in .

Fig. 2.1.28:

Fig. 2.1.29:

Furniture Accessories (Cushions, Throws, etc.)

These are small accessories such as cushions, throws, and bed linens enhance the comfort and look of a room.

Types: Cushions, Throws, Bed Linen, Decorative Pillows, Table Linens.

Applications: Sofas, beds, chairs, and dining areas.

Advantages: Comfort, texture, and easy to update with changing trends.

Colourful cushions in an apartment with a contemporary theme or woven throws in a home with a traditional aesthetic.

Cushions

Bed linens

Fig. 2.1.30:

Curtains and Drapes

Curtains and drapes are functional elements that add privacy, regulate light, and contribute to the overall design of a space.

Types: Sheer Curtains, Heavy Drapes, Roman Blinds, Venetian Blinds.

Applications: Windows, doorways, and partitions.

Advantages: Privacy, light control, and decorative appeal.

Heavy velvet drapes in a palace-style living room or light cotton curtains in a coastal home to let in natural light.

Fig. 2.1.31:

Flooring Accessories

Flooring accessories refer to add-on elements that enhance the functionality, safety, and aesthetics of floors. These include mats, rugs, carpets, skirting, underlays, stair treads, floor cushions, and threshold strips that complete the flooring design and improve user comfort.

Common Flooring Accessories with Sizes:

Accessory	Image	Description	Common Sizes (India)	Application Areas
Door Mats		Used to wipe dirt and moisture at entry points.	40×60 cm, 45×75 cm, 60×90 cm	Entryways, kitchen entrances, bathrooms

Area Rugs/ Carpets		Decorative fabric floor coverings that also insulate.	4x6 ft, 5x7 ft, 6x9 ft, 8x10 ft, 9x12 ft	Living rooms, dining areas, bedrooms
Anti-Skid Mats		Mats with rubber or textured base for slip resistance.	40×60 cm, 45×120 cm, 60×90 cm	Bathrooms, kitchens, staircases
Vinyl Floor Mats		Thin, decorative mats with printed surfaces for easy cleaning.	2x3 ft, 3x5 ft, 4x6 ft	Kitchen, kids' rooms, under dining tables
Foam Mats (EVA or Interlocking)		Soft, interlocking mats often used in children's play zones.	30×30 cm, 60×60 cm tiles (can be combined)	Playrooms, yoga zones, gyms

Stair Treads		Mats for each stair step, with adhesive or hooks.	60×20 cm, 65×25 cm (depends on stair size)	Residential/
Floor Cushions (Gaddis)		Large, thick cushions for informal seating.	60×60 cm, 75×75 cm, round – 24" diameter	Living rooms, study nooks, kids' areas
Skirting/Wall Beading		Decorative strip between floor and wall to hide joints.	Height: 2 to 4 inches, Length: 8 to 10 feet strips	All rooms – corners, baseboards
Threshold Strips		Divider between two flooring types or room transitions.	1.5", 2" width, 3 ft or 6 ft length	Room transitions, bathroom edges, balconies

Underlay/ Padding		Layer under carpets/mats for cushioning and sound-proofing.	Rolls or sheets – thickness: 6 mm to 12 mm	Below carpets in bedrooms or lounges

Table 2.1.12:

The different types of floor tiles are:

Tile Type	Image	Description	Applications	Common Sizes (mm)
Ceramic Tiles		Made from natural clay, glazed for durability. Affordable, colorful, and versatile.	Kitchens, bathrooms, living rooms, balconies	300x300, 600x600, 300x600
Porcelain Tiles		Denser and stronger than ceramic; water-resistant and ideal for high-traffic areas.	Living rooms, commercial spaces, outdoor patios	600x600, 800x800, 600x1200, 300x600
Vitrified Tiles		Porcelain tiles with low porosity, sleek and glossy finish.	Bedrooms, living rooms, office floors	600x600, 800x800, 600x1200

Marble Tiles		Natural stone with unique veining; elegant but needs maintenance.	Luxury interiors, bathrooms, living rooms	300x300, 600x600, custom slab sizes (e.g., 900x900)
Granite Tiles		Durable, granular natural stone; stain and scratch-resistant.	Kitchen flooring, staircases, hallways, terrace	300x300, 600x600, 300x600
Mosaic Tiles		Decorative small chips arranged on mesh sheets.	Accent walls, bathrooms, backsplashes	Typically 300x300 sheets
Cement Tiles		Handmade with artistic patterns; eco-friendly and vibrant.	Living rooms, entryways, feature floors	200x200, 300x300

Terracotta Tiles		Unglazed red clay tiles with a rustic look.	Verandas, courtyards, rustic interiors	200x200, 300x300
Wooden Finish Tiles		Porcelain/ vitrified tiles mimicking wood grain.	Bedrooms, hallways, resorts	145x600, 195x1200
Quartz Tiles		Engineered from quartz and resin; glossy and non-porous.	Commercial spaces, hotel lobbies	600x600, 600x1200

Table 2.1.13:

2.1.5 Categories of Advanced Architectural Hardware and Fittings

Architectural hardware comprises various fittings and fixtures that enhance the functionality, aesthetics, durability, and safety of interior and exterior spaces. These components serve both structural and decorative purposes in design projects. Below is an enhanced table outlining advanced categories, typical fittings, usage, materials, and unique features such as weatherproofing, warranties, and soundproofing (if applicable).

Category	Hardware / Fitting	Usage in Interior Design	Common Materials	Key Features & Benefits
Door Hardware	Handles, Locks, Hinges	Functional operation, safety, and security of entry and interior doors.	Brass, SS, Aluminium, Zinc	Weather-resistant, stylish, corrosion-proof, warranties up to 10 years.
	Door Closers, Latches	Controls the closing speed, ensures soft closing, and reduces door damage.	SS, Aluminium	Enhances user safety, fire-rated options available.
	Magnetic Door Stops, Bolts	Prevents wall damage and securely holds doors open or shut.	Brass, SS	Low maintenance, shock-absorbent, modern designs.
Window Hardware	Handles, Latches, Stay Arms	Ease of opening/ closing windows; important for ventilation and light.	Aluminium, SS, Brass	Smooth motion, rust-proof, long-life guarantee.
	Window Locks, Hinges	Secures windows against intrusion and weather.	Zinc Alloy, Aluminium, SS	Enhanced security, available in child-safe variants.
Furniture Hardware	Cabinet Handles, Drawer Pulls	For easy access and decorative touch to storage units.	Wood, Brass, SS, Aluminium	Ergonomic designs, anti-corrosive, wide finishes (chrome, matte, brushed).
	Hinges, Locks, Magnetic Latches	Facilitates movement of drawers, cabinets, and modular units.	Brass, SS, Nickel	Soft-close, silent operation, concealed hinges for premium finish.
Kitchen Hardware	Faucets, Sink Fittings	Ensures efficient water flow and hygiene in kitchen areas.	Brass, SS, Copper	Rust-proof, hot/ cold mixer, up to 15 years warranty.
	Pull-out Shelves, Pantry Systems	Enhances kitchen storage and accessibility.	SS, Wood, Aluminium	Space-saving, customizable, smooth gliding mechanisms.

Bathroom Fittings	Showerheads, Towel Bars, Floor Mesh	Plumbing and accessories for daily hygiene needs.	Chrome, SS, Brass	Anti-corrosive, water-saving, sleek aesthetic.
	Mirrors, Vanity Cabinets, Soap Dispensers	Improves storage and reflection in compact spaces.	Aluminium, Glass, SS	Fog-resistant mirrors, LED backlit, warranty options available.
Lighting Fixtures	Ceiling Lights, Pendants, Spotlights	Provides ambient, task, or accent lighting.	Metal, Glass, Crystal, Acrylic	Energy-efficient (LED), dimmable, UL certified, modern aesthetics.
	Wall Sconces, Cove Lighting	Adds ambient mood and space-saving lighting on walls.	SS, Aluminium, Glass	Low-heat emission, compact, enhances mood lighting.
Flooring Hardware	Skirting, Baseboards, Edging Profiles	Finishes flooring edges for a neat look and protects from damage.	MDF, Wood, PVC, Aluminium	Waterproof options, termite-resistant, concealed cable passage.
	Floor Trims, Thresholds	Transition between different floors or rooms.	Aluminium, Brass, SS	Seamless transitions, anti-slip, acoustic buffering.
Wall & Ceiling Fittings	Curtain Rods, Tracks, Brackets	Functional and aesthetic finish for drapes and curtains.	SS, Brass, Aluminium	Easy installation, extendable, corrosion-proof.
	Ceiling Fans, Vent Grills	Maintains air circulation, ventilation, and thermal comfort.	SS, Aluminium	Energy-efficient, silent operation, smart control compatible.
Structural Fittings	Railings, Balusters, Cable Systems	Provides safety and support in staircases and balconies.	Glass, SS, Wrought Iron, Wood	Tempered glass options, child-safe designs, warranties for external fittings.
	Handrails, Wall Grips, Stair Fittings	Offers grip and safety for movement in homes and public spaces.	SS, Wood, Rubberized Coatings	Ergonomic, anti-slip, weatherproof variants for outdoor use.

Table 2.1.14: Categories of Advanced Architectural Hardware and Fittings

Selecting the right architectural hardware is crucial for both functionality and aesthetic appeal in an interior design project. Architectural hardware refers to the components used for the construction and finishing of doors, windows, cabinets, flooring, and other structural elements. The type of application determines the choice of hardware, based on factors like design style, durability, function, material compatibility, and environmental conditions.

Let us understand how to select architectural hardware according to the type of application.

- **Door Hardware**
  - **Application Type:** Residential, Commercial, Hospitality
  - **Factors to Consider:**
    - **Material:** Choose stainless steel or brass for modern or high-end residences, and aluminium or mild steel for commercial spaces.
    - **Security:** For commercial or public spaces like offices and hotels, high-security locks and electronic access control systems are necessary.
    - **Aesthetic:** For residential designs, decorative handles made of wood or brass may be preferred, while sleek, minimalist handles are commonly used in modern office interiors.
    - **Durability:** For areas like bathrooms or kitchens, choose hardware with corrosion resistance, such as stainless steel or chrome.

Example:

- **Residential Project:** In a luxury home in, use brass or polished chrome door handles for a sophisticated look.

Fig. 2.1.32:

- **Commercial Project:** In a corporate office, choose stainless steel handles and digital locks for both security and a contemporary design.

Fig. 2.1.33:

- **Hospitality Project:** In a premium hotel suite, use antique bronze or matte black door hardware with intricate detailing to enhance the heritage-inspired interior design while ensuring durability and a luxurious guest experience.

Fig. 2.1.34:

- **Furniture Hardware**
  - **Application Type:** Residential, Commercial, Hospitality
  - Factors to Consider:
    - **Style:** Wooden furniture handles, glass pulls, and antique-style knobs suit traditional designs, while sleek metal handles work well for modern or minimalist interiors.
    - **Durability:** For heavy-duty furniture in offices or hotels, use stainless steel or brass for handles and locks to withstand frequent use.
    - **Ease of Use:** Ergonomically designed pulls are ideal for kitchen cabinets, while recessed handles work well in modern living room furniture.x

Example:

- **Residential Project:** In a luxury villa, use polished brass or silver-finish handles for wooden wardrobes to add elegance.

Fig. 2.1.35:

- **Commercial Project:** For a retail store, use stainless steel drawer pulls for functionality and modern appeal.

Fig. 2.1.36:

- **Kitchen and Bathroom Hardware**
  - **Application Type:** Residential, Commercial (Restaurants, Hotels)
  - **Factors to Consider:**
    - **Water Resistance:** Opt for stainless steel or brass for faucets, taps, and shower fittings in kitchens and bathrooms due to their resistance to moisture and corrosion.
    - **Functionality:** In commercial kitchens or hotels, high-performance faucets, sink accessories, and water-saving fixtures are essential for long-term durability and sustainability.
    - **Design:** For residential kitchens, sleek, modern faucets and minimalist drawer pulls are often chosen for a contemporary look.

Example:

- **Residential Project:** In an apartment, use brushed stainless steel faucets for a modern kitchen with minimalist aesthetics.

Fig. 2.1.37:

- **Commercial Project:** In a five-star hotel , choose brass or chrome-plated shower fittings for the bathrooms to add luxury while ensuring long-term durability.

Fig. 2.1.38:

- **Lighting Fixtures**
  - **Application Type:** Residential, Commercial, Hospitality
  - **Factors to Consider:**
    - **Brightness & Ambiance:** Choose LED lighting for energy efficiency in residential spaces, and suspended pendant lights for dramatic effect in commercial spaces like restaurants.
    - **Material:** Glass, crystal, and metal are commonly used for chandeliers and pendant lights in luxury and hospitality designs.
    - **Energy Efficiency:** For offices or eco-friendly homes, energy-efficient LED lights or motion-sensor lights are ideal.

Example:

- **Residential Project:** In an apartment, opt for recessed lighting and pendant lights with brushed steel finishes for a modern look.

Fig. 2.1.39:

- **Commercial Project:** In a hotel , use luxury crystal chandeliers to enhance the ambiance of the lobby.

Fig. 2.1.40:

- **Flooring and Wall Fittings**
  - **Application Type:** Residential, Commercial, Hospitality
  - **Factors to Consider:**
    - **Durability:** Choose ceramic or porcelain tiles for high-traffic areas such as kitchens and bathrooms, while wooden flooring works best in living rooms and bedrooms.
    - **Style:** Polished marble or granite is ideal for luxury hotels, while vinyl or engineered wood is more practical for residential spaces and commercial offices.
    - **Aesthetic:** Wall-mounted shelving and floating desks are ideal for modern office interiors.

Example:

- **Residential Project:** In a home, marble tiles with brass inlay in the hallway give a luxury feel to the space.

Fig. 2.1.41:

- **Commercial Project:** For a restaurant, use porcelain tiles for the flooring due to their easy maintenance and resistance to high foot traffic.

Fig. 2.1.42:

- **Structural Fittings (Railings, Balusters, etc.)**
  - **Application Type:** Residential, Commercial, Hospitality
  - **Factors to Consider:**
    - **Material:** Glass railings and metal balusters are ideal for a modern or industrial look, while wooden railings are suited for traditional or rustic designs.
    - **Safety:** Ensure the use of strong materials like stainless steel or tempered glass for handrails and balusters in staircases and balconies to meet safety standards.
    - **Aesthetic:** Wrought iron is often used for traditional themes, while tempered glass provides an elegant touch for modern spaces.

Example:

- **Residential Project:** In a luxury villa, wooden balusters with intricate carvings are used for staircases.

Fig. 2.1.43:

- **Commercial Project:** For a hotel, glass railings and stainless-steel handrails are used for modern aesthetics and safety.

Fig. 2.1.44:

Unit 2.2: Furniture Trends and Interior Projects

Unit Objectives

At the end of this unit, the participants will be able to:

1. List the different types of furniture and their area of applications.
2. Outline the latest trends and advancements related to the interior designing process.
3. Define the role of effective communication skills required for Interior Designer

2.2.1 Different Types of Furniture and their Area of Applications

Furniture is an essential element in interior design, offering both functionality and aesthetic value. The right furniture can enhance the usability and comfort of a space while reflecting the overall design style. Furniture comes in various types, each designed for specific purposes and applications.

The different types of furniture and their area of applications are discussed in the following section.

Seating Furniture

- **Sofas and Couches**

Fig. 2.2.1:

Sofas and couches are large, upholstered seating furniture pieces used in living rooms, lounges, and waiting areas.

Applications:

- **Living Rooms:** Sofas and sectionals provide seating for families and guests. In urban homes, sectional sofas are often used for flexibility in arranging seating in smaller spaces.
- **Commercial Spaces:** In hotels, lobbies and lounges, sofas provide a comfortable seating option for guests.

  Example: In an apartment, a modern sectional sofa in a neutral tone creates a relaxed and inviting atmosphere in the living room.

- **Armchairs and Lounge Chairs**

Fig. 2.2.2:

Smaller than sofas, armchairs and lounge chairs offer personal, comfortable seating. They often feature padded arms and are used for relaxation.

Applications:

- **Living Rooms:** Used alongside sofas to create cozy reading or lounging spaces.
- **Offices:** Lounge chairs are often placed in reception areas or break rooms to create comfortable, informal settings.

Example: In an office, a set of lounge chairs can be placed in the waiting area to create a professional yet welcoming environment.

- **Recliners**

Fig. 2.2.3:

Recliners are chairs designed to recline, allowing users to adjust the seating position for relaxation.

Applications:

- **Living Rooms:** Popular for creating a relaxing corner in homes, especially for watching TV or reading.
- **Commercial Spaces:** Reclining chairs are often used in VIP lounges or cinema halls for ultimate comfort.

Example: In a home, a leather recliner might be placed in the living room for a comfortable seating experience.

Storage Furniture

- **Cabinets and Cupboards**

Fig. 2.2.4:

Cabinets are storage units with enclosed compartments and doors, often used for storing clothes, books, and household items. Cupboards are smaller units and often movable piece of furniture.

Fig. 2.2.5:

Applications:

- **Bedrooms:** Wardrobes and cabinets store clothes, accessories, and personal belongings.
- **Living Rooms:** Display cabinets are used to showcase collectibles, books, or media equipment.

Example: A wooden wardrobe in a Kerala home provides both storage and an elegant traditional touch to the room.

- **Shelving Units**

Fig. 2.2.6:

Shelving units are open storage spaces with horizontal surfaces for displaying or storing items.

Applications:

- **Living Rooms:** Used to display books, photo frames, or decorative items.
- **Offices:** Shelves are commonly used to store books, files, and supplies.

Example: A floating bookshelf in a apartment adds a modern touch while keeping the space organized and clutter-free.

- **Sideboards and Buffets**

Fig. 2.2.7:

Sideboards and buffets are low, long furniture pieces typically used in dining rooms or living rooms for storage and serving.

Applications:

- **Dining Rooms:** Used to store dinnerware, serving pieces, and table linens.

- **Living Rooms:** Provides extra storage space for decorative items or media equipment.

Example: A modern sideboard in a dining room can hold fine china and cutlery, complementing the design of the space.

Bedroom Furniture

- **Beds**

Fig. 2.2.8:

Beds are the central piece of furniture in the bedroom, varying in size from single beds to king-size. These are used as the primary sleeping area in bedrooms, with options like storage beds, platform beds, and canopy beds for different design styles.

Example: In a luxury bedroom , a king-size bed with a wooden frame and elegant bedding adds a sophisticated touch to the space.

- **Nightstands**

Fig. 2.2.9:

Nightstands or bedside tables are small, convenient tables placed beside the bed for storing essentials like lamps, clocks, or books.

Applications:

- **Bedrooms:** Positioned next to the bed for practical storage of nighttime essentials.
- **Guest Rooms:** Nightstands are often included in guest rooms for convenience and added comfort.

Example: In a hotel room, a classic wooden nightstand with drawers provides guests with a functional and elegant solution.

- **Dressers and Vanities**

Fig. 2.2.10:

Dressers are tall, multi-drawer pieces of furniture used for storing clothes, while vanities typically feature a mirror and drawers for beauty or grooming items.

Applications:

- **Bedrooms:** Used for clothing storage and adding decorative flair to the room.
- **Master Bedrooms:** Large dressers with full-length mirrors add both functionality and style.

Example: In an Indian colonial-style bedroom, a wooden dresser with a mirror is used for both functional storage and as a decorative piece.

Dining Room Furniture

- **Dining Tables and Chairs**

Fig. 2.2.11:

Dining tables serve as the central piece of furniture in the dining room, with accompanying chairs for seating.

Applications:

- **Residential Dining Rooms:** Dining tables come in various sizes, often designed with wood, glass, or marble tops.

- **Restaurants:** Commercial dining tables and chairs are designed for durability and ease of maintenance.

Example: In a luxury home in , a marble dining table with elegant chairs becomes the focal point of the dining room.

- **Bar Carts**

Fig. 2.2.12:

Bar carts are mobile furniture pieces used for storing and serving drinks, while buffets are longer, storage-based units often placed in the dining area.

Applications:

- **Dining Rooms:** Bar carts are placed in dining or living rooms for entertainment, while buffets are used to serve food or store dishware.
- **Hotels:** In hotel rooms, a small bar cart can provide guests with drinks and snacks.

Example: A vintage bar cart in a apartment adds a sophisticated touch to the living room or dining area.

Office Furniture

- **Desks**

Fig. 2.2.13:

Desks are essential in offices for work or study purposes, offering surfaces for writing, computing, or organizing.

Applications:

- **Home Offices:** Compact desks are often used in home offices for space efficiency.
- **Corporate Offices:** Larger desks are used for executive offices, often with compartments for file storage.

Example: In an office, a modern ergonomic desk with a sleek design supports both work efficiency and comfort.

- **Office Chairs**

Fig. 2.2.14:

Office chairs are designed for comfort and support during long hours of work, often with adjustable features.

Applications:

- **Commercial Offices:** Ergonomic chairs are used to improve productivity and posture in corporate settings.
- **Home Offices:** Comfortable chairs are used to ensure good posture in home office environments.

Example: An ergonomic office chair in a Gurgaon tech startup enhances comfort and productivity, supporting employees during work hours.

- **Filing Cabinets**

Fig. 2.2.15:

Filing cabinets are used to store files, documents, and office supplies, available in various styles and sizes.

Applications:

- **Home Offices:** Filing cabinets help keep personal workspaces organized.
- **Corporate Offices:** Used for document storage in administrative offices.

Example: A stainless steel filing cabinet in an office in is both functional and visually appealing.

Outdoor Furniture

- **Patio Furniture**

Fig. 2.2.16:

Patio furniture includes outdoor seating and dining pieces that are weather-resistant, perfect for gardens, terraces, or balconies.

Applications:

- **Residential:** For balconies or outdoor gardens to create a comfortable seating area.
- **Commercial:** Used in restaurants or resorts to offer guests an outdoor seating experience.

Example: Wicker patio chairs and a wooden table in a beach resort provide comfort and style for outdoor dining.

- **Garden Furniture**

Fig. 2.2.17:

Garden furniture is typically made from materials like wrought iron, wood, or plastic, designed to withstand outdoor conditions.

Applications:

- **Gardens and Patios:** Comfortable seating arrangements for outdoor spaces.
- **Public Spaces:** Used in parks and gardens to offer seating to the public.

Example: In a garden, cast iron benches provide both style and functionality for outdoor relaxation.

Summary

- Interior drafting is the technical process of creating precise floor plans, elevations, and detailed layouts, while interior designing is a creative process that focuses on aesthetics, functionality, and client preferences.
- Steps in Interior Drafting Involves client consultation, space planning, site measurements, floor plan creation, elevations, electrical planning, and material specifications.
- In the interior Design Process the APM first consults with the client to understand their vision and then creates a conceptual design, followed by detailed planning, material selection, budgeting, and coordination with contractors.
- Interior design projects are categorized into residential, commercial, hospitality, healthcare, and educational projects, each with specific design considerations.
- Themes such as modern, traditional, transitional, industrial, rustic, and bohemian are used to define the aesthetic direction of a project, influencing material choices and furniture styles.
- Styles like minimalist, art deco, Scandinavian, Mediterranean, and coastal are employed to bring specific aesthetics to a space, with different characteristics and materials used in each style.
- High-quality materials such as wood, stone, glass, metal, fabrics, and concrete are selected for their durability, aesthetics, and suitability for specific project needs.
- Lighting fixtures, wall art, rugs, cushions, and curtains are used to enhance the visual appeal and functionality of a space.
- Architectural hardware such as door handles, window locks, cabinet pulls, and lighting fixtures plays a vital role in the functionality, security, and aesthetics of a space.
- Effective communication is key for designers to interact with clients, contractors, and suppliers, ensuring the design meets the client's expectations and project requirements.
- Assistant Interior designers must understand the client's needs through active listening, present design ideas clearly using visual aids, and manage client expectations to maintain a positive relationship throughout the project.

Exercise

Multiple Choice Questions (MCQs)

1. You are designing a luxury apartment's living room for a client who prefers traditional Indian aesthetics. Which of the following would be the most appropriate material and accessory combination?
   a. Marble flooring with velvet drapes and Tanjore wall art
   b. Vitrified tiles, leather recliner, and graffiti wall art
   c. Concrete floor, mirror art, and minimalist furniture
   d. Laminate flooring, abstract painting, and folding chairs

2. A client wants to renovate their boutique hotel lobby using a Mediterranean style. What materials and finishes would best suit the theme?
   a. Frosted glass walls, stainless steel door handles, and LED strips
   b. Terracotta flooring, wrought iron railings, and sea-inspired colours
   c. Tinted glass partitions, acrylic panels, and black leather seating
   d. Bamboo flooring, minimal wall art, and white laminate cabinetry

3. You are working on a modular kitchen for a high-end apartment. The client emphasizes durability and a modern look. What combination should you choose?
   a. Marble counters, MDF cabinetry, and bronze fittings
   b. Teak counters, wrought iron handles, and cotton blinds
   c. Quartz counters, veneer cabinets, and copper mesh trolleys
   d. Granite counters, HPL shutters, and stainless-steel pull-out systems

4. During a project review, a client is confused about the difference between interior drafting and designing. What explanation should you give?
   a. Drafting is artistic, designing is technical
   b. Drafting focuses on construction drawings, designing involves creative planning and aesthetics
   c. Drafting and designing are used interchangeably
   d. Designing is not required if drafting is accurate

5. While designing a commercial office, your client wants an open and collaborative workspace. Which style and furniture would best meet their needs?
   a. Art Deco style with crystal chandeliers and marble flooring
   b. Minimalist style with open workstations, ergonomic desks, and glass partitions
   c. Mediterranean style with terracotta flooring and ornate wood furniture
   d. Coastal style with pastel walls and lounge chairs

Notes

Scan the QR codes or click on the link to watch the related videos

https://www.youtube.com/watch?v=OuOzTQZMD9s

Elements of Interior Design

https://www.youtube.com/watch?v=4rFxk8W9yUg

Interior Design Trends

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

3. Interpret and Analyze the Client Requirement

Unit 3.1: Themes, Styles, Layouts Associated with Interior Design Projects
Unit 3.2: Interpreting Site Layout/Drawings

FFS/N0210

Key Learning Outcomes

At the end of this module, the participants will be able to:

1. List various interior decor elements like ventilation, colour, lighting, Vaastu shastra, symmetry, etc. for Residence, Kitchen, Commercial, Hospitality, Academic Institutions, and Retail Fitout & Exhibitions
2. Explain the various material specifications, design themes, styles, layouts, etc.
3. Describe the process of interpreting site layout/drawings based on different architectural elements at the worksite.
4. Interpret the site layout/drawings based on available design specifications.
5. Interpret the different elements of interior designing like style, theme, services, etc., based on client interactions

UNIT 3.1: Themes, Styles, Layouts Associated with Interior Design Projects

Unit Objectives

At the end of this unit, the participants will be able to:

1. List various interior decor elements like ventilation, colour, lighting, Vaastu shastra, symmetry, etc.
2. Explain the various material specifications, design themes, styles, layouts, etc.
3. Identify the different elements of interior designing like style, theme, services, etc., based on client interactions.
4. Describe the process of interpreting site layout/drawings based on different architectural elements at the worksite.
5. Interpret the site layout/drawings based on available design specifications.

3.1.1 Interior Decor Elements

Following is the comprehensive list of various interior décor elements categorized by project type, with multiple examples for each element such as ventilation, color, lighting, Vaastu shastra, symmetry, and others like materials, textures, and finishes ensuring completeness across residence, kitchen, commercial, hospitality, academic, and retail/exhibition spaces:

1. Residence

Element	Types / Examples
Ventilation	Cross ventilation, ventilator grills, French windows, jali panels, openable skylights
Color	Neutral (beige, ivory), Warm (terracotta, mustard), Pastel (mint, blush), Dual-tones
Lighting	Ambient lights, chandeliers, wall sconces, LED strip lights, floor lamps
Vaastu	Entrance in northeast, master bedroom in southwest, kitchen in southeast
Symmetry	Symmetrical furniture layout, aligned art pieces, centered rug or coffee table
Materials	Wood, natural stone, laminates, metal accents, textured wallpaper
Textures	Fabric upholstery, wall textures, stone cladding, wooden paneling
Décor	Indoor plants, area rugs, personal art, display shelves

Table 3.1.1:

2. Kitchen

Element	Types / Examples
Ventilation	Chimney, exhaust fan, sliding windows, corner ventilation ducts
Color	Monochrome (grey & black), Bright (red & yellow), Earthy (green & terracotta), Dual-tone
Lighting	Under-cabinet task lights, ceiling-mounted LED, pendant lights, profile lights
Vaastu	Southeast kitchen, stove facing east, sink in north, separate zones for fire/water
Symmetry	Modular cabinet alignment, centered hob and chimney, uniform drawer panels
Materials	Granite, quartz, acrylic, stainless steel, marine ply with laminate
Textures	Matte finishes, high gloss laminates, brushed steel, stone texture backsplash
Décor	Glass jars, hanging herbs, pull-out pantry, open shelves

Table 3.1.2:

3. Commercial (Offices, Studios)

Element	Types / Examples
Ventilation	HVAC systems, operable glass panels, air purifiers, partition grills
Color	Corporate neutrals (grey, navy), Brand-based colors, Biophilic tones (green/beige)
Lighting	Recessed lighting, task lights at desks, track lights, sensor lighting
Vaastu	Entrance in northeast, manager's cabin in southwest, conference in northwest
Symmetry	Linear workstation alignment, modular furniture layout, balanced partitioning
Materials	Glass, MDF, engineered wood, acoustic panels, metal framework
Textures	Fabric wall panels, laminated surfaces, perforated ceiling, textured carpet tiles
Décor	Company branding elements, wall graphics, indoor planters, clocks

Table 3.1.3:

4. Hospitality (Hotels, Cafes, Lounges)

Element	Types / Examples
Ventilation	Louvers, AC zoning, operable balconies, air curtains at entrance
Color	Warm neutrals (sand, taupe), Rich hues (burgundy, emerald), Monochrome, Luxe accents
Lighting	Cove lighting, dimmable LEDs, pendant lights, vintage bulbs, chandelier
Vaastu	Entry in northeast, water feature in east, reception in north, kitchen in southeast
Symmetry	Centered bed headboards, symmetrical lobby furniture, corridor wall lighting
Materials	Marble, brass, velvet, glass, patterned tiles, faux leather
Textures	Upholstered walls, stone-textured floor, woven rugs, wooden beams
Décor	Art installations, indoor plants, ambient candles, mirrors

Table 3.1.4:

5. Academic Institutions

Element	Types / Examples
Ventilation	Cross ventilation through windows, high ceilings, louvered doors, ceiling fans
Color	Pastel tones (sky blue, mint green), Primary accents (yellow, red), Whiteboards
Lighting	LED panel lights, focus lights on boards, daylight-utilization via clerestories
Vaastu	Classrooms in east, library in southwest, labs in southeast, entrance from north
Symmetry	Desk arrangement in rows, aligned lighting panels, central corridor layout
Materials	Pre-laminated boards, vinyl flooring, metal desks, fabric pin-up boards
Textures	Non-glossy surfaces, perforated acoustic panels, grid ceilings
Décor	Educational posters, motivational quotes, green boards, soft pin-up displays

Table 3.1.5:

6. Retail Fit-out & Exhibitions

Element	Types / Examples
Ventilation	Air conditioning, ducted cooling, temporary vent fans (for exhibitions)
Color	Brand-specific colors, black & white, attention-catching neons, themed palettes
Lighting	Spotlights, shelf lighting, LED track lights, RGB strips, fiber optics
Vaastu	Cash counter in southeast, entrance in east/north, display orientation facing east
Symmetry	Modular display grids, balanced aisle layouts, symmetry in signage
Materials	MDF, acrylic, backlit panels, aluminium framework, vinyl graphics
Textures	Glossy laminates, printed vinyl, digital print fabrics, faux wood textures
Décor	Logo placements, digital screens, mannequins, display risers

Table 3.1.6:

3.1.2 Themes and Styles in Interior Design

In interior design, the project theme or style sets the overall tone and direction for the entire space. It reflects the client's personality, brand identity, or cultural preference. For an Assistant Interior Designer, understanding these themes and styles is crucial to translating the client's vision into actionable plans and coordinating the design and execution process effectively. This chapter outlines common types of interior design styles and the specific design considerations associated with each.

Modern Style

Modern style is characterised by simplicity, clean lines, and a functional approach to space utilisation. It focuses on minimalism and avoids unnecessary decoration.

Design Considerations:

- Use of neutral colours such as white, grey, or beige
- Modular furniture with straight lines and sleek surfaces
- Minimalistic decor with emphasis on open spaces
- Use of materials like glass, metal, and laminates

- Hidden storage and built-in lighting solutions
- Smooth surfaces and easy-to-clean finishes.

Fig. 3.1.1: Modern Style

Applications:

Corporate offices, urban apartments, retail stores

Contemporary Style

Contemporary style is dynamic and evolves with current trends. It blends comfort with sophistication and often overlaps with modern design elements.

Design Considerations:

- Mix of textures and soft, curved lines
- Neutral colour palettes with occasional bold accents
- Use of eco-friendly and sustainable materials
- Emphasis on lighting, especially natural lighting
- Flexible and multifunctional furniture layouts

Fig. 3.1.2: Contemporary Style

Applications:

IT offices, collaborative workspaces, residential interiors

Traditional Indian Style

This style draws inspiration from Indian art, heritage, and culture. It focuses on detailed craftsmanship and rich materials.

Design Considerations:

- Use of natural materials such as wood, brass, and stone
- Intricate carvings, jali work, and handmade textiles

- Rich colour schemes including maroon, gold, and earthy tones
- Traditional furniture with heavy wood and classic silhouettes
- Ethnic motifs, wall murals, or artwork rooted in Indian tradition

Fig. 3.1.3: Traditional Style

Applications:

Heritage hotels, cultural centres, residential homes

Industrial Style

Overview:

Inspired by factories and warehouses, industrial style embraces raw and unfinished elements. It is utilitarian and bold in appearance.

Design Considerations:

- Exposed brick walls, ductwork, and pipes
- Use of concrete, iron, steel, and reclaimed wood
- Open ceilings and visible structural elements
- Neutral colour tones like grey, black, and brown
- Minimal partitions to maintain openness
- Special attention to acoustic treatment in large open areas



Fig. 3.1.4: Industrial Style

Applications:

Co-working spaces, studios, creative agency offices, cafés

Minimalist Style

Minimalist style emphasizes simplicity and functionality. The mantra is “less is more,” with the aim of creating calm and clutter-free spaces.

Design Considerations:

- Monochromatic colour schemes
- Simple and unadorned furniture
- Bare walls with minimal art or decor
- Efficient storage solutions to keep surfaces clear
- Focus on quality over quantity in materials

Fig. 3.1.5: : Minimalist Style

Applications:

Start-up offices, private workspaces, budget-conscious projects

Rustic or Natural Style

Rustic style incorporates natural, organic elements and aims to bring the outdoors inside. It offers a warm and cosy ambience.

Design Considerations:

- Use of raw or lightly treated wood, stone, bamboo
- Earthy colour palettes with greens, browns, and greys
- Handcrafted decor items and furniture
- Natural ventilation and daylight use

- Non-glossy surfaces and texture-rich finishes

Fig. 3.1.6: Rustic or Natural Style

Applications:

Eco-retreats, resorts, wellness centres

Each interior design style comes with its unique set of aesthetics, materials, and functional requirements. As an Assistant Interior Designer, it is important to not only understand these styles but also be able to assess whether they are suitable for a particular project type and client expectation. Careful consideration of materials, lighting, furniture, utility planning, and compliance requirements is essential during the execution phase. A clear understanding of project themes helps ensure that the design intent is preserved while meeting practical and commercial needs of the space.

Hands-On Activity - Identifying Interior Design Elements

Scenario:

You are an assistant interior designer meeting a new client who is planning to renovate a 3BHK apartment. The client has shared some verbal cues, mood board images, and a few lifestyle preferences.

Your task is to interpret the interaction, identify the design elements they're leaning toward, and suggest an appropriate design direction.

Instructions

1. **Review the Simulated Client Interaction Notes**
   - "I like natural lighting and clean spaces."
   - "I work from home and need a clutter-free environment."
   - "I prefer neutral tones—white, beige, maybe wood textures."
   - "Storage is very important, but I want it to look seamless."
   - (Shows images with Scandinavian furniture, minimal wall décor, and lots of daylight)
2. **Analyze the Interaction**
   - Note visual references, spoken preferences, and functional needs.

3. Identify and Record the Following Elements:

Element	Your Observations / Inference
Design Style	e.g., Scandinavian, Modern Minimalist
Theme	e.g., Natural, Light & Airy, Calm
Functional Services	e.g., Smart storage, WFH space, seamless cabinetry
Preferred Materials	e.g., Light wood, matte finishes, whites & neutrals
Lighting Preference	e.g., Natural light, sheer curtains, no heavy fixtures
Color Palette	e.g., White, beige, light grey
Space Layout	e.g., Open plan, multifunctional furniture

Table 3.1.8:

4. Present Your Design Direction

Prepare a 1-slide or 1-page design summary based on your interpretation. Include:

- Suggested style and theme
- Space layout approach
- Material and color direction
- Service recommendations (e.g., modular furniture, ergonomic setup)

Unit 3.2: Interpreting Site Layout/Drawings

Unit Objectives

At the end of this unit, the participants will be able to:

1. Describe the process of interpreting site layout/drawings based on different architectural elements at the worksite.
2. Interpret the site layout/drawings based on available design specifications.

3.2.1 Process of interpreting site layout/drawings based on different architectural elements at the worksite

Interpreting site layout and architectural drawings is a critical skill for any interior designer, site supervisor, or technician. It ensures that the design intent is correctly understood and implemented on-site, without deviations or execution errors. Following steps are involved in the process of interpreting site layout:

Step 1: Understand the Drawing Types

Begin by identifying the type of drawings provided. Common architectural drawings include:

- **Site Plan –** shows property boundaries, setbacks, access roads, landscape layout
- **Master Plan / Master Layout –** provides a comprehensive overview of a large development project. It includes the layout of buildings, roads, open spaces, utilities, and amenities, offering a holistic view of how the entire site will be developed.
- **Example:** A Master Plan for a township may show residential blocks, commercial zones, parks, internal roads, and utility areas.

Fig. 3.2.1: Sample Master Plan of a Township

- **Floor Plan –** horizontal section showing walls, doors, windows, fixtures, and furniture



Fig. 3.2.2: floor Plan

- **Elevations –** vertical views of each wall with heights, finishes, and openings
- **Sections –** cross-sectional views showing internal relationships and height levels
- **Reflected Ceiling Plans (RCP) –** layout of ceiling designs, light fixtures, and service lines



Fig. 3.2.3: RCP Drawing

- **Service Drawings –** plumbing, electrical, HVAC, and fire-fighting layouts



Fig. 3.2.4: Electrical Drawing

Step 2: Read the Legend and Scale

- Refer to the legend or key to understand symbols for walls, doors, windows, fittings, etc.
- Check the scale (e.g., 1:100, 1:50) to accurately interpret dimensions and distances.

Step 3: Identify Key Architectural Elements

Focus on recognizing important built elements that impact interior work:

Architectural Element	What to Check
Walls	Thickness, type (load-bearing/non-load-bearing), finishes
Columns & Beams	Position, size, structural role, restrictions for modification
Doors & Windows	Opening direction, sizes, placement for light/ventilation
Floor Levels	Elevation changes, slopes, step-downs, thresholds
Staircases	Riser-tread dimensions, railing needs, under-stair usage
Ceilings	Slab height, beam drops, scope for false ceiling
Service Shafts	Duct space for plumbing and HVAC lines
Orientation & Sunlight	Based on site plan and compass direction; affects design planning

Table 3.2.1:

Step 4: Cross-Verify with Site Conditions

- Conduct a physical walkthrough of the site and match it with the drawings.
- Note any discrepancies (e.g., an existing beam not shown in the drawing).
- Use tools like laser measures, plumb bob, or measuring tape to confirm dimensions.

Step 5: Interpret Functional Zoning

- Understand how the architectural layout supports interior zoning.

  Example: Positioning of kitchen near utility shaft or natural light flow in living room.

Step 6: Mark Design Opportunities and Constraints

- Identify areas where structural elements enable design features (e.g., niches between columns)
- Spot constraints like low beams, awkward corners, or wall offsets that affect furniture or lighting layout.

Example

If a drawing shows a beam running across a bedroom ceiling at 7 feet, the designer may need to revise the false ceiling design to incorporate the beam aesthetically and ensure light fixture clearance.

Thus, accurate interpretation of site drawings based on architectural elements helps translate design concepts into real-world, buildable solutions. It minimizes rework, supports technical coordination, and ensures efficient on-site execution.

Summary

- Interior décor elements such as ventilation, color, lighting, symmetry, materials, and Vaastu vary across different project types like residential, kitchen, commercial, hospitality, academic, and retail spaces.
- Material specifications include details about finishes, durability, colors, and textures, which are chosen based on space usage, theme, and client preferences.
- Interior design styles such as modern, minimalist, industrial, and traditional influence layout, color palette, furniture, and materials used in a project.
- Themes set the mood and visual direction of a space and may reflect cultural identity, lifestyle aspirations, or branding.
- Through client interactions, designers identify key preferences related to style, functional needs (e.g., WFH space), materials, lighting, and layout expectations.
- Site layout and architectural drawings include different types like floor plans, elevations, RCP, sections, and service layouts that must be read using legends, scales, and architectural symbols.
- Interpreting drawings involves identifying architectural elements such as walls, beams, doors, windows, and sunlight orientation to ensure accurate space planning.
- Cross-verifying drawings with actual site conditions helps identify discrepancies and adjust design plans accordingly to avoid execution errors and improve buildability.

Exercise

Multiple Choice Questions (MCQs)

1. You are designing a workspace for a startup. The client says they want an "open, clutter-free, functional office with neutral tones and good lighting." Based on this, which style would you recommend?

   a. Traditional Indian

   b. Minimalist

   c. Rustic

   d. Industrial

2. While reviewing an RCP (Reflected Ceiling Plan), you observe misalignment of light fixtures due to a beam not mentioned in the plan. What should be your first step?

   a. Proceed with installation

   b. Remove the beam

   c. Cross-verify on site and revise the false ceiling design

   d. Ignore the discrepancy

3. A client shares mood board images with soft curves, pastel colors, and multifunctional furniture. Which design theme are they likely aligned with?

   a. Contemporary

   b. Industrial

   c. Rustic

   d. Classic

4. While interpreting the site layout, you notice that the door swing affects furniture placement in the living room. What architectural element should you check in the drawing?

   a. Floor Level

   b. Orientation

   c. Door & Window Placement

   d. Staircase Width

5. A 3BHK apartment client mentions needing a compact WFH space, open layout, and neutral color palette with wood finishes. Which functional services should you recommend?

   a. Home theatre, mood lighting, vintage accessories

   b. Open shelving, exposed brickwork, heavy woodwork

   c. Modular workstation, concealed storage, daylight enhancement

   d. Traditional motifs, carved wooden panels, chandeliers

Hands-On Activity - Drawing Interpretation Based on Design SpecificationsWW

Scenario

You are assigned to assist with the renovation of a commercial office space. You have been provided with the following documents:

- A floor plan (including workstation, meeting room, and pantry layout)
- A reflected ceiling plan (RCP)
- A material specification sheet
- Notes from the designer on required finishes and furniture

Your task is to study the layout drawings and interpret the following elements based on the given specifications.

Steps to Perform

1. **Study the Drawing Set (Instructor will provide samples or PDFs)**
   - o Identify walls, doors, windows, column positions
   - o Review dimensions and service access points
   - o Refer to legends for symbols and materials
2. **Read the Material Specification Sheet**
   - o Understand materials assigned to each space
   - o Cross-check with drawing notes and labels (e.g., carpet tile code, wall paint)
3. **Interpret and Record Observations for the Following:**

Design Element	Drawing Clue	Your Interpretation
Flooring finishes	Hatching / labels on plan	Identify spaces with wooden, tile, or carpeted floors
Furniture layout	Desks, chairs, partitions marked on plan	Note quantity and spacing of workstations
Lighting/ceiling layout	Symbols in RCP	Identify lighting type and alignment with layout
Partition placement	Wall thickness, lines in plan	Identify solid walls vs. glass/ temporary partitions
Entry/exit and circulation	Door swing, corridor widths	Interpret movement paths and space efficiency
Service points (electrical/ HVAC)	Icons in plan	Mark switchboards, AC vents, and ceiling ducts

4. **Summarize Findings**
   - o Write a short report or fill the template with observations and comments
   - o Highlight any clashes, inconsistencies, or questions to clarify with the design team

Notes

Scan the QR codes or click on the link to watch the related videos

https://www.youtube.com/watch?v=LfxxGgePA6w

Interior Design Style

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

4. Site survey/ Recce for Interior Designing

Unit 4.1: Site Surveys
Unit 4.2: Measurement and Marking Activities
Unit 4.3: Recce Report Preparation

FFS/N0210

Key Learning Outcomes

At the end of this module, the participant will be able to:

1. Discuss the SOP for conducting site survey and recce.
2. List different technical infrastructure like ply boxing, drywall, civil wall, etc. at the worksite affecting project designing.
3. List various design elements at worksite like tiles, furniture, light, paints, sanitary fittings, etc. affecting the project scope of work.
4. Analyze the recce planning for tools, materials, and equipment based on required job work specifications.
5. Identify suitable methods to ensure tasks are planned and sequenced in conjunction with others involved in or affected by the work.
6. Explain the process of interpreting MEP and construction details for project designing.
7. Explain the process of interpreting the scope of work details based on different design elements at the worksite.
8. List all the pre-requisites involved in performing measurement and marking activities.
9. State the importance of workplace monitoring during measurement and marking activities.
10. Examine the worksite for the appropriate execution of measurement and marking activities. based on specified instructions.
11. Describe various elements involved in a recce report and the process of interpreting them.
12. Explain the importance of time management during assigned job work.
13. State the importance of preparing and validating a measurement sheet.
14. Identify suitable techniques for adequate preparation and timely submission of the recce report.
15. Explain the process of recce report validation based on site layout and space plan.

UNIT 4.1: Site Surveys

Unit Objectives

At the end of this unit, the participants will be able to:

1. Discuss the SOP for conducting site survey and recce.
2. List different technical infrastructure like ply boxing, drywall, civil wall, etc. at the worksite affecting project designing.
3. List various design elements at worksite like tiles, furniture, light, paints, sanitary fittings, etc. affecting the project scope of work.
4. Analyze the recce planning for tools, materials, and equipment based on required job work specifications.
5. Identify suitable methods to ensure tasks are planned and sequenced in conjunction with others involved in or affected by the work.
6. Explain the process of interpreting MEP and construction details for project designing.
7. Explain the process of interpreting the scope of work details based on different design elements at the worksite.

4.1.1 Standard Operating Procedure (SOP) for Conducting Site Survey/Recce

A site survey or recce is a planned visit to the project location to assess the site's condition, layout, and feasibility for interior work. It is a critical step before design execution begins.

Following are the SOP steps for conducting site survey/recee:



Fig. 4.1.1: SOP steps for conducting site survey/recee

1. Pre-Survey Preparation

- Review the client's brief and initial layout drawings (if available).
- Schedule the site visit in coordination with the client's Point of Contact (POC).
- Prepare a checklist covering measurements, photographs, lighting, services, and access points.
- Carry required tools: laser measurer, notebook, PPE (if under construction), camera, etc.

2. Role of Client POCs

- Client POCs (Point of Contacts) help facilitate access, coordinate with society or building staff, and explain client expectations.

- They may also provide existing floor plans, approvals, or guide interaction with security and facility managers.

3. Permission and Entry Protocol

- Inform the building management or society office in advance.
- Obtain any required gate passes or permission letters, especially in commercial complexes or gated societies.
- Carry ID proof and authorization letter from the client or firm, if necessary.

4. On-site Assessment

- Meet the client POC to gain access and understand any site-specific protocols.
- Measure all relevant areas (walls, ceiling heights, floor dimensions, windows, doors).
- Note locations of electrical points, water outlets, ventilation, natural light sources, and structural constraints.
- Take photographs and sketches to record observations.
- Identify challenges like damp walls, leakages, uneven flooring, or space restrictions.

5. Involvement of External Agencies (if applicable)

- For large or technically complex sites, professionals like civil engineers, electrical consultants, or HVAC vendors may accompany the designer.
- In cases involving government or heritage buildings, liaison officers may be required to confirm guidelines or permissions.

6. Post-Survey Documentation

- Prepare a Recce Report including photos, dimensions, observations, challenges, and recommendations.
- Submit the report to the client and internal team for design alignment.
- The report helps finalize the Scope of Work and ensures design feasibility.

4.1.2 Technical Infrastructure Affecting Project Designing

A clear understanding of the technical infrastructure at a project site is essential for effective interior design planning. Elements such as load-bearing walls, ply boxing, drywalls, ceiling heights, and service shafts influence layout feasibility, visual balance, cost planning, and material selection. Assessing such constraints during the site visit enables practical decision-making.

Let us understand how these infrastructure elements affect project designing.

1. **Civil Walls (Masonry Walls / Load-bearing Walls)**: These are permanent walls constructed using bricks, concrete blocks, or RCC. They are either load-bearing or partition walls.

Fig. 4.1.2: Civil Walls (Masonry Walls / Load-bearing Walls)

Non-modifiable:	Load-bearing walls cannot be broken or altered without structural risk.
Placement Restrictions:	Restricts shifting of room layout (e.g., can't expand bathroom or kitchen beyond a civil wall).
Surface Treatment:	Masonry walls often require plastering, POP finish, or cladding, which affects time and finish cost.

Fig. 4.1.2(a): Civil Walls – Impact on Design

For Example: If a client wants an open kitchen concept, but a civil wall separates the kitchen and dining, the design may need to switch to a pass-through window instead of full wall removal.

2. **Ply Boxing (Wooden Boxing / False Structures):** Ply boxing refers to framed structures made using plywood and supports. Commonly used for window encasing, pelmets, curtain boxes, beam covers, TV units, etc.

Fig. 4.1.3: Ply Boxing (Wooden Boxing / False Structures)

Following could be the impact on design:

Increases Design Flexibility:	Can conceal wiring, create recessed lighting panels, or simulate architectural elements.
Material Compatibility	Choice of ply (MR, BWR, BWP) impacts moisture resistance and load-bearing capacity.
Finish Layer Dependent	Needs compatible finishes—laminate, veneer, duco, or PU paints.

Fig.: 4.1.4: Impact on Design - Ply Boxing (Wooden Boxing / False Structures)

For Example: In a bedroom, ply boxing is used to conceal curtain tracks and indirect strip lighting. If not accounted for early, it can reduce ceiling height, affecting aesthetics.

3. **Drywall (Gypsum or Cement Board Partitions):** These are lightweight, prefabricated walls made from gypsum or cement boards mounted on a metal framework. Used widely for internal partitions.



Fig. 4.1.5: Gypsum Boards

Easy Modification:	Easier to install or shift compared to masonry walls.
Weight Bearing Limitations:	Cannot hold heavy loads (like wall-hung cabinets or TVs) unless supported with internal bracing.
Faster Turnaround:	Speeds up project timelines.

Fig.4.1.6: Impact on Design - Drywall (Gypsum or Cement Board Partitions)

Example:

In a retail store project, a display wall was created using drywall. The designer ensured concealed support channels were added for shelf mounting.

4. **Structural Columns and Beams:** It refers to the exposed RCC columns and beams that support the building's structure. Example:

In a living room, a protruding column was wrapped with MDF panels and converted into a display shelf with recessed lights.

Fig. 4.1.7: Structural Column and Beam

Fixed Positioning:	Cannot be removed or relocated—must be visually blended into the design.
Design Opportunity:	Can be cladded or used to frame design features like niches, lighting strips, or mirror panels.

Fig. 4.1.8: Impact on Design – Structural Column and Beam

5. **Window and Door Frames (Metal, Wood, UPVC):** These are the pre-installed fenestration elements that affect light entry, ventilation, and opening direction.

Fig. 4.1.9: Window and Door Frames (Metal, Wood, UPVC)

Following could be the impact on design:

Natural Light Planning:	Influences the placement of furniture and window treatments
Material Coordination:	Finishes of frames must match or complement other materials used in the space.

Fig. 4.1.10: Impact on Design - Window and Door Frames (Metal, Wood, UPVC)

Example:

In a compact bedroom, a window opening inward limited wardrobe placement. The design was revised to accommodate a sliding shutter system.

6. **Service Lines (Electrical, Plumbing, HVAC, Fire Safety):** It includes conduits, pipelines, drains, and ducting that carry utilities throughout the site.

Fig.4.1.11: Service Lines (Electrical, Plumbing)

Following could be the impact on design:

Design Planning:	Location of service lines affects layout—for example, plumbing points define bathroom or kitchen sink placement.
False Ceiling Requirement:	Ducts and electrical wiring may require drop ceilings to conceal.
Coordination Required:	Delays or misalignment in MEP (Mechanical, Electrical, Plumbing) work affects installation sequencing.

Fig. 4.1.12: Impact on Design - Service Lines (Electrical, Plumbing, HVAC, Fire Safety)

Example:

If an HVAC duct crosses through the bedroom ceiling, the false ceiling design must integrate it using a tray or boxing design to maintain uniform height.

7. **Electrical Points and Distribution Boards:** It includes switchboards, sockets, MCBs, distribution boxes, and concealed electrical conduits that provide power and control lighting and appliances throughout the residence.



Fig. 4.1.13: Electrical Points and Distribution Boards

Following could be the impact on design:

Functional Placement:	Determines where furniture and lighting fixtures can be placed (e.g., bedside switches, study tables).
Design Integration:	Must be integrated aesthetically into panels, walls, and units.
Rework Risk:	Incorrect placement can result in wall breakage and costly rewiring.

Fig. 4.1.14: Impact on Design - Electrical Points and Distribution Boards

Example:

If the client wants pendant lights above each bedside, but no electrical points are provided on the ceiling, the designer will need to propose alternate wall-mounted lights or suggest false ceiling provisions.

8. **Plumbing Lines and Drainage:** It includes concealed or exposed water supply and drainage pipes for kitchens, bathrooms, and utility areas.



Fig. 4.1.15:

Following could be the impact on design:

- **Layout Restrictions:** Wet zones must align with plumbing points (e.g., sink or WC placement).
- **Flooring Slope Requirements:** Impacts tile gradient and waterproofing layers.
- **Material Coordination:** Requires compatible cabinetry and finishes in moisture-prone areas.

Example:

In a compact kitchen, the sink cannot be moved to the island counter because plumbing lines are fixed on the wall. The design is adapted to include a sink within the back counter only.

9. **Ceiling Slab Level and Beam Height:** It refers to the vertical distance from the floor to the ceiling slab, including protruding beams or dropped slab sections.

Fig. 4.1.16:

- **False Ceiling Restrictions:** Low heights limit the depth of false ceilings and types of lighting used.
- **Aesthetic Limitations:** Tall cabinetry, chandeliers, or hanging fixtures may not be feasible.
- **Ceiling Treatments:** Beam-boxing or step-downs need to be creatively designed.

Example:

A client wants a layered false ceiling with cove lights in the bedroom. Due to a low slab height of 8 feet, the designer suggests surface-mounted LED panels instead.

10. **Fire Safety Provisions:** It includes fire-rated doors, sprinklers, smoke detectors, and flame-retardant materials required as per building codes.

Fig. 4.1.17: Fire Safety Provisions

Following could be the impact on design:

- **Material Selection:** Only certified fire-retardant laminates, paints, and fabrics can be used.
- **False Ceiling Planning:** Sprinklers and smoke sensors must be accessible and unobstructed.
- **Compliance Documentation:** Design and materials must meet safety regulations.

Example:

In the kitchen entrance area, a fire-rated door with intumescent seal is installed. The designer need to ensure that the ceiling cutouts do not interfere with sprinkler flow.

12. **Shafts and Utility Ducts:** They may be vertical ducts used to carry electrical risers, plumbing lines, or ventilation shafts, commonly found in kitchens and bathrooms.

Following could be the impact on design:

- **Space Consumption:** Occupies wall space and affects cabinet or vanity design.
- **Access Requirement:** Needs access doors or panels for future maintenance.
- **Aesthetic Integration:** Must be boxed in creatively to blend with interiors.

Example:

A vertical shaft in the bathroom corner is concealed with a laminated panel door that matches the vanity, while keeping it accessible for plumbing checks.

4.1.3 Design Elements at Worksite Affecting the Project Scope of Work

In interior design projects across sectors whether residential or commercial (such as hospitality, retail, etc.) design elements like tiles, furniture, lighting, paint, and sanitary fittings significantly influence the Scope of Work (SOW). These components impact layout planning, service integration, aesthetics, cost estimation, and timelines. For an Assistant Interior Designer, understanding how these elements affect execution helps in accurate project planning and coordination with vendors and teams.

Let us learn how each design element contributes to defining and refining the project's scope.

1. **Tiles (Flooring & Wall Cladding)**

   Impact on Scope of Work:

   - **Surface Preparation:** Tile selection (ceramic, vitrified, stone) influences subfloor levelling, waterproofing, and screed thickness.
   - **Time & Cost Estimates:** Imported or mosaic tiles require longer laying time and skilled labor, affecting project timeline and cost.
   - **Design Customization:** Pattern layouts (e.g., herringbone, diagonal) or inlays add to design scope and execution complexity.

Example:

Client selects patterned vitrified tiles for the living room. The SOW must now include additional tile cutting and layout marking, extending the flooring timeline.

2. **Furniture (Loose & Fixed)**

   Impact on Scope of Work:

   - **Space Allocation:** Size and layout of furniture determine wall clearances, plug point locations, and walkways.
   - Custom Joinery Needs: Fixed furniture like wardrobes or kitchen cabinets requires carpentry work, which expands the SOW.
   - Material Matching: SOW must align laminate, finish, and handle choices with the rest of the interior theme.

Example:

A modular study table requires the relocation of electrical sockets. This adds electrical rework and furniture panel adjustments into the SOW.

3. **Lighting Fixtures**

   Impact on Scope of Work:

   - **Ceiling Coordination:** Choice of recessed, pendant, or cove lighting defines false ceiling design and depth.
   - **Wiring Layout:** Location of lights influences conduit planning, switchboard positions, and looping.
   - **Fixture Type:** Some designer lights require special junction boxes or hanging support, expanding installation scope.

Example:

A chandelier in the dining area requires reinforcement and a separate dimmer switch. This must be reflected in the electrical and ceiling works scope.

4. **Paints and Wall Finishes**

   Impact on Scope of Work:

   - **Surface Treatment:** Textured or stencil paints need extra putty, masking, and finish coats.
   - **Theme Integration:** Colour schemes must coordinate with furniture, flooring, and lighting, affecting design finalization stages.
   - **Weather Resistance:** In wet zones or balconies, exterior-grade or washable paints are added to SOW.

Example:

The client wants a two-tone accent wall with texture paint. The painter's scope and timeline increase due to extra coats and detailing.

5. **Sanitary Fittings (Toilets, Washbasins, Faucets)**

   Impact on Scope of Work:

   - **Plumbing Layout:** The type and size of fitting impacts pipe diameters, wall chases, and outlet positions.
   - **Mounting Requirements:** Wall-hung fittings require structural supports and brackets, altering wall design.
   - **Brand/Model Dependency:** Some imported fittings need extra accessories or unique installation techniques.

Example:

The client chooses a wall-mounted WC with a concealed cistern. This introduces masonry, plumbing, and tile rework into the scope.

6. **Windows and Curtains/Blinds**

   Impact on Scope of Work:

   - **Natural Light Control:** Curtain type (ceiling-mounted, wall-mounted, recessed) affects ceiling boxing and electrical plans (for motorized blinds).
   - **Height and Style:** Tall windows may require fabric selection and custom tailoring, affecting cost and procurement scope.

Example:

Motorized blackout blinds are planned in the master bedroom. This adds motor wiring, remote switch configuration, and boxing into the SOW.

7. **Wall Panels, Art, and Décor Items**

   Impact on Scope of Work:

   - **Mounting Surface:** Some wall art requires reinforcement or embedded channels.

- **Electrical Add-ons:** If backlighting is needed for art panels, it adds electrical scope.
- **Theme Finalization:** Décor must align with overall visual strategy—often requiring client approvals and material adjustments.

Example:

A wooden veneer feature wall with cove lighting is proposed in the TV unit area, adding ply framing, electrical, and finishing work to the scope.

4.1.4 Analyze the Recce Planning

A recce (reconnaissance/site inspection) is a critical pre-execution activity. Effective planning for recce ensures that the Assistant Interior Designer gathers accurate site data and identifies constraints that may impact design feasibility. Recce planning involves the following:

- Understand the type of job work (e.g., carpentry, false ceiling, tiling, painting)
- Carry the right tools and instruments based on the scope
- Prepare a checklist of material samples, catalogues, or finishes needed for client reference or measurement matching

For Example: During recce for a hotel lobby, the designer plans to propose marble cladding. They carry marble samples, polish finish swatches, and a laser measurer to assess the column sizes accurately.

Practical Hands-On Activity

Title: Plan a Recce Toolkit Based on Job Work

Scenario: You are assisting the designer on a site recce for a custom wardrobe in a master bedroom of a residential apartment. The client has asked for sliding shutters, internal organizers, and wants the wardrobe to align with an existing window.

Identify:

- Measurement needs (height, wall-to-wall, window clearance)
- Material finish options
- Electrical plug positioning inside wardrobe (if any)

Instructions:

1. Identify the job work specifications from the scenario.
2. List the tools, samples, equipment, and reference documents needed for the recce.
3. Justify why each item is needed.

Expected Output: A checklist reflecting the tools, materials, and equipment based on required job work specifications.

4.1.5 Methods to Ensure Tasks are Planned and Sequenced

Interior projects involve multiple teams such as civil, MEP, carpentry, painting, furnishing. Tasks must be sequenced logically to ensure smooth execution without rework or delay.

For example: In a retail fit-out, carpenters arrive before electrical rough-in is complete. The site gets delayed. If the Assistant Interior Designer had checked the electrical handover status, task sequencing could have been realigned.

Effective interior project execution depends on proper task sequencing, stakeholder coordination, and use of planning tools.

The following key concepts ensure smooth workflow, avoid rework, and help the Assistant Interior Designer align activities with timelines and team responsibilities on site:

- **Task Sequencing:** Logical order of job execution (e.g., electrical conduit before false ceiling)
- **Stakeholder Coordination:** Align schedules with vendor availability and dependencies
- **Planning Tools:** Gantt charts, daily checklists, site handover sheets

Interior design projects follow a logical sequence of execution activities to ensure efficiency and quality. Understanding this order helps Assistant Interior Designers coordinate tasks, avoid overlap, and ensure each stage is completed before the next one begins. The common sequencing order is as follows:



Fig. 4.1.18 Sequencing Order

Practical Hands-On Activity

Title: Sequence and Schedule Interior Tasks

Task: Sample Design Scope: Retail Store – Fashion Boutique (400 sq. ft.)

Project Type: Retail Fit-Out for Women's Wear Store

Client Brief:

- Minimalist theme with focus lighting on display racks
- Central ceiling-hung signage with cove lighting
- Modular shelves and trial room with mirror wall
- Wooden tile flooring
- Reception desk with logo wall
- Wall graphics and branded elements

- Ducted AC and electrical panel near trial room

Instructions:

1. Break the total work into major tasks (civil, electrical, false ceiling, painting, etc.)
2. Sequence them in logical order.
3. Add dependency notes (e.g., painting after electrical).

Process of interpreting MEP and construction details for project designing

MEP (Mechanical, Electrical, Plumbing) and construction drawings are essential technical documents in any interior project. These provide information about:

- Service routes for ducts, wires, and pipelines
- Load-bearing elements like beams, columns, and slab thickness
- Equipment locations such as air conditioning units, DB panels, water tanks
- Technical constraints for false ceilings, wall claddings, or partitions

You should be able to:

- Identify symbols for lighting, sockets, switches, plumbing fixtures, AC units, fire alarms, etc.
- Understand conduit routes (walls, ceilings, floors)
- Note beam depths, slab levels, and shaft locations that affect furniture or ceiling designs
- Cross-reference construction drawings with interior layouts to avoid design conflicts

For Example: In a commercial project, the AC duct runs across the proposed reception backdrop. The Assistant Interior Designer must adjust the wall panel height to accommodate the duct or reroute lighting design.

Practical Hands-On Activity

Title: Interpreting MEP and Structural Drawings

Sample MEP and Structural Layout (For Training Purpose)

Project Type: Commercial Office Cabin (12 ft × 15 ft)

Location: 4th Floor – Office Building

Purpose: For interpreting structural and MEP details during design planning

Structural Layout Details

- **Columns:** RCC Column at each corner (300 mm x 300 mm)
- **Beams:** Main beam runs horizontally above mid-span of the room (12” depth)
- **Slab Height:** Floor-to-ceiling slab is 10 feet
- **Drop Beam:** Present above the entrance with 6” vertical drop (affects false ceiling)

Electrical Layout (E in plan)

- **Light Point 1 (L1):** Ceiling-mounted, center of the room
- **Switchboard S1:** Near the door, includes fan, light, and one 5A socket

- **Socket Point S2:** Below desk level on the right wall (for computer)
- **AC Point:** 16A point at top-left wall with drainage hole for split AC

Plumbing Layout (P in plan)

- **Sink Inlet & Outlet (P1):** On rear wall (to be covered with pantry counter)
- **Drainage Pipe (Vertical):** Near left-side corner shaft – 4" diameter

Mechanical (HVAC)

- **Duct Line:** Rectangular duct (12" x 8") passes above ceiling along rear wall
- **Diffuser Placement:** Midpoint of ceiling – cool air discharge
- **Return Vent:** Above door beam

Sample Legend (can be printed on layout sheet)

Symbol	Represents
C1, C2	RCC Columns
B1	RCC Beam
L1	Light Point
S1, S2	Switchboards & Sockets
P1	Plumbing Point
D1	Duct Location

Instructions

- Identify 3 design decisions that will be affected by MEP or structure (e.g., false ceiling depth, location of AC, positioning of desk).
- Mark areas where interior elements must be adjusted (e.g., avoid placing light below duct).
- Suggest 2 possible solutions to integrate design without clashing with MEP/structure.

UNIT 4.2: Measurement and Marking Activities

Unit Objectives

At the end of this unit, the participants will be able to:

1. List all the pre-requisites involved in performing measurement and marking activities.
2. State the importance of workplace monitoring during measurement and marking activities.
3. Examine the worksite for the appropriate execution of measurement and marking activities. based on specified instructions.

4.2.1 Pre-requisites Involved in Performing Measurement and Marking Activities

Before starting any measurement and marking work on-site, it is essential to ensure that all necessary pre-conditions are met. This not only ensures accuracy and efficiency, but also prevents delays, rework, and safety issues during execution.

Following is the key pre-requisites:



Fig. 4.2.1: Pre-Requisites

Approved Design Drawings: Before any measurement or marking activities begin, you need to ensure that all client-approved design drawings are available and up to date. These include the final layout plan, elevations, and furniture drawings, which form the basis for accurate on-site marking. Any revisions, site adjustments, or client-requested changes must be clearly reflected in the drawings prior to measurement. All site markings must strictly adhere to these finalized drawings to avoid rework, design mismatches, or execution errors.

Site Readiness: Proper site readiness is a key pre-condition for accurate measurement and marking. The area where marking is to be performed must be clear of construction debris and free from any ongoing wet work, such as plastering or tiling. This ensures uninterrupted access and prevents errors caused by unfinished surfaces. Additionally, walls and floors should be plastered or levelled, if applicable, to

serve as reliable reference planes. Adequate lighting must be available to ensure visibility of markings, particularly in corners or enclosed spaces.

Measurement and Marking Tools

- **Measuring Tape** – For basic linear measurements.
- **Laser Distance Measurer** – For quick and accurate distance checks.
- **Spirit Level** – To verify straightness and verticality of walls and markings.
- **Plumb Bob/Line Dori** – For vertical alignment.
- **Chalk Line or Marker Pens** – For marking wall/floor lines.
- **Masking Tape** – For clean, temporary line markings.
- **Step Ladder** – For reaching higher wall areas.
- **Notebook/Digital Tab** – To record dimensions and observations.

Defined Reference Points: It is important to identify and agree upon fixed reference points on-site. These may include room corners, midpoints, beam edges, or door and window junctions. Such points act as consistent physical benchmarks from which all other measurements can be taken. Using well-defined reference points ensures uniformity and accuracy across different rooms or elevations, making it easier to align elements like furniture, electrical points, and wall finishes during execution.

Material Samples or Appliance Specs (if required): In certain cases, it is necessary to carry material samples or technical specifications of key appliances or components to the site during measurement and marking activities. Items such as kitchen appliances, sinks, hardware fittings, or modular accessories often have specific size and clearance requirements that directly influence marking dimensions. Having these references on hand helps ensure that depth, height, and spacing are accurately planned, reducing the risk of errors during installation and improving overall design integration.

Safety Gear and Permissions: It is essential to ensure that all team members are equipped with the appropriate Personal Protective Equipment (PPE) such as hard hats, closed-toe footwear, gloves, and reflective jackets, especially when working on active or multi-agency sites. Additionally, proper access permissions must be obtained from the site supervisor, facility manager, or building authorities. This is particularly important in commercial or under-construction environments where movement is restricted or requires safety briefings and formal clearance.

4.2.2 Importance of Workplace Monitoring During Measurement and Marking Activities

Monitoring the worksite during measurement and marking is a crucial responsibility for an Assistant Interior Designer. These early-stage tasks form the foundation for all subsequent design execution. Without proper supervision, even small errors can lead to design mismatches, material waste, or safety hazards. Regular observation helps ensure that all markings are accurate, aligned with approved plans, and carried out in a safe and organized manner. Following are some of the importance of workplace monitoring:



Fig. 4.2.2: Importance of workplace monitoring

Sample Monitoring Checklist: Measurement and Marking Activities		
Checklist Item	**Yes/No**	**Remarks**
Are approved layout plans and elevations available at the site?		
Are reference points (e.g., corners, centerlines) clearly identified?		
Are measurements being taken using appropriate and calibrated tools?		
Is marking being done on clean, finished, or leveled surfaces?		
Are vertical and horizontal markings aligned as per drawing specifications?		
Are heights (e.g., switchboards, shelves) correctly marked from finished floor level?		
Are there any conflicts between markings and existing site elements (beams, ducts)?		
Are workers following safety protocols (PPE, safe tool use)?		
Is the marking work being cross-verified by a supervisor or designer?		
Are deviations, if any, being documented and communicated for design revision?		

Table. 4.2.1:

UNIT 4.3: Recee Report Preparation

Unit Objectives

At the end of this unit, the participants will be able to:

1. Describe various elements involved in a recce report and the process of interpreting them.
2. Explain the importance of time management during assigned job work.
3. State the importance of preparing and validating a measurement sheet.
4. Identify suitable techniques for adequate preparation and timely submission of the recce report.
5. Explain the process of recce report validation based on site layout and space plan.

4.3.1 Recee Report Elements/Documents

Proper documentation during and after a site survey (recce) is essential to ensure clarity, transparency, and accuracy in interior design project execution. Such documents serve as critical reference points throughout the design and execution stages. They help ensure that project decisions are based on accurate data and site realities and help avoiding future disputes, streamlining approvals, and ensuring the design aligns with actual site conditions.

Following are the key documentation required for a Site Survey/Recce activity:



Fig. 4.3.1: Key documentation

1. **Site Survey/Recce Checklist:** It is a pre-prepared list used to systematically observe and record key details during a site visit. It ensures that no important aspect is overlooked during the inspection. The checklist typically includes items such as wall measurements, ceiling height, natural and artificial lighting availability, ventilation, flooring condition, and any

Sample: Site Survey/Recce Checklist

Project Name: _____

Site Address: _____

Date of Visit: _____

Visited By: _____

Client POC: _____

General Site Information

Checklist Item	Yes/No	Observations/Notes
Site accessible for inspection		
Site cleaning done before visit		
Basic floor plan available		
Power supply available		
Water connection available		
Any ongoing construction		

Measurements

Area to be Measured	Measured (Yes/No)	Dimensions (L x B x H in feet/meters)
Entrance		
Living Room		
Bedrooms (each)		
Kitchen		
Bathrooms		
Balcony/Terrace		
Ceiling Heights		

Lighting & Ventilation

Checklist Item	Yes/No	Observations
Availability of natural light		
Location of windows		
Artificial lighting points identified		
Cross ventilation		

Fig. 4.3.2:

Electrical & Services		
Checklist Item	**Yes/No**	**Remarks**
Switchboards and plug points marked		
AC units or provision available		
Existing lighting layout available		
Plumbing lines marked		
Drainage and waste lines visible		
Civil & Structural Conditions		
Checklist Item	**Yes/No**	**Observations**
Any visible damage (dampness/cracks)		
Wall condition (paint, finish)		
Flooring condition		
Load-bearing walls present		
Ceiling condition		

Fig. 4.3.3: Sample: Site Survey/Recce Checklist

Additional Notes:

-
-
-

Signature of Surveyor: _____

Signature of Client POC (optional): _____

2. **Measurement Sheets:** These are formal records that capture all the dimensions taken during the site survey. These include length, breadth, and height of rooms, door and window sizes, ceiling heights, and available floor areas. This documentation is crucial for accurate layout planning, ensuring that furniture fits well within the space, and for deciding flooring patterns and ceiling design details. Proper measurement sheets help avoid errors during execution and support smooth coordination between design and installation teams.

Sample Measurement Sheet for Interior Design Project

Project Name: _____

Site Address: _____

Date of Visit: _____

Measured By: _____

Room Measurements

Room Name	Length (ft/m)	Breadth (ft/m)	Height (ft/m)	Floor Area (sq ft/m²)	Notes/ Observations
Living Room					
Bedroom 1					
Bedroom 2					
Kitchen					
Bathroom 1					
Balcony					

Doors & Windows

Type	Location	Width (ft/m)	Height (ft/m)	Notes/ Condition	
Main Door	Entrance				
Bedroom Door	Bedroom 1				
Window 1	Living Room			Mesh installed / Grills, etc.	
Window 2	Kitchen				

Ceiling Height & Features

Room Name	Ceiling Height (ft/m)	Features (Beams, False Ceiling, etc.)	Notes
Living Room			
Kitchen			
Bedroom 1			

Wall & Floor Conditions

Room Name	Wall Condition (Paint, Cracks)	Flooring Type/ Condition	Notes
Living Room			
Kitchen			

Fig. 4.3.4: Sample: Measurement Sheets

Additional Notes:

-
-
-

Signature of Surveyor: _____

Verified by Client POC (optional): _____

3. **Photographic Records:** These are an essential part of the site recce process. They involve taking clear, well-angled photographs of the site, including each room, walls, ceilings, flooring, fixtures, and any problem areas. These images serve as visual evidence to support the measurements taken and help identify issues such as dampness, cracks, unfinished surfaces, or space constraints. Adding notes or labels to photos makes it easier for the design and execution teams to refer during planning, ensuring that all decisions are based on accurate site visuals.

Sample – Photographic Record	
Photo	Photo Description
	Measuring the width of the main door – 3 feet (36 inches)
	Measuring the full height of the door frame – 7 feet (84 inches)
	Measuring the distance of the window from floor to frame - 3 feet (36 inches)
	Measuring the height of the window from sill to top frame – 4 feet 6 inches (54 inches)
	Measuring the wall height from floor to ceiling – 9 feet (108 inches)

Fig. 4.3.5: Sample: Photographic Record

4. **Observation Notes:** These are handwritten or typed remarks recorded during the site visit to capture important details that may not be visible in photographs or measurements. These notes highlight on-site challenges such as dampness, uneven flooring, structural obstructions, or missing electrical points. Designers also record specific client inputs or any deviations from the original plan. These observations are valuable for updating the design team, suggesting modifications, and ensuring that all practical considerations are addressed before finalizing the design or beginning execution.

Sample Observation Notes – Site Recce

Project Name: Urban Studio Apartment

Site Address: Flat No. 204, Maple Residency

Date of Visit: 18 May 2025

Surveyor: Rahul Mehta

General Observations

- Site is accessible; main entrance door has sufficient clearance.
- Natural light is limited in the living area due to adjacent building shadow.
- Ceiling height is consistent at approximately 9 feet throughout the flat.

Structural and Civil

- Minor damp patch noticed on the wall adjacent to the kitchen sink – possible plumbing issue.
- Bedroom wall opposite to window has a slight bend; may require alignment for full-height wardrobe fitting.
- Flooring in balcony is uneven and chipped in one corner – needs levelling and retile.

Electrical and Services

- Electrical points present, but switchboard placement in the living area may interfere with planned TV unit.
- AC provision present in both bedrooms; requires confirmation of load capacity from electrician.
- No existing points for chandelier in dining area – electrical extension will be needed.

Client Inputs (Recorded during visit)

- Client prefers wall-mounted storage units in the kitchen; requested waterproof material for shutters.
- Wants blackout curtains in the bedroom – track to be mounted on false ceiling.
- Open to smart automation features if within the existing electrical scope.

Recommendations

- Recommend site inspection by plumber for damp patch confirmation.
- Suggest layout revision for TV unit wall due to switchboard position.
- Electrical load and wiring map to be re-verified before lighting layout is finalized.

Fig.4.3.6: Sample: Observation Notes

5. Recce Report

Sample: Site Recce Report Template

1. Project Details

Field	Description
Project Name	ABC Corporate Office Renovation
Client Name	ABC Pvt. Ltd.
Site Address	3rd Floor, Omega Towers, Sector 62, Noida
Date of Recce	27 March 2025
Conducted By	[Your Name], Designation
Client POC Met	Mr. Rohan Verma, Admin Manager
Internal Teams Present	Interior Designer, MEP Contractor

Table. 4.3.1:

2. Purpose of Recce

To assess the physical site conditions, take detailed measurements, and evaluate the feasibility of the client's requirements before beginning the design and execution phase.

3. Summary of Client Requirements

- Modern, open-plan office design with 30 workstations
- One boardroom and two meeting rooms
- Reception with branding wall
- Pantry and server room
- False ceiling with recessed lighting
- Central air conditioning
- Brand colours: Blue and white

4. Site Observations

Area	Observation
Overall Layout	Approx. 3000 sq. ft. L-shaped floor plate. One load-bearing column near central zone.
Flooring	Existing vitrified tiles in good condition; minor cracking near entrance.
Walls	Drywall partitions exist but need removal as per new layout.
Ceiling	Slab height 10 ft. Ducts and sprinklers in place. Feasible for 2x2 grid ceiling.

Table. 4.3.2:

Natural Light	Good lighting on east-facing side. West side blocked. Additional lighting required.
Electrical	DB available near entrance. Existing wiring to be verified by electrical team.
HVAC	Central duct lines present. Vent relocation needed for new layout.
Access	Service lift available for materials. Entry allowed between 8:00 AM–8:00 PM.
Plumbing	Provision available for pantry and restrooms. No drainage near server room.

Table. 4.3.3:

5. Site Photos (Attach separately)

- Entry zone and lobby
- Existing ceiling ducts
- Electrical panel
- Area marked for pantry

6. Identified Issues and Constraints

Issue	Impact	Recommendation
Low slab height near column	May restrict false ceiling	Propose exposed ceiling in that section
No drain in server room	Affects AC water outlet	Use self-draining tank or reroute to pantry drain
Limited sunlight on west wall	Affects workstation lighting	Plan for artificial ambient lighting

Table. 4.3.4:

7. Recommendations

- Revise layout to accommodate structural column
- Plan lighting based on natural light availability
- Use modular furniture to ptimize space
- Confirm load-bearing capacity for file storage area
- Check for fire safety compliance during demolition

8. Signature and Submission

Field	Signature
Prepared By	[Name, Signature, Date]
Reviewed By	[Senior/Project Manager's Name]

Table. 4.3.5:

Note:

- All observations should be validated with drawings.
- Measurements to be confirmed during final survey.

6. **Client or POC Acknowledgment (if applicable):** It is a formal confirmation obtained after completing the site survey. This can be in the form of a signature on the recce report or a written/ email confirmation from the client or their representative. It serves as proof that the site visit was conducted and that the observations recorded during the recce are mutually agreed upon. This step ensures transparency, builds trust, and avoids disputes later by aligning the client's expectations with the actual site conditions noted by the design team.

Sample: Client or POC Acknowledgment – Site Recce

Project Name: _____

Site Address: _____

Date of Recce: _____

Conducted By: _____ (Interior Designer / APM)

Client / POC Name: _____

Acknowledgment Statement:

I, the undersigned, confirm that the site survey/recce was conducted on the above-mentioned date. I acknowledge that the observations, measurements, and visual records captured during the visit have been reviewed and represent the actual condition of the site to the best of my knowledge.

I further understand that this information will be used to plan, design, and execute the interior project, and I agree to notify the design team in case of any changes or updates at the site.

Client / POC Signature: _____

Date: _____

Contact Number: _____

Email ID: _____

7. **Revised Floor Plan (if required):** Based on actual site conditions, the original layout may need to be updated or redrawn.

Sample: Revised Floor Plan



Fig. 4.3.8: Sample: Revised Floor Plan

8. **Approval Logs (for restricted or regulated properties):** These logs are maintained when a project site is in a restricted or regulated property, such as a housing society, commercial complex, or heritage zone. If the interior work requires permissions from external agencies such as municipal corporations, building management committees, or housing societies etc. then all related documents like NOCs (No Objection Certificates), layout approval forms, or municipal sanction letters must be collected, documented, and filed. These logs ensure that the project complies with legal and community regulations and can proceed without interruptions or objections.

Sample NOC for Interior Renovation Work

To Whomsoever It May Concern,

This is to certify that we, the undersigned, as the authorized committee of [Name of Housing Society / Building / Complex], have no objection to the commencement of interior renovation work at the following premises:

Flat / Office No.: _____

Block / Tower: _____

Building / Society Name: _____

Address: _____

Owner / Resident Name: _____

The interior work may include civil changes (non-structural), electrical modifications, painting, flooring, carpentry, false ceiling, modular fittings, plumbing, and installation of fixtures as discussed with the management committee.

This NOC is issued under the following conditions:

1. All work must be carried out during permissible working hours: [e.g., 9:00 AM to 6:00 PM].
2. No structural changes should be made without prior written approval from a certified structural engineer and the society/authority.
3. The contractor must ensure cleanliness and safety in common areas and remove construction debris daily.
4. Use of lifts and common passages should be done without causing inconvenience to other residents.
5. All work must comply with applicable local municipal and safety regulations.

This certificate is valid from [Start Date] to [End Date], and any extension or deviation from the agreed work must be informed to the society office in advance.

Issued By:

For and on behalf of [Society / Building Management Committee]

Signature: _____

Name: _____

Designation: _____

Date: _____

Seal (if applicable)

Fig. 4.3.9: Sample: NOC

4.3.2 Preparing and Submitting Recce Reports

The recce report (site reconnaissance report) is a crucial document that captures site conditions, measurements, risks, and technical observations. It provides the foundation for project planning, layout finalization, budgeting, and execution. Timely and accurate submission ensures effective communication with supervisors, designers, and clients.

Following are the basic steps involved in preparing and timely submission of the recce report and contributing to the development of an effective and accurate recce report:



Fig. 4.3.10: Basic steps involved in preparing and timely submission of the recce report

Step 1: Review the Client Brief and Project Requirements

Before beginning the site recce, thoroughly study the client's brief to understand their functional, aesthetic, and technical expectations. Review floor plans, design concepts, and any specific requests such as materials, layout features, or compliance requirements. This background knowledge helps focus your attention during the visit, ensuring you examine all areas relevant to the project. Clarifying these requirements in advance also prevents misunderstandings and enables better planning and communication during the recce with clients and internal teams.

Step 2: Conduct the Site Recce with Proper Tools

Visit the site with essential tools such as a measuring tape or laser device, site layout, checklist, notepad, mobile camera, and PPE if required. Carefully inspect the site layout, room dimensions, ceiling height, existing civil condition, service points, and access limitations. Record all relevant data in real-time. Taking accurate measurements and photos is crucial for later documentation. A proper site recce helps validate whether the proposed design is feasible and forms the base for planning and execution.

Step 3: Coordinate with Key Stakeholders

During the site recce, ensure clear coordination between the client's point of contact (POC), building representatives (if applicable), and internal design or installation teams. Each stakeholder brings valuable information that influences the project plan. Use this opportunity to ask technical questions, understand building restrictions, and confirm available service lines or infrastructure. Facilitating

coordination on-site ensures smoother communication, eliminates confusion, and lays the groundwork for aligned decision-making and collaborative problem-solving as the project progresses.

Step 4: Compile Observations and Measurements

After examining the site, optimize all data collected into categories—site layout, wall/floor condition, ceiling height, natural light, HVAC points, electrical load, plumbing lines, and access routes. Ensure that every measurement is accurate and traceable to a specific zone. Use sketches, annotated plans, and photo references for better clarity. These observations must be structured in a way that they can be directly referred to during design reviews, scope definition, or technical planning. Precision at this stage avoids errors later.

Step 5: Identify Gaps, Risks, and Recommendations

Compare the site conditions with client expectations to identify any mismatches or risks. For example, a client might want a false ceiling, but slab height limitations may pose challenges. Highlight such issues clearly, along with suitable alternatives or workarounds. Identifying risks early—like drainage issues or structural restrictions—helps prevent delays or cost escalations. Documenting both constraints and recommendations enables the project team to make informed design adjustments and set client expectations realistically and professionally.

Step 6: Draft the Recce Report in Standard Format

Prepare the recce report using a standard format that is clear, professional, and easy to interpret. The report should include project details, date, purpose, observations, measurements, photographs, issues identified, and your recommendations. Organise the report into sections based on zones or building services. Ensure all technical terms are accurately used. A well-structured recce report serves as a reference document for all stakeholders and is often used for project approvals, budgeting, and scheduling discussions.

Step 7: Review and Cross-Check the Report

Before submitting, thoroughly review the recce report to verify the accuracy of measurements, correctness of site observations, and clarity of recommendations. Check for missing information or contradictory notes. Attach all photos and sketches in the correct order. If required, share the draft report with senior team members or designers for input. A review step improves report quality, ensures alignment across departments, and eliminates avoidable errors, which could lead to miscommunication or design flaws later on.

Step 8: Submit the Report to the Supervisor on Time

Timely submission of the recce report is essential for uninterrupted project planning. Ideally, the report should be submitted within 24 to 48 hours of the site visit. Submit the final version via the approved communication channel—email or project management software—and confirm receipt by the supervisor or project head. Timely reporting builds credibility, supports smooth workflow, and enables quick decision-making. It also demonstrates your professionalism and responsibility in managing your role as an Interior designer.

Tips to Examine Recce Reports Based on Measurements and Survey Data

Following are some practical and professional tips to examine recce reports based on measurements and survey data:

1. **Cross-Verify All Key Measurements**
   - Check room dimensions, ceiling heights, wall lengths, and openings against existing floor plans or CAD drawings.
   - Validate the alignment of furniture zones, passage widths, and service areas.
   - Watch for inconsistent measurements or unusually rounded-off numbers—this may indicate errors or estimation.

2. **Compare Survey Data with Client Requirements**
   - Ensure the site conditions support the proposed design elements. For example, confirm that slab height can accommodate a false ceiling or that the server room has drainage provisions.
   - Mark items that require redesign, adjustment, or special coordination.

3. **Confirm Service Point Locations**
   - Check that all electrical DBs, sockets, switches, plumbing lines, and AC ducts are correctly marked with measurements and photos.
   - Ensure that load capacities, outlet positions, and water inlets match the design intent.

4. **Assess Accessibility and Material Movement Feasibility**
   - Review access points, staircases, service lifts, door widths, and material drop areas.
   - If not suitable, flag it early for modular design or phased delivery planning.

5. **Validate Site Conditions Through Photos**
   - Ensure every key measurement or condition mentioned in the report is supported with photo documentation.
   - Photos should be labeled or numbered and referenced in the report (e.g., “Photo 4 – electrical conduit entry point”).

6. **Identify Risks and Deviations Clearly**
   - Look for remarks related to dampness, uneven surfaces, structural cracks, or service conflicts.
   - Verify that the report includes recommended solutions or alternatives for such issues.

7. **Ensure Consistency and Professional Format**
   - Confirm that the report follows a logical structure (project overview, area-wise observations, measurements, photos, challenges, and suggestions).
   - Check for missing sections or incomplete data fields.

8. Clarify Doubts Immediately

- o If anything is unclear or contradictory (e.g., ceiling height says 3 m but photo shows duct obstruction), clarify with the person who conducted the recce.
- o Schedule a second visit if needed for re-measurement or technical clarification.

9. Check for Budget or Design Impact

- o Highlight anything that may impact the cost or scope—such as the need for demolition, load restrictions, or upgraded materials due to poor site conditions.

10. Use the Report as a Basis for Scope Finalization

- o Ensure that the report supports the preparation of the final scope of work, BOQs, and scheduling.
- o It should be detailed enough to allow informed design finalization and vendor coordination.

Summary

- Project details must be communicated effectively to clients using visual presentations, concept boards, and structured explanations to ensure clarity and client approval.
- Client presentations should reflect finalized layouts, color schemes, materials, lighting plans, and service zones, along with mood boards and product catalogues.
- Maintaining a record of meeting discussions through MOMs (Minutes of Meetings) ensures clarity, avoids miscommunication, and helps track design changes.
- Change requests must be managed systematically by reviewing feasibility, updating designs, obtaining approvals, and documenting each revision.
- Revised drawings should clearly highlight modifications using revision tags, cloud marks, or color codes for easy identification.
- A defined SOP for modification and approval of drawings ensures consistency, accountability, and timely client sign-offs.
- Drawing revision logs are essential to track changes, versions, dates, reasons for modification, and approval status.
- Maintaining revised drawings ensures site teams follow the latest version, thereby enhancing accuracy and reducing rework.
- Updated drawings support on-site safety, coordination, and post-project maintenance, acting as legal and operational references.
- The CAPA (Corrective and Preventive Action) process ensures errors in approved designs are rectified and similar issues prevented in the future through analysis, corrective steps, and documentation.

Exercise

1. During a client walkthrough, they request to shift a partition wall slightly to increase pantry size. What should you do first?
   a. Approve the request and execute directly
   b. Update the layout without informing anyone
   c. Document the change request and initiate design review
   d. Deny the change due to time constraints

2. Which of the following best describes the purpose of a Drawing Revision Log?
   a. To track financial approvals
   b. To record site inspection reports
   c. To log changes made to drawings with reasons and approval
   d. To maintain vendor lists

3. A design team revised the electrical layout but didn't update the drawing distributed to the contractor. What risk does this pose?
   a. Client confusion
   b. On-site execution errors
   c. Increase in material cost
   d. Faster approvals

4. A client says, "I didn't approve this material change." How can you avoid such situations?
   a. Only use verbal communication
   b. Maintain and share detailed Minutes of Meeting (MOMs)
   c. Avoid asking for approvals
   d. Allow team members to approve on client's behalf

5. What is the benefit of incorporating the CAPA process in design approvals?
   a. Speeds up drawing duplication
   b. Prevents furniture damage
   c. Ensures errors are corrected and not repeated
   d. Increases project cost

Hands-On Activity: Examine the Worksite for Measurement and Marking Accuracy

Objective: To enable learners to inspect and verify whether measurement and marking tasks at the site have been executed accurately and in accordance with specified layout instructions.

Materials Needed:

- Printed layout plan (furniture layout or electrical plan)
- Measuring tape or laser distance measurer
- Spirit level
- Sample site (actual room/marked floor or classroom simulation with chalk/tape lines)
- Monitoring checklist (provided)
- Notepad and pen

Instructions

1. Review the provided layout drawing and marking instructions.
2. Visit the assigned mock or real worksite where measurements and markings have been completed (floor lines, switchboard positions, furniture outlines, etc.).
3. Use measuring tools to cross-check actual markings against drawing dimensions.
4. Use the monitoring checklist to assess alignment, accuracy, and clarity of markings.
5. Identify and record at least:
    - o 2 correct markings that match the instructions
    - o 2 incorrect or questionable markings
6. Discuss with your trainer or peers how these errors could affect the next stage of work (e.g., electrical, carpentry).
7. Suggest corrective measures for any errors you find.

Sample Output Table:

Marking Area	Drawing Instruction	Actual Measurement	Correct/Incorrect	Remarks/Action Required
TV Unit wall width	1800 mm	1800 mm	Correct	None
Switchboard height	1200 mm from finished floor	1400 mm	Incorrect	Re-mark at correct height
Wardrobe left boundary	Starts 150 mm from window edge	Touching window frame	Incorrect	Re-align 150 mm away
Centerline of sofa wall	Aligned with room midpoint	Perfectly centered	Correct	Confirm with furniture vendor

Expected Outcomes:

- Interpret layout instructions and compare them with physical markings
- Identify errors in measurement and suggest practical corrections
- Understand how improper marking affects downstream tasks (e.g., electrical, carpentry, painting)

Scan the QR codes or click on the link to watch the related videos

https://www.youtube.com/watch?v=YX-3O82xEQ0

INTERIOR DESIGN - SITE ANALYSIS

https://www.youtube.com/watch?v=xHY2fVTvITI

HOW TO TAKE SITE MEASUREMENT

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

5. Client Deliberations and Market Research

Unit 5.1: Conduct Market Research and Trend Analysis
Unit 5.2: Client Deliberation

FFS/N0211

Key Learning Outcomes

At the end of this module, the participant will be able to:

1. Define the scope of work and its importance in project execution.
2. List various national and international market trends and technologies in interior designing.
3. State the role of market research during effective client deliberation and design finalization.
4. Illustrate the role of products and material catalogues in project client discussions.
5. List various documentation formalities associated with client deliberation and meetings.
6. Explain the process of preparing tentative scope of work based on client requirements.
7. Conduct market research based on initial client requirements for market trends and new technologies.
8. Employ suitable methods to evaluate the design specifications based on trends, styles, new products, materials, etc.
9. Explain the process of preparing and managing products and material catalogs.
10. Explain how to prepare a sample Minutes of Meeting (MOM).
11. Employ suitable documentation methods for record-keeping of client discussions.

UNIT 5.1: Conduct Market Research and Trend Analysis

Unit Objectives

At the end of this unit, the participants will be able to:

1. Define the scope of work and its importance in project execution.
2. List various national and international market trends and technologies in interior designing.
3. State the role of market research during effective client deliberation and design finalization.
4. Explain how to conduct market research based on initial client requirements for market trends and new technologies.
5. Explain the process of preparing tentative scope of work based on client requirements.

5.1.1 Scope of Work

The Final Scope of Work (FSOW) is a detailed and agreed-upon document that outlines the confirmed list of tasks, materials, services, deliverables, and timelines required to complete a project. It is finalized after site surveys, client consultations, and design approvals, and becomes the official project execution plan. Following are the key features of FSOW:

Fig. 5.1.1: Key Features of FSOW

Role of FSOW in Project Execution:

- **Guides All Activities:** FSOW serves as a reference for all vendors, contractors, and team members throughout execution.
- **Defines Deliverables:** It clearly states what will be built, installed, or delivered at each stage.
- **Enables Budget Control:** With confirmed quantities and material specifications, FSOW helps create an accurate cost estimate.

- **Supports Time Management:** It includes a work schedule, helping project managers track progress and meet deadlines.
- **Prevents Disputes:** Since FSOW is agreed upon by all stakeholders, it minimizes misunderstandings during execution.
- **Supports Quality Checks:** It includes quality expectations for workmanship, materials, and design compliance.

Sample Final Scope of Work (FSOW)

Project Title: Interior Fit-Out for ABC Solutions.

Site Location: 5th Floor, Omega Business Park, Andheri East, Mumbai

Project Type: Commercial Office Interior

Client: XYZ Solutions Pvt. Ltd.

Project Manager: [Name] –

Date of Finalization: 28 March 2025

1. Objective

To execute the complete interior fit-out work of XYZ Solution's new office space (4,000 sq. ft.), as per approved design and specifications, ensuring compliance with building norms, timelines, and quality standards.

2. Scope of Work

A. Civil and Demolition Works

- Removal of existing partitions and flooring in designated areas
- Leveling of floor surface
- Wall preparation and plaster touch-up where required

B. Partition and Carpentry Work

- **Fabrication and installation of:**
  - Reception Desk (custom-built)
  - Meeting Rooms with glass and gypsum partitions
  - Manager Cabins with acoustic panelling
- Open workstations for 40 employees using modular partitions
- Pantry storage units and server room rack

C. Electrical and Data Work

- Installation of new electrical points with DB and MCBs
- Concealed wiring for workstations, meeting rooms, and pantry
- Provision of LAN cabling (Cat-6) for 50 data points
- Installation of light fixtures, fans, UPS points

D. False Ceiling

- Grid ceiling in work area and meeting rooms (2x2 gypsum tile)
- Gypsum ceiling with cove lighting in reception and cabins
- Coordination with HVAC and sprinkler layout

E. Flooring

- Carpet tiles in the work area and meeting rooms
- Vitrified tiles in reception and pantry zones
- Vinyl flooring in server room

F. Painting and Finishing

- Two coats of putty, primer, and low-VOC emulsion paint for all internal walls
- Branded wall graphics at reception and breakout zone

G. Furniture

- Supply and installation of:
  - 40 modular workstations with chairs
  - 2 manager desks and 2 guest chairs each
  - Conference table with 10 chairs
  - Pantry table and stools
  - Lounge seating in breakout area

H. HVAC & Ventilation

- Supply and installation of 5 cassette AC units (2 tons each)
- Duct routing and air outlet adjustment as per new layout
- Exhaust fan installation in pantry

I. Miscellaneous Works

- Window blinds and soft furnishings
- Fire extinguisher mounting and emergency signage
- Site cleanup and handover in ready-to-occupy condition

Timeline

Activity	Duration	Start Date	End Date
Site Preparation	5 days	1 Apr 2025	5 Apr 2025
Civil & Electrical Work	10 days	6 Apr 2025	15 Apr 2025
Carpentry & Furniture	15 days	16 Apr 2025	30 Apr 2025
Final Finishing & Handover	5 days	1 May 2025	5 May 2025

Table. 5.1.1:

Total Project Duration: 5 Weeks

4. Exclusions

- Fire alarm panel and sprinkler system (handled by building management)
- Internet router and server configuration (by client's IT team)
- Signage on building exterior

5. Quality Standards

- All works to follow IS codes and site safety norms
- Approved materials and vendor specifications to be used
- Quality checks after each major phase with client sign-off

6. Approval Signatures

Name	Role	Signature	Date
[Client Name]	Client Representative		
[Your Name]	Assistant Project Manager		
[Design Lead Name]	Interior Design Consultant		

Table. 5.1.2:

5.1.2 Tentative Scope of Work (TSOW)

Tentative Scope of Work (TSOW) is the initial outline of the expected work to be carried out in a project. It is created during the initial planning or proposal stage, based on the client's early inputs, site visit assumptions, and conceptual discussions. TSOW helps in providing an estimated idea of the project's scale, requirements, and deliverables before detailed designs or technical drawings are finalised. Following are the key features of TSOW:



Fig. 5.1.2: key features of TSOW

Differentiate between Tentative Scope of Work (TSOW) and Final Scope of Work (FSOW)

Aspect	Tentative Scope of Work (TSOW)	Final Scope of Work (FSOW)
Definition	A preliminary outline of work based on client discussion and early assumptions	A finalized document with exact details after survey, design finalization, and client approval
When Prepared	At the proposal or planning stage	Before actual work begins, after recce and approvals
Level of Detail	General and flexible; subject to change	Detailed and specific; fixed for execution
Purpose	To estimate cost, feasibility, and resources needed	To execute the project accurately and as agreed
Basis	Initial discussions and concept drawings	Site surveys, confirmed drawings, material specs
Usefulness	Helpful for budgeting and client approval stages	Essential for contracting, execution, and monitoring
Changeability	Can be revised or updated	Changes allowed only through a formal variation order or change request

Table. 5.1.3:

Hands-on Exercise: Finalising the Scope of Work

Objective:

- Prepare a Final Scope of Work (FSOW) based on suggestions and modifications on Tentative Scope of Work (TSOW).

Instruction

1. Read the Tentative Scope of Work (TSOW) given below.
2. Review the list of modifications and site recce observations.
3. Using these inputs, prepare a Final Scope of Work (FSOW) document.
4. Organise your FSOW under standard headings (e.g., Objective, Description of Work, Materials, Timeline, Exclusions).

   Deliverable: Typed or handwritten FSOW (max 2 pages)

TSOW

- **Project:** Startup Office Interior Design

  Location: 2nd Floor, Galaxy Tech Park, Bengaluru

  Office Size: 2,000 sq. ft.

  Client: NexGen Analytics Pvt. Ltd.
- Design theme: Minimalist + Collaborative
- Workstations: Approx. 20 in open-plan layout
- Manager cabin x 1
- One small meeting room (6-seater)
- Pantry counter with basic storage
- Carpet flooring in office area
- Lighting: LED panel lights
- False ceiling across full office
- Tentative timeline: 4–5 weeks
- Materials: Standard commercial-grade finishes
- Exclusions: AC, Server room setup

Site Recce Observations and Client Modifications:

1. Site Condition:

- Slab height is low (only 9 ft). False ceiling not feasible across the full area.
- One column near the meeting room zone affects layout.
- Entry point narrower than expected — restricts delivery of large furniture pieces.

2. Client Feedback:

- Increase seating to 24 workstations (with 2 hot desks).
- Prefer exposed ceiling concept with suspended lighting in work zone.
- Change flooring to vinyl planks for easy maintenance.
- Add dry erase wall paint in meeting room.
- Branding wall requested near reception.
- Soft closure cabinets preferred in pantry.

- Timeline fixed: Must be completed in 5 weeks.

Task:

Prepare the Final Scope of Work (FSOW) for this project, incorporating the updated site observations and client inputs. Use the following headings:

Final Scope of Work (FSOW) Template – Headings to Use

1. Project Title and Details
2. Objective of the Project
3. Scope of Work – Area-wise or Task-wise
4. Key Materials and Finishes
5. Timeline and Work Schedule (Week-wise or Phase-wise)
6. Constraints and Considerations
7. Exclusions
8. Approvals and Sign-Off Fields (optional)

5.1.3 Market Trends and Technologies in Interior Designing

Market research plays a critical role in interior design by enabling professionals to understand client needs, industry trends, and material availability. It helps designers make informed decisions, offer relevant options, and align design proposals with the client's expectations, budget, and lifestyle.

During client deliberation, market research allows the designer to present design concepts supported by current style trends, cost-effective materials, and innovative technologies. This not only builds client confidence but also speeds up the decision-making process by showcasing practical and appealing alternatives.

In the design finalization stage, research insights guide the selection of vendors, finishes, furniture, and fittings that are trendy, durable, and within budget. Designers also use market data to predict lead times, evaluate sustainable options, and assess material performance. By referencing current market information, designers ensure that the final design is both relevant and feasible, enhancing client satisfaction and project efficiency.

Importance of Regular Market Research in the Identification of Different Types of Materials Based on Project Feasibility

Regular market research is essential for interior designers to stay updated with the availability, pricing, quality, and trends of different materials. It enables professionals to make informed choices that align with the project's scope, budget, aesthetic goals, and functional requirements.

Market research helps in identifying new and alternative materials that may offer better performance, sustainability, or cost-effectiveness. For example, discovering a new range of engineered wood or recycled tiles can help reduce project costs while maintaining design quality. Research also helps compare vendors, assess warranties, and understand installation requirements.

By tracking market fluctuations in material costs, designers can adjust specifications to remain within the client's budget. For example, if marble prices rise unexpectedly, designers can propose a high-quality quartz alternative with a similar finish. This adaptability ensures feasibility without compromising on design intent.

Moreover, research is vital when working on specialized projects (e.g., sustainable design, acoustics, or moisture-prone areas), where materials must meet technical standards. It helps identify certified, regulation-compliant, or locally available solutions, ensuring smoother procurement and timely execution.

In short, regular market research empowers designers to balance aesthetics, functionality, and budget—making it a cornerstone of project feasibility and success.

Let us understand with the help of a scenario.

Scenario:

An interior designer is working on a mid-budget commercial café project. The client wants a rustic look with natural wood finishes throughout the space, including tabletops, wall panels, and shelving. However, during the initial material inquiry, the designer discovers that the price of natural teakwood has increased significantly due to limited supply and high demand.

Market Research Application:

Instead of exceeding the client's budget or compromising on quality, the designer conducts fresh market research and identifies a laminated engineered wood product that mimics the appearance of teak but is more cost-effective, sustainable, and easier to maintain. The designer also discovers a local supplier offering this material with quick delivery and customization options.

Outcome:

- The client is happy with the proposed alternative, both aesthetically and financially.
- The project stays within budget and timeline.
- The final design meets the rustic theme without compromising durability.

This scenario highlights how regular market research allows designers to quickly identify suitable alternatives when material availability or cost becomes a challenge—ensuring the project remains feasible and aligned with client expectations.

Activity: Conduct Market Research Based on Initial Client Requirements for Market Trends and New Technologies

Objective:

To develop the ability to identify relevant market trends, materials, and technologies based on a given client brief, and to present suitable options that align with client preferences and project feasibility.

Scenario:

You are an interior designer approached by a client who wants a modern, sustainable home office setup with smart features, within a moderate budget. The client is open to using eco-friendly materials and is interested in new technologies that improve comfort and energy efficiency.

Instructions

1. **Understand the Client Brief:**
    - Style: Modern

- Focus: Sustainability and smart technology
- Budget: Moderate
- Application Area: Home office (approx. 150 sq. ft.)

2. **Conduct Market Research:**
   - Identify 3–4 current trends in modern and sustainable interior design.
   - List 2–3 new technologies suitable for home offices (e.g., smart lighting, automated blinds).
   - Explore 3 material options that are eco-friendly and cost-effective (e.g., bamboo boards, recycled tiles, low-VOC paint).
3. **Prepare a Research Report or Presentation:**

   Include:
   - Design Trends Identified
   - Technology Features & Their Benefits
   - Material Options with Specifications and Estimated Costs
   - Names of vendors/sources (web or local)
   - Visual references (images or mood board)
4. **Presentation (Group or Individual):**
   - Present your findings in a 5-minute mock client meeting format.
   - Justify your choices based on client needs, feasibility, and design relevance.

Tools/Resources Required:

- Internet or vendor catalogues
- Design magazines or portals (optional)
- MS Word/Excel/Google Slides or physical chart paper

UNIT 5.2: Client Deliberation

Unit Objectives

At the end of this unit, the participants will be able to:

1. Identify the role of products and material catalogues in project client discussions.
2. Explain the process of preparing and managing products and material catalogues.
3. List various documentation formalities associated with client deliberation and meetings.
4. Identify suitable methods to evaluate the design specifications based on trends, styles, new products, materials, etc.
5. Explain how to prepare a sample Minutes of Meeting (MOM).
6. Employ suitable documentation methods for record-keeping of client discussions.
7. Explain the role of effective notes making techniques in maintaining client data.
8. Explain the process of managing client requirements using effective notes making techniques

5.2.1 Role of Product and Material Catalogues

In interior design projects, products and material catalogues play a critical role during discussions with clients. They serve as a visual and technical reference that helps both the designer and the client make informed decisions about finishes, fixtures, fittings, and styles. Due to following factors, the Product and Material Catalogues is important in Client Discussions:

Fig. 5.2.1: Role of Product and Material Catalogues

- **Visual Representation of Options:** Material and product catalogues provide clients with a clear, visual understanding of available finishes, textures, colors, and patterns. Instead of relying on verbal descriptions, clients can view actual samples or high-quality printed references to better visualize how the material will look when installed. This reduces ambiguity, helps avoid miscommunication, and leads to quicker and more confident decision-making during discussions.
- **Standardization and Comparison:** Catalogues enable clients to compare multiple brands and product types side by side. This includes differences in specifications, pricing, warranties, finishes, and durability. Whether it is for laminates, tiles, lighting fixtures, or sanitaryware, catalogues offer a structured format for evaluating options systematically, which aids in selecting the best value for their design and budget.
- **Facilitates Informed Decision-Making:** With the help of catalogues, clients can evaluate materials based on multiple parameters—such as aesthetics, maintenance requirements, lifespan, and cost. Technical datasheets and specifications in product catalogues support objective assessment and ensure that selections are both visually appealing and functionally appropriate for the intended space.
- **Supports Design Alignment:** Catalogues help the Assistant Interior Designer guide clients toward selections that are aligned with the approved design concept, layout, and theme. For example, a selected wall tile must complement the furniture finish and paint palette. Using catalogues ensures all elements come together cohesively as per the design intent.
- **Helps Set Realistic Expectations:** Product catalogues also provide essential information about stock availability, delivery timeframes, pricing slabs, and installation requirements. This allows clients to make decisions that are not just design-friendly but also practical within the project's timeline and budget, reducing future dissatisfaction or delays.
- **Assists in Scope and BOQ Finalization:** Once materials are selected using catalogues, these choices are directly referenced in the preparation of the Bill of Quantities (BOQ) and material procurement list. Each specification—such as brand, model, size, and finish—can be accurately listed, allowing for seamless coordination with vendors and contractors.
- **Builds Client Confidence and Trust:** When catalogues are used professionally during meetings, it reinforces the designer's credibility and preparedness. Clients appreciate the transparency and attention to detail, which builds trust and improves the overall client experience. It also shows that material decisions are being made with both aesthetics and technical soundness in mind.

For Example: During a residential kitchen discussion, an Assistant Interior Designer shows three laminate options from a branded catalogue. The client chooses a matte walnut finish after comparing it with glossy and textured options. This choice is recorded and included in the final scope of work and procurement list.

Steps Involved in Preparing and Managing Catalogues



Fig. 5.2.2: Process of Preparing and Managing Catalogues

1. **Understanding Project Requirements:** Start by reviewing the approved design layout, style, theme, and material specifications of the project. This helps identify the type of products or finishes needed—such as wood finishes, lighting options, tiles, fabrics, or sanitaryware.
2. **Collecting Product Information from Vendors:** Reach out to reliable vendors and suppliers to collect updated catalogues, brochures, swatches, and technical datasheets. Ensure that catalogues cover essential information such as product images, size, material, finish, price range, installation details, and lead time.
3. **Organizing Catalogues by Category:** Classify and arrange products into logical categories—like flooring, wall finishes, lights, loose furniture, hardware, etc. Maintain both physical files and digital folders (PDFs, Excel lists) with proper labels and filters for easy retrieval during client meetings.
4. **Shortlisting Based on Project Constraints:** Shortlist product options based on design requirements, client preferences, site conditions, and budget constraints. This helps avoid presenting unsuitable options during meetings and streamlines the selection process.
5. **Preparing Client-Ready Presentation Kits:** Curate the selected product samples or catalog pages into presentation kits or mood boards. These kits may include physical samples (e.g., laminate swatches, tiles) or digital slide decks showcasing the best options with brand and price references.
6. **Managing Version Control and Updates:** Regularly update the catalogues to reflect changes in availability, pricing, or discontinued products. Maintain a version control system so outdated material is not mistakenly presented to clients or teams.
7. **Maintaining Vendor Contact Logs:** Create and manage a database of vendor contacts along with notes on each vendor's specialization, credit terms, delivery timeline, and past reliability. This helps in quick coordination during procurement and installation.

5.2.2 Documentation Formalities

Documentation formalities for record-keeping client inputs and requirements refers to the organized process of collecting, storing, and managing all relevant information provided by the client throughout the duration of a project. This process ensures that all client feedback, preferences, and requirements are properly recorded and tracked. Its purpose is to have clear, accurate, and accessible records that can be referred to at any stage of the project for clarification, decision-making, or future reference.

The documentation formalities for record-keeping client inputs and requirements are:

- **Client Profile:** Collect and maintain essential client details such as name, contact information, preferred communication methods, and any special preferences.
- **Project Brief:** Document the client's initial project description, including their design goals, style preferences, functional requirements, and expectations for the final outcome.
- **Client Requirements Document**: Clearly record all specific client requirements related to the project, such as budget, timeline, and any unique specifications (e.g., materials, sustainability goals).
- **Meeting Notes**: Document the outcomes of each meeting with the client, including discussions, decisions, feedback, and any action items or follow-ups.
- **Design Approval Documents:** Record the approval of design concepts, sketches, layouts, and any revisions. This ensures that the client's preferences are properly documented and agreed upon.
- **Communication Logs:** Maintain a detailed log of all communications with the client (emails, phone calls, and messages), ensuring that any verbal agreements or informal requests are captured.
- **Change Requests:** Keep a record of any changes or modifications requested by the client during the project. This includes any adjustments to design, scope, timeline, or budget, along with the client's approval.
- **Budget and Cost Estimates:** Document all financial discussions, estimates, and final approvals. Include a breakdown of materials, labor, and additional costs to ensure alignment with the client's budget.
- **Timeline and Milestone Documents:** Record the project timeline, key milestones, and deadlines. Document any adjustments to the schedule based on client feedback or project changes.
- **Client Sign-offs:** Maintain records of formal sign-offs from the client at each stage of the project, including design approvals, final selection of materials, and final acceptance of deliverables.
- **Contracts and Agreements:** Store all signed contracts, terms of agreement, payment schedules, and any legal documents that outline the project's terms and conditions.
- **Risk Management Records:** Document any potential risks identified during the project and any client-approved risk mitigation strategies or contingency plans.
- **Client Feedback and Satisfaction Surveys:** Record any client feedback or survey responses regarding the project's progress, design, or overall experience, ensuring any concerns are addressed.
- **Post-Project Review and Handover Documentation:** Keep records of the final review with the client, including final approvals and project handover. Include any maintenance or warranty information provided.
- **Final Payment and Invoice Records:** Document all payment transactions, including final invoices, receipts, and any outstanding payments, to ensure clear financial records are kept.

By maintaining these documentation formalities, you can ensure smooth project execution, proper management of client requirements, and effective communication. These records also provide protection in case of disputes or future reference.

5.2.3 Managing Notes Efficiently

Managing notes in an efficient manner is essential for ensuring smooth project execution, helps in keeping all relevant information organized, improves communication, and ensures accountability. Proper note management reduces errors, saves time, and ensures that all decisions and actions are clearly documented for easy reference throughout the project lifecycle.

1. **Accurate Record-Keeping:** Efficiently managed notes ensure that important information, decisions, and action items are accurately recorded. This prevents misunderstandings and ensures that all team members are aligned with the client's requirements and project goals.
2. **Easy Access to Information:** When notes are organized and managed well, they can be easily accessed when needed. This is crucial for referencing past discussions, reviewing project changes, or verifying decisions made in meetings.
3. **Improved Productivity:** Well-maintained notes allow quick retrieval of key information, saving time and effort that would otherwise be spent searching for documents or clarifying past conversations. This increases productivity and minimizes delays.
4. **Clear Communication:** Properly managed notes ensure that communication is clear, especially when multiple team members or stakeholders are involved. They can be referred to during meetings or when updates are needed, helping to avoid repeated discussions.
5. **Tracking Progress and Accountability:** Notes help track the progression of decisions, client feedback, and tasks. It becomes easier to hold team members accountable for their responsibilities and ensures that deadlines and deliverables are met.
6. **Legal and Compliance Protection:** Well-organized notes can serve as a reference in case of disputes, clarifying what was agreed upon or discussed. This provides protection for both the business and the client.
7. **Efficient Follow-up:** With efficient notes, it's easy to remember follow-up actions and tasks, making sure that nothing important is overlooked, and that deadlines are met.

Notes-Keeping Technique

Notes-Keeping Techniques refer to the overall system of recording, organizing, and managing notes in an effective and structured manner, ensuring that information is easily accessible, accurate, and actionable. Effective notes-keeping is crucial for managing client requirements and project details efficiently. Following are some techniques to maintain organized, accurate, and accessible notes:

Fig. 5.2.3: Notes-Keeping Technique

1. **Structured Templates:** Use structured templates for meeting notes, which include sections such as date, attendees, agenda items, discussion points, action items, and follow-up tasks. This ensures that important details are captured consistently.
2. **Digital Tools:** Utilize digital note-taking tools like OneNote, Evernote, or Google Docs to organize, store, and access notes. These tools allow for easy editing, searching, and sharing of notes with team members or clients.
3. **Color Coding and Highlighting:** To make important information stand out, use color coding or highlight key points, action items, or deadlines. This makes it easier to quickly locate and prioritize tasks.
4. **Clear and Concise Language:** Write notes in clear, concise language to avoid ambiguity. Avoid unnecessary jargon and focus on the key points, decisions, and action items to ensure clarity and quick understanding.
5. **Categorization:** Organize your notes into categories based on project phases (e.g., design, budget, client meetings) or client segments. This helps keep the notes organized and makes it easier to refer to them at a later stage.
6. **Review and Revise:** Regularly review and update your notes after meetings. This ensures that all information is accurate and up to date. If changes occur, promptly make the necessary revisions.
7. **Cloud Storage:** Store notes in cloud-based storage to ensure easy access and backup. This helps maintain records even if your local device is lost or damaged, providing a secure and reliable backup system.

By using these techniques, notes can be kept organized, accessible, and effective for managing project tasks, client feedback, and important decisions, contributing to successful project execution.

Minutes of Meeting (MoM)

Minutes of Meeting (MoM) are official written records of discussions held during client or internal meetings. In interior design projects, MoMs help document decisions, design approvals, pending tasks,

and responsibilities. Well-prepared MoMs ensure clear communication, accountability, and reference for follow-ups.

Sample Minutes of Meeting (MoM)

Project: 2BHK Residence Interior Design – Sunshine Apartments

Date: 12 June 2025

Time: 11:00 AM – 12:15 PM

Venue: Client's Residence

Purpose: Material and Layout Finalization for Living Room

Attendees:

- Mr. Rakesh Sharma – Client
- Ms. Priya Mehta – Interior Designer
- Mr. Amit Jain – Site Engineer
- Ms. Rekha Verma – Assistant Interior Designer

Meeting Discussion and Action Points

Agenda / Discussion Point	Decision Taken / Comments	Action Required	Responsible Person	Deadline
Living room laminate finish	Matte Walnut finish (Greenply) approved by client	Confirm order with vendor	Assistant Designer	14 June 2025
Electrical socket position (TV wall)	Socket to be shifted 300 mm right due to TV unit redesign	Update electrical layout drawing	Site Engineer	13 June 2025
False ceiling light points	4 ceiling spotlights approved as per revised plan	Coordinate with electrician	Assistant Designer	15 June 2025
Sofa fabric selection	Beige linen fabric (D'Décor) approved	Send fabric code to vendor	Interior Designer	13 June 2025
Next meeting schedule	Site visit for bedroom layout approval	Share calendar invite	Assistant Designer	14 June 2025

Table. 5.2.1:

Remarks:

Client expressed satisfaction with the material samples presented. Requested a digital 3D view of the living room with the finalized finishes.

Prepared by:

Ms. Rekha Verma

Assistant Interior Designer

Date of Issue: 12 June 2025

Summary

- Final Scope of Work (FSOW) is a detailed and approved project plan outlining all tasks, deliverables, materials, and timelines. It helps manage budget, time, and quality while minimizing disputes.
- Tentative Scope of Work (TSOW) is a preliminary version based on initial client inputs and assumptions. It is later refined into FSOW after site recce and client confirmation.
- Market Research helps interior designers stay updated with national and international trends, vendor pricing, material options, and technologies relevant to client needs and budgets.
- Market research plays a critical role during client deliberation and design finalization, offering data-driven options that align with budget, aesthetics, and feasibility.
- Using product and material catalogues supports visual representation, comparison, decision-making, and alignment with the approved theme and budget constraints.
- Product catalogues help finalize the Bill of Quantities (BOQ) and promote transparency during discussions, building client trust.
- Designers must document all client interactions, including preferences, approvals, meeting notes, and changes, to ensure clarity and maintain project records.
- Proper note-keeping enhances productivity, communication, and legal protection by tracking decisions, tasks, and follow-ups across the project lifecycle.
- Digital tools like OneNote, Google Docs, and structured templates ensure accessible and organized record-keeping.
- Minutes of Meeting (MoM) are official written records of discussions held during client or internal meetings. In interior design projects, MoMs help document decisions, design approvals, pending tasks, and responsibilities.

Exercise

Activity: Analyze and Approve Design Specifications for Project Execution

Objective:

To practice evaluating and approving project-related specifications before execution.

Basic Steps:

- Review the Design Brief
- Study Submitted Drawings and Layouts
- Examine Material Samples and Finish Boards
- Check Against Project Scope and Budget
- Validate Technical Feasibility (MEP/Safety)
- Incorporate Stakeholder Feedback

4. Technical Validation (MEP / Safety / Compliance)

Validated By (Team/Consultant)	
Scope of Validation	
Remarks/Changes Suggested	
Approval Date	

5. Final Client Approval

Approval Provided By	
Date of Approval	
Signature	
Comments (if any)	

6. Vendor Coordination

Material/Service Approved	
Vendor Name	
PO Issued?	
Delivery Timeline	

7. Change Control Log (If Any)

Date	Change Description	Initiated By	Approved By	Status

Hands-On Exercise: Demonstrating Effective Notes-Keeping Technique

You are attending a meeting with a potential client, Priya Sharma, for her residential project. During the meeting, you will need to take structured, organized notes that will help you recall and reference important details in future interactions, keep the project on track, and ensure clear communication with your team and the client.

Tasks to be performed:

- Design a template for meeting notes that includes:
  - Date and time
  - Participants
  - Agenda items
  - Discussion points
  - Action items and deadlines
  - Client feedback or decisions
  - Follow-up tasks
- Fill out the template during the meeting, ensuring all key points are covered and recorded.
- After the meeting, sort notes into relevant categories such as Design, Budget, Timeline, etc.
- Identify action items and deadlines from the notes.
- Use color coding or bold text to make them stand out.
- At the end of each meeting or weekly, review the notes.
- Update with new tasks, deadlines, and developments.
- Ensure action items are assigned and followed up on.
- Store notes in digital tools like OneNote, Evernote, or Google Docs for easy access.
- Keep the notes organized by client or project.
- Backup all digital notes using cloud storage (e.g., Google Drive, Dropbox).

- If using paper notes, scan them and save the digital copies.
- After each meeting, summarize the key points and action items.
- Share notes with stakeholders via email or project management tools.

Materials Required:

- Meeting Notes Template (Digital or Printed)
- Digital Tools (e.g., OneNote, Google Docs, Evernote)
- Cloud Storage (Google Drive, Dropbox)
- Email or Project Management System (for sharing notes)
- Markers or Highlighters (for color-coding action items)

Notes

Scan the QR codes or click on the link to watch the related videos

https://www.youtube.com/watch?v=YX-3O82xEQ0

AI for Interior Design

6. Project Budgeting and Execution Planning

FURNITURE & FITTINGS SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

UNIT 6.1: Project Planning and Timeline Management
UNIT 6.2: Need Assessment and Estimation
UNIT 6.3: Project Documentation and Approvals

FFS/N0211

Key Learning Outcomes

At the end of this module, the participant will be able to:

1. List various tools and software's for project planning.
2. Explain various elements involved in calculating a project timeline.
3. State the importance of need assessment in a project execution.
4. Explain various features of a project budget and how to calculate them.
5. Describe the role of the Final Scope of Work (FSOW), Material Sheet, and Detailed Design Instructions in the project approval process.
6. Demonstrate the preparation of project timelines and work schedules using appropriate tools.
7. Calculate the workforce and material requirements for project execution.
8. Demonstrate the process of preparing requisite documents for project approval.

UNIT 6.1: Project Planning and Timeline Management

Unit Objectives

At the end of this unit, the participants will be able to:

1. List various tools and software's for project planning.
2. Explain various elements involved in calculating a project timeline.
3. Explain how to prepare of project timelines and work schedules using appropriate tools.

6.1.1 Tools and Software for Project Planning

Project Planning: Introduction

Project planning is the process of defining the scope, objectives, tasks, timelines, resources, and budget necessary to complete a project successfully. It involves creating a roadmap that guides the project team through various stages of execution while ensuring deliverables are met within time and cost constraints. Effective project planning helps manage risks, allocate resources efficiently, and track progress against defined goals.

Tools and Software for Project Planning

For an interior designing firm, the ideal project management tool should support design workflows, client communication, visual task tracking, timeline scheduling, and collaboration among designers, procurement teams, vendors, and site supervisors.

Following are some of the commonly used project management tools well-suited for interior design firms:

Fig. 6.1.1: Commonly used project management tools well-suited for interior design firms

1. **Trello:** It is a visual, Kanban-style task manager that's great for design workflows and client projects.

Use Case: An interior design firm can use Trello boards for each project, with cards representing tasks like concept creation, client feedback, material selection, and site execution.

2. **Monday.com:** It is a highly customizable work management tool that integrates timelines, tasks, automation, and team collaboration.

Use Case: Teams can plan a commercial interior project by creating columns for budget, timelines, vendor updates, client approvals, and progress trackers—all in one dashboard.

3. **Asana:** It is a project planning and team collaboration platform that supports task dependencies, Gantt timelines, and client feedback.

Use Case: Asana can help a design team track space planning, material procurement, coordination with electricians and carpenters, and weekly client reviews.

4. **ClickUp:** It is an all-in-one platform for tasks, documents, goals, timelines, and time tracking. It is useful for firms managing multiple clients and projects.

Use Case: An interior design firm working on residential, commercial, and retail projects can set up separate workspaces with shared calendars, design file uploads, and task tracking.

5. **Smartsheet:** It combines the familiarity of Excel with project management features like Gantt charts, automation, and team collaboration.

Use Case: Ideal for firms that work with procurement and inventory planning. Designers can track vendor delivery schedules, furniture specs, and installation plans.

6. **Houzz Pro:** It is tailored for interior designers and architects, it offers tools for project planning, invoicing, mood boards, and client communication.

Use Case: Designers can share concept boards with clients, get feedback, prepare quotes, and manage the full project lifecycle from the same platform.

7. **Studio Designer:** It is a specialized platform for interior design businesses offering features like product sourcing, accounting, project tracking, and client dashboards.

Use Case: Can be used to handle client budgets, vendor orders, project timelines, and invoicing all customized for the design workflow.

6.1.2 Elements Involved in Calculating a Project Timeline

When calculating a project timeline, one should be primarily concerned with how long the project will take and in what sequence tasks must occur. This process requires considering multiple factors such as the scope of work, task dependencies, available resources, and potential risks. An accurate timeline is essential to ensure that all project activities are completed on schedule and within budget.

Following are the key elements involved in calculating a project timeline:



Fig. 6.1.2: Key elements involved in calculating a project timeline

1. Project Scope and Deliverables

The project scope defines the boundaries of what is to be done, including deliverables, features, and end outcomes. Without a clear scope, time planning becomes speculative and disorganized. The scope allows project managers to estimate how much work is involved and to set clear expectations for all stakeholders.

For Example: In an interior design project, the scope may include space planning, lighting design, furniture layout, and final styling of the space.

2. Work Breakdown Structure (WBS)

The Work Breakdown Structure breaks the overall project into smaller, manageable components or tasks. Each level of the WBS drills down into more specific activities. This approach is crucial for time estimation because it allows planners to assess the duration of each subtask individually.

For Example: "Furniture Installation" can be broken down into "Vendor coordination," "Transport," "Assembly," and "Quality Check."

3. Activity List and Sequencing

This involves preparing a list of all the tasks needed to complete the project and arranging them in logical order. Tasks often have dependencies, where one task must be completed before another can begin. Proper sequencing helps prevent delays and inefficiencies.

For Example: Electrical wiring must be completed before installing a false ceiling to avoid damage or rework.

4. Activity Duration Estimation

Each task in the activity list must be evaluated to estimate how long it will take. Duration estimation is typically done using expert judgment, historical data, or industry benchmarks. Accurate estimation allows for realistic scheduling and efficient resource use.

For Example: Based on previous projects, installing modular kitchen cabinets might take 3–5 working days.

5. Resource Allocation

The time required to complete tasks depends significantly on the availability and skill level of resources such as manpower, equipment, or materials. More resources can reduce task duration, while limited availability may cause delays.

For Example: If a project has two carpenters instead of one, the woodwork installation can be completed in half the time.

6. Task Dependencies

Dependencies describe the relationship between tasks—specifically, which tasks need to happen before or after others. These relationships are categorized as Finish-to-Start (FS), Start-to-Start (SS), Finish-to-Finish (FF), and so on. They are critical for identifying project sequences and delays.

For Example: Painting can only start after wall putty and sanding are completed (Finish-to-Start dependency).

7. Critical Path Method (CPM)

The Critical Path Method is a scheduling technique used to identify the longest path of dependent

tasks in a project. This path determines the minimum time required to complete the project. Delays in critical path activities directly impact the project deadline.

For Example: If floor tiling, furniture delivery, and installation are all on the critical path, delay in any of these will delay the project handover.

8. **Milestones**

   Milestones are significant checkpoints in the project timeline with zero duration. They help mark progress and enable stakeholders to monitor key phases of the project. Milestones often represent approvals, phase completions, or legal sign-offs.

   For Example: "Client approval of 3D renders" is a milestone that must be completed before execution begins.

9. **Buffers or Contingency Time**

   Buffers are additional time allowances added to the schedule to manage risks, unforeseen delays, or changes in scope. Contingency time ensures that the project remains on track even when things do not go as planned.

   For Example: A buffer of 2 days might be added after furniture delivery to account for possible transit delays.

10. **Calendar and Constraints**

    Every timeline must consider the working calendar, including weekends, holidays, and non-working hours. Constraints such as client deadlines, site access limitations, or regulatory permissions must also be factored in.

    For Example: If a client requires the project to be completed before Diwali, all tasks must be scheduled backward from that date, considering public holidays and working hours.

6.1.3 Designing Work Timelines and Schedules

Designing work timelines and schedules means planning the sequence of tasks, deciding how long each task will take, and fixing when each task should start and finish during a project. It helps in managing time, resources, and responsibilities in an organised way.

In interior design projects, there are many activities such as layout planning, material selection, vendor coordination, installation, and client approvals. Each task needs to be completed in a specific order and within a specific time. This planning is done through a project timeline and schedule.

A good timeline shows what work will be done, by whom, and by when. It allows the team to track progress, avoid delays, and complete the project within the agreed deadline. It also helps the client stay informed and involved in key stages like approvals and handovers. Following are the elements involved in designing work timelines and schedules



Fig. 6.1.3: Elements involved in designing work timelines and schedules

The following Gantt chart represents the timeline for an interior design project. It visually represents the tasks, their sequence, start times, and durations to understand how to design and manage project schedules:



Fig. 6.1.4: Sample Gantt Chart

UNIT 6.2: Need Assessment and Estimation

Unit Objectives

At the end of this unit, the participants will be able to:

1. State the importance of need assessment in a project execution.
2. Explain various features of a project budget and how to calculate them.
3. Calculate the workforce and material requirements for project execution.

6.2.1 Importance of Need Assessment in a Project Execution

Need assessment is the process of identifying and understanding the requirements, expectations, and constraints of a project before execution begins. It forms the foundation of successful project planning and delivery by ensuring that the project aligns with client objectives and site realities.

The importance of need assessment is as follows:



Fig. 6.2.1: Importance of Need Assessment

1. **Defines Project Goals Clearly**

   Need assessment helps clarify what the client wants to achieve through the project. It ensures alignment between the client's vision and the design or execution plan.

   Example: A client may prioritize a minimalist style with natural lighting, which influences layout and material choices.

2. **Ensure Scope Control**

   By documenting client needs in detail, project teams can avoid frequent changes during execution, saving time and cost.

   Example: If the number of workstations in an office fit-out is identified early, the design can be finalized without last-minute additions.

3. **Enables Accurate Planning and Budgeting**

   Understanding what is needed helps in creating realistic budgets and timelines, and selecting the right materials and resources.

   Example: A need assessment might reveal the requirement for custom-built furniture, which affects both cost and delivery time.

4. **Helps Identify Site Constraints Early**

   During need assessment, a site visit or analysis may uncover structural issues, space limitations, or legal requirements.

   Example: Discovering poor ventilation during assessment may lead to the inclusion of mechanical exhaust systems in the plan.

5. **Supports Better Client Communication**

   It provides a documented baseline of client expectations, which can be referred to during project discussions and decisions.

   Example: If a client later requests changes, the initial need assessment helps evaluate how the new request affects scope and timeline.

6. **Enhances Design and Execution Quality**

   A thorough understanding of needs allows for tailored, functional, and aesthetically pleasing design solutions.

   Example: For a retail store, understanding customer traffic flow during need assessment can influence the placement of display counters.

Hence, a well-conducted need assessment ensures that project execution is grounded in client requirements, site realities, and practical constraints. It minimizes risks, streamlines decision-making, and increases the chances of delivering a project on time, within budget, and to the client's satisfaction.

6.2.2 Project Budget

Calculating Project Budget Parameters Based on Project Execution Requirements

To calculate the budget for any interior design project, you must estimate the total cost required for successful execution. This is done by identifying key components of the project and assigning approximate or actual costs to each item. Following are the steps to calculate budget parameters:



Fig. 6.2.2: Project Budget Parameters

Formula (Basic):

Total Project Budget = Material Cost + Labour Cost + Vendor Charges + Transport + Design Fees + Contingency

Cost Variance and its Importance

Cost variance refers to the difference between the planned (budgeted) cost and the actual cost incurred during project execution. It is a key indicator of how well the project is being financially managed. For example: If you budgeted ₹1,50,000 for furniture but actually spent ₹1,80,000, the cost variance is ₹30,000 (unfavourable). Cost Variance benefits in the following ways:



Fig: 6.2.3: Cost Variance benefits

Sample budget sheet				
Category	**Estimated Cost (₹)**	**Actual Cost (₹)**	**Variance (₹)**	**Remarks**
Civil Work & Flooring	2,50,000	2,70,000	=2,50,000–2,70,000 = –20,000	Vinyl upgrade; client request
False Ceiling	1,50,000	1,50,000	=1,50,000–1,50,000 = 0	On budget
Electrical & Lighting	1,20,000	1,10,000	=1,20,000–1,10,000 = +10,000	Negotiated bulk discount with vendor
Furniture & Fixtures	3,00,000	3,05,000	=3,00,000–3,05,000 = –5,000	Custom orders added
Painting & Finishes	80,000	95,000	=80,000–95,000 = –15,000	Rework due to colour change

HVAC & Networking	1,00,000	98,000	=1,00,000–98,000 = +2,000	Savings on duct routing
Miscellaneous Fittings	50,000	55,000	=50,000–55,000 = –5,000	Extra grab bars for ICU
Design & Supervision Fees	70,000	70,000	=70,000–70,000 = 0	Fixed professional fee
Contingency (10%)	80,000	75,000	=80,000–75,000 = +5,000	Unused buffer
Total	**11,00,000**	**11,28,000**	**11,00,000–11,28,000 = –28,000**	**Overall overrun by ₹28,000**

Table. 6.2.1:

- Variance formula: Budgeted Cost – Actual Cost
  - o A positive variance (e.g., +₹10,000) means you're under budget.
  - o A negative variance (e.g., –₹20,000) means you're over budget.

Steps Involved in Incorporating Cost Changes During Project Execution

During execution, costs can change due to client revisions, vendor delays, or material rate changes. Managing these changes properly is important to stay on track.

Steps to Incorporate Cost Changes:

1. Identify the Reason for Change
   – Is it due to scope change, material upgrade, labour rate increase, or delay?
2. Calculate the Revised Cost
   – Estimate how much more (or less) the new choice will cost.
3. Discuss with Client and Get Approval
   – Always take client consent before increasing the budget.
4. Update the Project Budget Sheet
   – Modify the affected line item in the cost sheet with new figures.
5. Document the Change
   – Maintain written records (email or signed note) as proof of cost change and approval.
6. Adjust Timeline and Resources if Needed
   – If the cost change delays the project, update the schedule too.
7. Track and Monitor New Cost
   – Keep an eye on whether the new cost stays within the revised estimate.

Let us go through the following case study to understand project budgeting parameters:

Case Study: Interior Design Project for a Private Hospital (2000 sq. ft.)

Scenario: An interior design firm was hired to redesign the interiors of a 2000 sq. ft. private hospital. The hospital included:

- Reception and waiting area
- 2 OPD rooms
- 1 ICU
- Nurse station
- Pantry
- Restrooms

The client had a budget of ₹12 lakhs and a strict timeline of 40 working days.

Execution Plan:

Scope of Work

- Zoning and layout planning as per hospital regulations
- Use of anti-bacterial finishes, non-slip flooring, and high-durability materials
- Modular furniture installation for OPD and nurse station
- False ceiling with concealed lighting and AC ducting
- Accessible restrooms and compact pantry

Team Availability

- 1 interior designer
- 1 project manager
- 2 carpenters
- 1 electrician
- 1 painter
- 1 civil team (outsourced)

Budget Estimation (Initial)

Category	Estimated Cost (₹)
Civil work & flooring	2,50,000
False ceiling	1,50,000
Lighting & electrical	1,20,000
Furniture	3,00,000
Painting	80,000
HVAC & Networking	1,00,000

Table. 6.2.2:

Misc. fittings	50,000
Design fees	70,000
Contingency (10%)	80,000
Total	**11,90,000**

Table. 6.2.3:

Issues During Execution:

- The client requested vinyl flooring instead of regular tiles mid-project, increasing the cost by ₹40,000.
- The false ceiling vendor delayed delivery, causing a 3-day extension.
- The painting team had to do a re-coat due to a colour mismatch (added ₹15,000).

Budget Revisions & Cost Variance

Category	**Actual Cost (₹)**	**Variance (₹)**	**Reason**
Flooring	2,90,000	+40,000	Material upgrade (vinyl)
False ceiling	1,50,000	0	On budget
Painting	95,000	+15,000	Rework due to colour mismatch
Total Variance	+55,000		

Table. 6.2.4:

Steps Taken to Manage Cost Changes:

1. Informed the client of each change and took written consent.
2. Adjusted budget allocations to avoid overshooting the final budget by more than 5%.
3. Used buffer days to accommodate false ceiling delay.
4. Updated the cost sheet and submitted it to the client at project close.

Suitable Tools to Prepare a Project Budget

Preparing a project budget involves estimating and recording the expected costs of various tasks, materials, labour, and overheads. To do this efficiently and accurately, interior designers can use a variety of tools and software that help in planning, calculating, tracking, and revising budgets throughout the project lifecycle. Following table lists the Commonly used Tools for Budget Preparation in Interior Design Projects

Tool	Purpose/Use	Examples
Spreadsheets	To create item-wise cost estimations, auto-calculate totals, and track variance	Microsoft Excel, Google Sheets
Estimation Software	Pre-built modules for material, labour, and overhead cost calculations	EasyEstimator, Buildxact
Project Management Tools	Combine budget with scheduling, resource, and task tracking	Microsoft Project, Monday.com
Interior Design Software	Includes cost calculation for space design, materials, and furnishings	SketchUp Pro with Estimator plugin, AutoCAD with cost tagging
Accounting Software	To maintain financial records, invoices, and expense tracking	Tally ERP, QuickBooks
Mobile Apps for On-Site Estimation	Quick estimation tools for vendors and site managers	MagicPlan, Coohom, Houzz Pro

Table. 6.2.5:

When and How to Use These Tools

- **Start with Excel or Google Sheets**

  Create a budget format that includes category-wise cost heads, estimated cost, actual cost, variance, and remarks.

- **Use Estimation Software**

  For medium to large projects, use tools that include price databases, rate analysis, and vendor quotes.

- **Integrate with Design Software**

  If working in SketchUp or AutoCAD, link your 3D layouts to quantity and cost estimators.

- **Track Budget Continuously**

  Use project management tools to regularly update expenses, monitor usage, and compare with planned budget.

Activity 1: Estimating Material Cost and Requirement

Objective: Demonstrate the process of estimating material cost and requirement for budget calculation.

Scenario:

You have to redesign the interiors of a 2BHK flat (Living Room, Bedroom, Kitchen). The client has requested cost-effective but durable finishes. You must prepare a material requirement and cost estimate based on the following:

- Total Area: 750 sq. ft.
- Finish: Laminated furniture, vitrified tiles, emulsion paint

- Furniture: 1 wardrobe, 1 TV unit, 1 modular kitchen

Tasks to Perform:

1. **List All Required Materials**

   e.g., plywood, laminates, handles, hinges, paint, tiles

2. **Calculate Material Quantities**

   Based on room sizes and design scope. Example:

   o Wardrobe: 4 sheets of 18mm plywood

   o Paint: 12 litres for one bedroom

3. **Find Unit Prices (Use Market Averages)**

   Use catalogues, vendor rates, or sample price sheets.

4. **Prepare a Cost Table**

   Create a column-wise table:

Item	Quantity	Unit Price (₹)	Total Cost (₹)
Plywood 18mm	10 sheets	₹1,200	₹12,000
Emulsion Paint	15 litres	₹250	₹3,750
...	...	...	...

Table. 6.2.6:

5. **Calculate Total Estimated Material Cost**

6. **Present Your Sheet for Peer or Facilitator Review**

Outcome:

A material estimate table that includes quantities, unit costs, and total material cost for budgeting.

Activity 2: Track the Budget: Identify Cost Variance in an Ongoing Project

Objective: Evaluate the financial performance during project execution using the cost variance process.

Scenario:

You are mid-way through a 4-week office interior fit-out project. The initial planned budget was ₹9 lakhs. Your team will now review 5 cost categories and identify where variances occurred.

Tasks to Perform:

1. **Refer to the Planned vs Actual Data Sheet (provided by facilitator)**

Category	Planned Cost (₹)	Actual Cost (₹)	Total Cost (₹)
Flooring	1,50,000	1,70,000	₹12,000
False Ceiling	1,00,000	90,000	₹3,750
Electrical Work	1,30,000	1,50,000	...
Painting	80,000	80,000	
Furniture	2,20,000	2,40,000	

Table. 6.2.7:

2. **Calculate Cost Variance for Each Category**

   Formula: CV = Budgeted Cost – Actual Cost

3. **Identify Overruns or Savings**

   Mark which categories are under/over budget.

4. **Discuss Reasons for Variance**

   e.g., delay, rework, material upgrade, wrong estimation

5. **Summarize Project's Financial Performance**

Was the project financially healthy? What corrective steps would you take?

Outcome:

A written analysis report/table highlighting:

- Total cost variance
- Insights into financial gaps
- Suggestions to manage costs better

UNIT 6.3: Project Documentation and Approvals

Unit Objectives

At the end of this unit, the participants will be able to:

1. Describe the role of the Final Scope of Work (FSOW), Material Sheet, and Detailed Design Instructions in the project approval process.
2. Demonstrate the process of preparing requisite documents for project approval.

6.3.1 Role of Final Scope of Work (FSOW), Material Sheet, and Detailed Design Instructions in the Project Approval Process

The project approval process involves presenting finalized documentation to clients or approving authorities to confirm that the proposed work aligns with agreed expectations, technical feasibility, and budgetary constraints. Three key documents play a vital role in this process:

a. **Final Scope of Work (FSOW):** As learnt in previous module, it outlines all agreed deliverables, design elements, services, and project boundaries in detail. It ensures all stakeholders have a shared understanding of what will be done, by whom, and within what timeframe. It serves as the foundation for project approval and contract finalization.

   For Example: In a residential interior project, FSOW may specify modular kitchen design, false ceiling in all bedrooms, and matte-finish wall paint in the living room.

b. **Material Sheet:** It lists all approved materials, finishes, colors, brands, and specifications for each element in the design. It ensures client has visibility into material quality, cost, and availability before project execution begins.

   For Example: A material sheet might list 600x600 mm vitrified tiles in beige finish for flooring, acrylic modular kitchen shutters, and wall-mounted WCs in all bathrooms.

c. **Detailed Design Instructions:** These are the execution-ready drawings, sketches, installation notes, and design interpretations provided to the contractor and on-site teams. It facilitates accurate on-site implementation and minimizes ambiguity during execution.

   For Example: Includes electrical layout, carpentry joinery details, tile laying patterns, and elevation drawings.

Together, these documents form the basis for project sign-off, client approval, and execution readiness. They also protect against disputes or delays caused by scope confusion.

6.3.2 Process of Preparing Requisite Documents for Project Approval

The preparation of documents for project approval involves a structured workflow to ensure accuracy, completeness, and alignment with client expectations. Following steps are involved in the process of preparing requisite documents for project approval:

Fig. 6.3.1: Process of Preparing Requisite Documents for Project Approval

Summary

- Interior design firms commonly use tools like Trello, Asana, ClickUp, and Houzz Pro to visually manage tasks, timelines, client communication, and procurement workflows.
- Calculating a timeline involves defining scope, creating a Work Breakdown Structure, sequencing tasks, estimating durations, allocating resources, and using methods like Critical Path Analysis.
- Creating a schedule includes defining tasks, assigning resources, visualizing in Gantt charts, and identifying milestones like design approvals and site handovers.
- Identifying client needs, expectations, and site conditions before execution is crucial to control scope, improve budgeting, and align deliverables with the client's vision.
- A typical budget includes components like material costs, labor, vendor charges, and contingency. Tools like Excel, Tally, and SketchUp plugins help manage these effectively.
- Cost variance measures the difference between budgeted and actual expenses. Positive variance indicates savings; negative means overspending.
- During project execution, changes should be documented, cost impact calculated, and client approvals obtained to update budgets and timelines.
- Project Approval Documents include:
    - Final Scope of Work (FSOW) – clearly lists deliverables and timelines.
    - Material Sheet – confirms specs, colors, and brands.
    - Detailed Design Instructions – guides on-site execution with layouts and elevations.
- Designers use spreadsheets for estimates, project management tools to monitor, and apps like Houzz Pro for quoting and procurement integration.

Exercise

1. A client for a 3BHK renovation project requests a material upgrade midway, increasing your budget. What should you do FIRST?
   a. Adjust the project deadline automatically
   b. Revise the drawings silently
   c. Calculate the revised cost and get client approval
   d. Inform your painter

2. You are halfway through a commercial fit-out. Your team realizes electrical work is delayed, which is a critical path task. What is the impact?
   a. Only electrical work is delayed
   b. Entire project completion may get delayed
   c. Budget is unaffected
   d. You can skip other tasks

3. Which of the following would be listed in a Material Sheet for client sign-off?
   a. Gantt chart timeline
   b. Design team salary
   c. Laminate brand and finish
   d. Weekly attendance sheet

4. Why is Need Assessment conducted before execution?
   a. To skip design fees
   b. To decorate the client's office
   c. To align project with client requirements and constraints
   d. To cancel the project

5. While preparing a budget sheet for a hotel lobby design, you realize the material quantity for marble flooring was underestimated. What should you do to manage this issue?
   a. Ignore the change and continue execution
   b. Add the extra cost silently to labor charges
   c. Update the material estimate and reflect the change in FSOW and BOQ
   d. Wait till client notices the overrun

Hands-on Activity: Project Plan & Timeline for Commercial Space Design

Objectives

1. Prepare a project plan based on the given project timeline, schedules, and team availability.
2. Demonstrate the process of preparing work timelines and schedules based on the effective demarcation of materials and resources.

Scenario

You have been assigned to design the interiors of a co-working space located in a commercial building in Bengaluru. The space is 1,800 sq. ft. and includes:

- A reception and lounge area
- 2 private cabins
- A 10-seater conference room
- Open workstations for 15 people
- Pantry area and restrooms

Client Requirements

- Modern, functional design with neutral colour palette
- Basic acoustic treatments for cabins and conference room
- Fast execution within 45 working days
- Budget of ₹22 lakhs
- Preferred vendors already selected for furniture and lighting
- Team available: 1 Site Manager, 2 Carpenters, 1 Electrician, 1 Painter, 1 Civil Supervisor

Tasks to be Performed

1. **Study the Case Brief**

   Read the scenario and note down the scope, budget, timeline, and team details.

2. **Prepare a Detailed Project Plan**

   Include:

   - Project scope and zoning
   - Sequence of design and execution tasks
   - Estimated durations for each task
   - Team allocation based on skill and availability
   - Budget allocation across tasks (block estimate format)

3. **Break Down the Work into Activities**

   Example activities:

   - Site measurement and layout finalisation

- Partition work (cabins, conference room)
- Electrical wiring and networking
- False ceiling and lighting installation
- Painting and finishing
- Modular furniture installation
- Pantry and restroom setup
- Final cleaning, walk-through, and handover

4. **Identify Task Dependencies and Resources**
   - Which task depends on another?
   - What materials are needed at each stage?
   - Plan based on vendor delivery schedules.

5. **Create a Work Timeline and Schedule Chart**
   - Include task names, start/end days, buffer time
   - Represent in a Gantt-style or tabular chart

6. **Define Key Milestones**
   - Completion of civil work
   - Design approval
   - Handover preparation
   - Final walkthrough with client

7. **Submit and Present Your Project Plan**

   Prepare a short explanation (2–3 minutes) of your project strategy and timeline.

Expected Deliverables

- A written project plan
- A table or visual work timeline
- A task-resource-material matrix
- A summary/presentation note

Notes

Scan the QR codes or click on the link to watch the related videos

https://www.youtube.com/watch?v=1jAVFCH0Siw

Time Management

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

7. Design Project Drafts, Mood Boards, and Models

UNIT 7.1: Mood Boards, 3D Renders, and Miniature Models Development
UNIT 7.2: Project Presentation and Change Request

FFS/N0211

Key Learning Outcomes

At the end of this module, the participant will be able to:

1. List various Computer-Aided Design (CAD) software for project designing based on the area of application.
2. Explain the working and use of common CAD software like 3DS Max, SketchUp, Revit, etc.
3. List the common design drafting and sketching software available.
4. Explain the working and use of common drafting softwares like AutoCAD, Coral Draw, Photoshop, etc.
5. Describe various elements involved in mood board designing.
6. State the role and importance of mood board elements in project design and approval.
7. Explain the importance of miniature models in the project designing process.
8. Explain the importance of presenting project details in an effective way to clients.
9. Explain the requisites involved in managing a change request.
10. Demonstrate the process of developing 3D renders and models using appropriate Computer-Aided Design (CAD) software.
11. Examine the design drafting and sketching process based on specified specifications.
12. Prepare a mood board based on specified specifications.
13. Demonstrate the process of creating miniature models using given design specifications.
14. Prepare a client presentation based on project details for client deliberations.
15. Perform modification in the proposed drawings/designs based on suggested changes.

UNIT 7.1: Mood Boards, 3D Renders, and Miniature Models Development

Unit Objectives

At the end of this unit, the participants will be able to:

1. List various Computer-Aided Design (CAD) software for project designing based on the area of application.
2. Explain the working and use of common CAD software like 3DS Max, SketchUp, Revit, etc.
3. List the common design drafting and sketching software available.
4. Explain the working and use of common drafting softwares like AutoCAD, Coral Draw, Photoshop, etc.
5. Describe various elements involved in mood board designing.
6. State the role and importance of mood board elements in project design and approval.
7. Explain the importance of miniature models in the project designing process.
8. Demonstrate the process of developing 3D renders and models using appropriate Computer-Aided Design (CAD) software.
9. Prepare a mood board based on specified specifications.
10. Demonstrate the process of creating miniature models using given design specifications

7.1.1 Mood Boards, 3D Renders, and Miniatures

Mood Boards

A mood board is a visual presentation that captures the essence of a design concept using a curated collection of images, colors, textures, materials, typography, and objects. In interior design, it acts as a creative guide to translate a client's vision or design theme into tangible, visual elements before actual execution begins.

Fig. 7.1.1: Sample Mood Board for a Bathroom

Elements of Mood Boards for an Interior Design Project

Fig. 7.1.2: Elements of a mood board

- **Material & Finishes:** Its purpose is to present the physical textures and surface finishes to be used in the space. It includes fabric swatches, tiles, flooring samples (wood, stone, laminate), wallpaper or paint texture, upholstery samples etc.

Fig. 7.1.3: Material and Finishes

This image presents a well-curated collection of materials and finishes:

- **Wood samples:** Light oak, dark teak, and polished veneer for flooring and furniture
- **Textile swatches:** Upholstery and curtain fabric in warm neutrals
- **Tiles:** Patterned ceramic tile and smooth marble for accent walls or coffee table tops
- **Color cards:** Neutral tones to complement fabric and wood selection
- **Colour Palette:** Its purpose is to establish a harmonious set of colours that will unify the space visually. It includes following elements: It includes, primary, secondary, and accent colours, wall paint chips, tone variations and coordinated colour groupings with images.

Fig. 7.1.4: Colour Palette

The image uses a green-focused palette to evoke freshness and calmness:

- **Colour Swatches**: A gradient of greens — mint, sage, moss, forest, and deep olive
- **Decor Coordination:** Matching throw pillow, framed botanical art, and green textured fabrics
- **Furniture Highlight:** A green armchair to anchor the scheme
- **Textures:** Loop pile carpet, felt finish, and weaves in shades of green

Furniture & Accessories: Its purpose is to showcase the proposed furniture pieces, fixtures, and styling elements. It includes sofas, chairs, tables, beds, lighting fixtures, Frames, rugs, baskets, decor items like vases or mirrors. It helps visualize the scale, form, and style compatibility before selection and purchase.

Fig. 7.1.5: Furniture and Accessories

This image reflects a refined and luxurious modern living room setup:

- **Sofa:** A sleek, beige three-seater with black metal legs for a minimalist profile
- **Accent Chair:** A plush, rounded boucle chair for comfort and elegance
- **Coffee Table:** High-gloss white marble top with black cylindrical base
- **Lighting:** Matte black sculptural floor lamp and woven designer pendant
- **Accessories:** Abstract art, matte ceramic vase, black woven rug, minimalist mirror

Styling: Its purpose is to set the ambiance, décor style, and final look of the space through soft elements. It includes plant styles, art prints, cushions, throws, lamps and curtains, and room images styled with final layers

Fig. 7.1.6: Styling

This captures final-layer styling elements that complete the aesthetic:

- Sofa Styling: Soft beige sofa with textured throw pillows and cozy blanket
- Accessories: Framed botanical art, sculptural lamp, and potted indoor plants
- Decor Accents: Rattan pendant light, neutral woven rug, and terracotta accent pillow
- Color Palette: Earthy tones, emphasizing calm, warmth, and balance

Role of Mood Boards in Interior Designing and Execution

Mood boards serve as a bridge between imagination and implementation of the ideas. Their role includes:



Fig. 7.1.7: Role of mood Board

Digital tools to create Mood Boards are as follows:

- Canva
- Adobe Photoshop / Illustrator
- PowerPoint (basic digital mood board)

Steps to Design a Mood Board

Following are the steps to design a mood board:

Step	Description
1. Understand the Client Brief	Define the space, user needs, function, and preferred aesthetics.
2. Choose the Mood or Theme	Determine whether the space will feel modern, bohemian, minimalist, rustic, etc.
3. Research Visual References	Collect inspiration from online platforms, magazines, sample books, etc.

4. Select Key Elements	Finalize visuals for flooring, furniture, textiles, lighting, colors, and decor.
5. Organize Layout	Arrange selected elements in a balanced, visually appealing grid or layout.
6. Annotate Elements	Label items like “fabric”, “wall finish”, “accent color” for clarity.
7. Review and Revise	Get feedback from the team or client, and update accordingly.
8. Finalize and Present	Share printed or digital versions for approval and future reference.

Table. 7.1.1:

Steps to Create a Mood Board Using Canva



https://www.canva.com/create/mood-boards/



Fig.7.1.8:

Ensure that the mood board matches the budget, functional needs, and space constraints of the project. It should not only be aesthetically pleasing but also practical.

3D Renders

3D renders are highly realistic or semi-realistic digital visualizations that represent interior spaces as they will appear after execution. These renders are created from 3D models using computer software and include materials, lighting, furniture, and textures to create lifelike images of a designed space.

They help interior designers and clients visualize the final outcome of a space before it is physically built.



Fig. 7.1.9: 3D Renders in SketchUp

Image courtesy: https://youtu.be/qw-WPpd97JE

Role of 3D Renders in Interior Design and Execution

3D renders play a strategic role in both the creative and execution phases of a design project:

In the Design Phase:

Visual Clarity	Translates abstract ideas into clear, tangible visuals
Client Presentation	Helps clients understand the spatial layout and design concept
Concept Validation	Offers a way to test different materials, colors, and furniture before finalizing

Fig. 7.1.10: Role of 3D Renders in Design Phase

Design Approval
Used as visual proof for client and stakeholder sign-off

Technical Coordination
Guides contractors, vendors, and site teams

Marketing & Portfolio
Useful for showcasing projects to prospective clients or in promotional material

Avoids Errors
Reduces chanses of mismatch in expections vs execution

Fig.7.1.11: Role of 3D Renders in Design Phase

Tools Used for 3D Modelling and Rendering

To create high-quality 3D renders in interior design, professionals rely on a combination of 3D modeling software and rendering engines:

Modeling Software:

- SketchUp – User-friendly and ideal for quick modeling and layout planning
- AutoCAD 3D – Used for precise technical modeling with architectural accuracy
- Revit – BIM-based tool preferred for detailed architectural and interior design
- 3ds Max – Advanced modeling tool with strong capabilities for complex surfaces and forms

Rendering Engines:

- V-Ray – Industry standard for photorealistic rendering with light and material controls
- Lumion – Real-time rendering with drag-and-drop materials and lighting presets
- Enscape – Lightweight plug-in for real-time walkthroughs and immersive VR integration
- Twinmotion – Interactive visualization tool known for fast, high-quality outputs

These tools allow designers to produce detailed 3D environments with precise materials, lighting, and furniture layouts offering clients a realistic preview of the final space.

Steps to Create 3D Renders (Using a Tool like SketchUp + V-Ray)

Step 1: Create or Import 2D Layout

- Prepare a floor plan in AutoCAD or draw directly in SketchUp/Revit.
- Ensure correct scale and measurements.

Step 2: Build the 3D Model

- Use a 3D modeling tool (e.g., SketchUp, Revit, 3ds Max) to build the structure:
  - Add walls, doors, windows, ceiling, floor levels
  - Model built-in furniture or partitions

Step 3: Add Furniture and Fixtures

- Insert furniture components from model libraries or import custom models
- Position accessories like lamps, shelves, curtains, plants, etc.

Step 4: Apply Materials and Textures

- Use material libraries to assign finishes:
  - Wood flooring
  - Wall paint
  - Upholstery fabrics
  - Metal or marble surfaces

Step 5: Set Up Lighting

- Add artificial lighting (pendants, downlights, floor lamps)
- Set natural light based on window placement and time of day

Step 6: Position Camera and Viewpoints

- Fix angles that showcase the space clearly (top view, eye-level perspective, corner view)

Step 7: Render the Scene

- Use a rendering engine (e.g., V-Ray, Lumion, Enscape) to:
  - Apply high-quality lighting effects
  - Generate shadows and reflections
  - Output images in high resolution

Step 8: Post-Processing (Optional)

- Open final image in Photoshop or similar software to:
  - Adjust brightness, contrast, or sharpness
  - Add sky backgrounds, people, or branding overlays

Hands-On Activity: Create a 3D Render for a Living Room Using SketchUp

Objective:

To design and visualize a realistic living room layout by creating a 3D render using a modeling tool like SketchUp + V-Ray.

Activity Overview:

Scenario:

You are designing a modern living room for a small apartment. The space should include:

- One 3-seater sofa
- One armchair
- Coffee table
- TV unit or shelf
- Rug, lighting, and indoor plant
- Optional: A feature wall or artwork

Tools Required:

- SketchUp (free or Pro version)
- V-Ray for SketchUp (or Enscape/Lumion if available)
- Pre-downloaded furniture models from SketchUp's 3D Warehouse
- Measuring scale or sample 2D plan (provided by trainer)

Steps:

Part 1: Modeling in SketchUp

1. **Draw the Room Layout**
   - Dimensions: 5m x 4m
   - Height: 3m
   - Add wall thickness, openings (1 door, 1 window)
2. **Model the Furniture**
   - Insert pre-made sofa, coffee table, and chair
   - Add carpet, pendant light, floor lamp, and shelf
3. **Apply Materials and Textures**
   - Choose wood, fabric, and paint finishes
   - Apply to walls, furniture, and flooring
4. **Set the Lighting**
   - Use both natural (from window) and artificial lights
   - Ensure one main light source is above the coffee table

Part 2: Rendering with V-Ray

5. **Position the Camera**
   - Set 2 key viewpoints: one corner shot and one straight-on shot
6. **Adjust Lighting in V-Ray**
   - Tweak sun intensity and ambient light
   - Set exposure, white balance, and render quality
7. **Render the Image**
   - Save your image in JPEG or PNG format (min. 1920x1080 resolution)

Ensure the following will performing the activity:

- Accurate modeling and layout
- Use of appropriate furniture
- Realistic textures and materials
- Lighting and shadows
- Quality of final render image

What Are Miniatures?

Miniatures, also called scale models, are small-scale physical representations of an interior space or structure. They visually and tangibly demonstrate the spatial layout, proportions, materials, and overall design intent before the actual execution begins.

They are typically built using foam boards, card stock, acrylic sheets, wood, and other materials to represent flooring, walls, furniture, and decor at a reduced scale (e.g., 1:50 or 1:100).

Fig. 7.1.12: Miniature

Role of Miniatures in Interior Designing and Execution

In the Design Phase:

Visual Clarity	Helps both designers and clients grasp spatial relationships and aesthetics
Client Presentation	Used to pitch or showcase design ideas, especially in academic or competition settings
Concept Validation	Allows for testing furniture placement, circulation, and functionality

Fig. 7.1.13: Role of Miniatures in Design Phase

Construction Reference

Assists contractors in understanding spatial hierarchy and material layering

Client Approvals

Acts as a reference model to gain client confidence

Material & Color Coordination

Simulates how different textures and finishes will appear together

Fig. 7.1.14: Role of Miniatures in Execution Phase

Steps Involved in Designing Drafts of Miniatures

The following table represent the basic steps involved in designing drafts of miniatures:

Step	Description
1. Prepare Scaled Drawings	Use AutoCAD or manual drafting to create top and elevation views at 1:50 or 1:100 scale
2. Select Model Materials	Choose foam board, mount board, cardboard, wood sheets, acrylic, etc.
3. Print & Cut Templates	Use printouts or scaled sketches to trace and cut out floor, walls, furniture elements
4. Assemble Components	Join walls and floors with glue or adhesive tape to create a 3D structure
5. Add Finishes & Textures	Apply color paper, textures, and tiny props to simulate finishes
6. Detail the Interiors	Add miniature furniture, curtains, plants, lights to bring realism
7. Label & Present	Add zone labels, signage, or circulation arrows if required

Table. 7.1.2:

Tools for Miniature Design

Digital Drafting Tools:

- AutoCAD – To draft precise scale layouts and elevations
- SketchUp / Rhino – To build digital models that can be converted into physical ones
- Revit – For BIM-based interior space modeling
- Illustrator / CorelDRAW – To create laser-cut layout templates

Fabrication Tools:

- Laser Cutter – Cuts model components from acrylic, foam board, or MDF
- 3D Printer – For precise mini furniture or decor pieces
- Cutting Tools – Craft knife, steel ruler, cutting mat

Now a days, 3D Printers are commonly used in creating miniature models

3D printers can produce precise, scaled-down replicas of:

- Furniture elements

Fig. 7.1.15: 3D Printer - Chair

Image Courtesy: https://everythingverysmall.com/how-to-create-miniatures-with-3d-printing-for-beginners-a-step-by-step-tutorial/

- Decor items (lamps, vases, partitions)



Fig. 7.1.16: 3D Printer - Vase

- Full rooms or structures (walls, floors, modules)

Fig. 7.1.17: 3D Printer – Room Miniature

Image Courtesy: https://cdnb.artstation.com/p/assets/images/images/043/640/849/large/javier-mora-img-20211017-145346.jpg?1637842967

These components are printed using materials like PLA, ABS, or resin and then assembled to form a detailed physical model.

Common Workflow for 3D Printing Miniatures



Fig. 7.1.18:

Hands-On Activity

Title: Visualizing Interior Design Concepts through Mood Boards, Miniatures, and 3D Renders

Objectives

- Develop a mood board aligned with client-approved design specifications
- Construct a basic miniature/model representing spatial layout and elements
- Create a realistic 3D render using design software

Scenario:

A client has approved the design concept for a modern living room (or selected space). Your task is to translate the approved design into three visual formats:

1. A Mood Board that captures the style and materials
2. A Miniature Model that shows spatial arrangement
3. A 3D Render that visualizes the final outcome

Task

Part 1: Mood Board Creation

Objective: Visually represent the design style, materials, and color scheme.

Instructions:

1. Review the approved design brief (dimensions, theme, palette)
2. Use Canva or Photoshop (or a physical board) to:
    - Include color swatches, material samples, inspiration photos, and textures
    - Arrange and label elements clearly
3. Present the board digitally or as a printout

Tools:

- Canva / Photoshop / Physical board
- Magazines, fabric swatches, material printouts (for physical version)

Part 2: Miniature Model Making

Objective: Construct a scale model (e.g., 1:50) of the approved space.

Instructions:

1. Use the scaled layout to cut wall and floor templates
2. Assemble the miniature using foam board/cardboard
3. Add furniture blocks and basic detailing (optional: use 3D printed components)
4. Label zones or features if needed

Tools & Materials:

- AutoCAD (for plan), foam board, craft knife, ruler, glue
- Optional: 3D printer, laser cutter for advanced output

Part 3: 3D Rendering

Objective: Develop a digital 3D render of the interior space.

Instructions:

1. Model the space in SketchUp / Revit / 3ds Max
2. Add furniture, lighting, materials, and textures
3. Use V-Ray / Lumion / Enscape to render the scene
4. Save 2 high-quality rendered views

Tools:

- SketchUp + V-Ray or any equivalent modeling/rendering suite

UNIT 7.2: Project Presentation and Change Request

Unit Objectives

At the end of this unit, the participants will be able to:

1. Explain the importance of presenting project details in an effective way to clients.
2. Explain the requisites involved in managing a change request.
3. Examine the design drafting and sketching process based on specified specifications.
4. Prepare a client presentation based on project details for client deliberations.
5. Perform modification in the proposed drawings/designs based on suggested changes.

7.2.1 Importance of Presenting Project Details

Presenting project details clearly and effectively is essential in establishing trust, ensuring alignment, and securing approvals from clients. It goes beyond just showcasing the design; it involves communicating the plan, scope, cost, and execution strategy in a way that is transparent, professional, and easy to understand. Following are the key reasons that highlights the importance of effective project presentation:

Fig. 7.2.1: Importance of effective project presentation

1. **Builds Client Confidence and Trust:** A well-structured presentation with accurate drawings, material samples, and execution plans shows the client that the team is organized and reliable.

   Example: Presenting a Gantt chart with clearly defined timelines reassures the client that deadlines are being tracked and managed professionally.

2. **Clarifies Expectations and Reduces Miscommunication:** Detailed presentations reduce ambiguity. Clients can visualize the outcome and understand deliverables, leading to fewer disputes later.

   Example: A 3D walkthrough video helps clients see how their living room will look post-completion, reducing confusion over color, lighting, or layout.

3. **Facilitates Faster Decision-Making:** When options and plans are presented clearly, clients are more likely to approve designs, materials, and timelines without delay.

   Example: Side-by-side comparison of material samples with price differences helps clients quickly choose the best-fit option.

4. **Enables Better Budget Control:** Clear presentation of cost estimates, BOQs, and material specifications ensures the client is aware of financial commitments at each stage.

   Example: A detailed cost breakdown sheet allows clients to adjust selections based on budget without affecting design intent.

5. **Enhances Client Engagement and Collaboration:** An interactive presentation format, such as a digital dashboard or shared cloud folder, allows clients to stay involved and give feedback in real time.

   Example: Clients may comment on mood boards or material swatches shared via tools like Trello or Houzz Pro.

6. **Supports Documentation and Approval:** Properly presented documents such as the FSOW, material sheet, and detailed design drawings become part of the contractual agreement and protect both parties.

   Example: Once approved, these documents serve as the official reference during execution and inspections.

7.2.2 Requisites Involved in Managing a Change Request

In project execution, especially in interior design, change requests are common and may arise due to client feedback, site conditions, budget revisions, or material availability. Managing change requests efficiently is critical to avoid delays, cost overruns, and miscommunication. Following are the key requisites for managing a change request:



Fig. 7.2.2: Key requisites for managing a change request

- Formal Documentation of Request: The change must be recorded using a formal Change Request Form or email, specifying what needs to be altered. For Example: The client wants to replace laminate shutters with acrylic finish in the kitchen.
- Evaluation of Impact: Assess how the change affects cost, timeline, design integrity, or procurement. For Example: Acrylic shutters may increase costs by 20% and delay delivery by 5 days.
- Internal Team Review: Consult with design, procurement, and site teams to confirm feasibility. For Example: Check if the new material fits within structural and design limits.
- Client Approval and Sign-Off: Present the revised plan or estimate to the client and take written approval before implementation. For Example: The client signs the revised BOQ and timeline.
- Revision of Project Documents: Update the FSOW, drawings, material sheet, and budget to reflect the change. It helps in maintain version control of all documents.
- Communication to Execution Teams: Notify vendors, contractors, and site supervisors about the approved change with revised instructions. For Example: Issue a site memo for updated material delivery and installation process.
- Record and Track: Maintain a change log including reasons, dates, impact, and approvals. It helps in billing, quality checks, and final audits.

7.2.3 Design Drafting and Sketching Process Based on Specified Specifications

Design drafting and sketching is the foundation of interior project visualization and execution. It converts concepts and client inputs into measurable and actionable design instructions, ensuring that what's imagined can be accurately built. Following are the steps involved in the design drafting and sketching process:

1. **Understanding Specifications:** Start by reviewing the client-approved scope, material choices, space dimensions, and service layouts.
    - **Example:** The design brief specifies a Scandinavian-style bedroom with white oak flooring and pastel finishes.
2. **Concept Sketching:** Rough hand-drawn sketches are created to experiment with layouts, aesthetics, and space functionality.
    - **Example:** Sketching three different wardrobe placements and bed orientations.
3. **Detailed Drafting:** Using software like AutoCAD, create dimensioned 2D drawings—layout plans, elevations, and sections.
    - **Example:** Floor plan with dimensions for furniture, wall sockets, and lighting points.
4. **Material and Color Integration:** Add notes or layers showing material specifications, textures, and color palettes as per the client's approval.
    - **Example:** Highlight areas for textured wall panels, laminate codes, or tile placements.
5. **Incorporation of Service Layouts:** Overlay plumbing, electrical, HVAC, and lighting plans to ensure coordination with the design layout.
    - **Example:** Ensuring light fixtures align with false ceiling design.
6. **Client Review Drafts:** Create print-ready drawings for review, supported with 3D views or mood boards if necessary. Take feedback and iterate.
7. **Final Construction Drawings:** Once approved, convert the drawings into GFC (Good for Construction) format for site execution.
    - **Example:** Issuing final tile laying pattern and plumbing point drawings to the contractor.

Sample Drawing



Summary

- Mood Boards visually communicate a design concept by combining textures, colors, furniture, and décor elements to reflect the client's vision.
- Core Elements of Mood Boards include materials & finishes, color palette, furniture & accessories, and styling components that help unify the overall theme.
- Mood Board Creation Tools include Canva, Adobe Photoshop, PowerPoint, and physical collage boards using fabric swatches and material samples.
- 3D Renders are realistic visualizations of interior spaces created using software like SketchUp, Revit, or 3ds Max, rendered with V-Ray, Lumion, or Enscape.
- Role of 3D Renders includes visualizing the end result, validating layout and lighting choices, and helping clients make faster decisions before actual execution.
- Miniature Models (also called miniatures) are scaled-down physical models built using foam boards, cardboard, or 3D printing to present spatial layout and material schemes.
- Miniature Creation Process includes preparing scaled drawings, selecting model materials, assembling with finishes, and adding furniture components or labels.
- Effective Client Presentation involves a well-structured, visual presentation of FSOW, materials, budget, layout plans, and project timelines to enhance client clarity and approval.
- Managing Change Requests requires formal documentation, impact evaluation, team review, client sign-off, document revision, team communication, and maintaining a change log.
- Drafting and Sketching Process includes rough concept sketches, AutoCAD-based technical drafts, layering material codes, integrating service layouts, and issuing GFC (Good for Construction) drawings.

Exercise

1. You are creating a living room mood board for a client who prefers a cozy and earthy look. What key elements should you include?
   a. Glossy finishes, neon color palette, metal furniture
   b. Black-and-white abstract images only
   c. Beige and rust-colored fabric swatches, wooden textures, plant photos
   d. Only CAD drawings and material sheets

2. Which software tool would best support creating a photo-realistic 3D render of a hotel reception area?
   a. MS Excel
   b. AutoCAD 2D
   c. SketchUp with V-Ray
   d. Canva

3. Your client decides to switch from laminate to back-painted glass for all wardrobe shutters mid-project. What is the first step?
   a. Revise final GFC drawings immediately
   b. Record the request formally and assess cost/timeline impact
   c. Purchase the glass
   d. Ignore and continue work

4. In a project presentation, which of the following slides helps clarify the execution schedule to the client?
   a. Title slide with project name
   b. Color palette swatches
   c. List of pending vendor payments
   d. Project timeline with key milestones

5. While sketching the layout for a Scandinavian-style bedroom, what should be considered during the detailed drafting phase?
   a. Adding random decor suggestions
   b. Skipping measurements for now
   c. Using AutoCAD to draw precise plans with furniture, lighting, and services
   d. Avoid client inputs during drafting

Activity: Prepare a Client Presentation Based on Project Details

Scenario: You are working as a junior interior designer at a design firm. Your team has finalized the project scope, layout plans, material specifications, and estimated costs for a residential 2BHK flat renovation. Your task is to prepare a client-facing presentation to showcase all relevant details for final approval.

Steps to Perform

1. **Gather Inputs**
   - Final Scope of Work (FSOW) document
   - Material Sheet (with specifications, brands, and quantities)
   - Layout plan and at least one 3D render
   - Budget or cost estimate breakdown
   - Project timeline (simplified Gantt chart or task schedule)

2. **Structure the Presentation (6–8 Slides)**
   - Slide 1: Project Title, Client Name, and Designer Introduction
   - Slide 2: Brief Project Overview and Objectives
   - Slide 3: Final Scope of Work (room-wise highlights)
   - Slide 4: Layout Plan and 3D Visuals
   - Slide 5: Material Specifications (use visuals)
   - Slide 6: Project Timeline with Key Milestones
   - Slide 7: Estimated Budget Summary
   - Slide 8: Next Steps and Space for Client Feedback

3. **Presentation Guidelines**
   - Keep content visually engaging (use icons, images, swatches)
   - Use client-friendly language (avoid technical jargon)
   - Include before-after design comparisons if available
   - Ensure fonts, colors, and design are consistent and professional

4. **Submission Format**
   - Submit the presentation in PowerPoint or PDF format

Notes

Scan the QR codes or click on the link to watch the related videos

https://www.youtube.com/watch?v=GOZkvQwtjZ4

SKETCHUP TUTORIAL FOR BEGINNERS

https://www.youtube.com/watch?v=EJRwAxdQyLM

Create a Mood Board Step by Step Easy Tutorial Using Canva

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

8. Team and Task Management

UNIT 8.1: Task Delegation
UNIT 8.2: Management and Monitoring

FFS/N0212

Key Learning Outcomes

At the end of this module, the participant will be able to:

1. Explain the rules which guide in selecting the tasks for delegation to the appropriate person.
2. State the importance of delegating tasks.
3. Explain the role of effective knowledge management in the workplace.
4. List all the common knowledge-sharing tools for effective communication with team members.
5. Define the term KPI and its role in performance management and monitoring.
6. List various performance management software for effective work monitoring.
7. Demonstrate the process of delegating tasks and responsibilities effectively.
8. Employ suitable knowledge-sharing tools to instruct team members on assigned tasks.
9. Employ suitable performance management software to monitor the job work of team members.

UNIT 8.1 Task Delegation

Unit Objectives

At the end of this unit, the participants will be able to:

1. Explain the rules which guide in selecting the tasks for delegation to the appropriate person.
2. State the importance of delegating tasks.
3. Explain the process of delegating tasks and responsibilities effectively.

8.1.1 Managing Team and Task Delegations

Identifying suitable teams is essential for the timely and successful execution of interior design projects. Each phase of the project—whether it's design, procurement, or site execution—requires specific skill sets. A well-structured team ensures that the right people are handling the right tasks, reducing errors, delays, and miscommunication. Allocating work based on capability helps in maintaining quality, accountability, and workflow continuity. It also promotes collaboration and ensures that tasks are completed efficiently and within deadlines.



Fig. 8.1.1: Importance of Identifying Suitable Teams for Effective Project Execution

Following are some of the useful questions that can guide task management and effective delegation:

What is the objective of this task?

Who has the necessary skills and experience to complete it?

What is the deadline for completion?

What resources or support are required to carry it out?

Are there any dependencies or related tasks?

How will progress be monitored or reported?

What are the possible risks or challenges?

Has the person been briefed clearly about expectations and outcomes?

What tools or documents need to be provided for successful task execution?

What is the escalation mechanism in case of roadblocks?

Fig. 8.1.2: Questions That Can Guide Task Management And Effective Delegation

Steps Involved in Task Delegation to Share the Workload and Increase Productivity

Effective task delegation allows project managers to optimize team productivity and focus on high-priority work. The steps include:

Fig. 8.1.3: Steps Involved in Task Delegation

Factors Affecting Team and Task Delegation

Following are key factors affecting team and task delegation in interior design or any project-based environment:

1. **Skill Set and Expertise**

   Tasks must be assigned based on individual team members' technical and creative capabilities to ensure quality and efficiency.

2. **Experience and Seniority**

   Complex or high-priority tasks may require experienced personnel who can make informed decisions and manage risks.

3. **Availability and Workload**

   Delegation depends on the current availability and workload of team members to prevent burnout and ensure balanced task distribution.

4. **Task Complexity**

   More complex tasks may require breaking down into smaller parts or assigning to a team rather than an individual.

5. **Timeline and Deadlines**

   Tasks must be delegated considering project timelines to ensure timely delivery and avoid bottlenecks.

6. **Resource Availability**

   Availability of tools, materials, and site access can impact who can perform the task effectively.

7. **Communication Skills**

   Some roles, especially those involving clients or vendors, require team members with good interpersonal and communication abilities.

8. **Trust and Accountability**

   Delegation is often influenced by the trust level in team members' reliability and ability to deliver results independently.

9. **Geographic or Remote Constraints**

   Team members working remotely or across locations may face limitations in handling certain site-based responsibilities.

10. **Legal or Compliance Requirements**

    Some tasks (like electrical work or structural approvals) must be assigned to certified professionals or licensed contractors.

Steps Involved in Taking Input from Internal and External Agencies

Collaboration with internal and external stakeholders is essential in interior projects, especially when dealing with consultants, vendors, or clients. The steps include:



Fig. 8.1.4: Steps Involved in Taking Input from Internal and External Agencies

1. Define the Purpose of the Input: Know exactly what input you need—design changes, technical approval, vendor feedback, etc.
2. Identify Stakeholders: Decide who the internal (e.g., design team, purchase department) and external (e.g., consultants, contractors) contributors are.
3. Set Up Communication Channels: Choose how the input will be collected—meetings, emails, shared documents, or software.
4. Share Relevant Documents or Context: Provide background, reference drawings, or requirements to support clear responses.
5. Record and Track Input Received: Maintain documentation or trackers to ensure all responses are captured and traceable.
6. Incorporate and Acknowledge the Input: Integrate valid suggestions and keep contributors informed about how their input was used.

Break Tasks into Specific Skillsets for Team and Task Delegations

Breaking down tasks into specific skillsets ensures the right person handles the right job. This not only increases accuracy but also improves efficiency and accountability. It includes the following:



Fig. 8.1.5: Breaking down tasks into specific skillsets

1. **Analyze the Task Scope:**

   Understand the complexity and expected outcome of the task. For example:

Example:

A modular kitchen installation task requires coordination with carpenters, electricians, and vendors; it has both design and execution components.

2. **Identify Required Skillsets:**

   Determine whether the task needs technical skills, creative thinking, procurement knowledge, or people management.

Example:

Designing a feature wall needs creative and 3D rendering skills, while electrical layout needs technical expertise.

3. **Map Skills to Team Members:**

   Allocate tasks to individuals or teams who possess the relevant competencies.

Example:

Assigning the furniture layout task to a junior architect familiar with CAD software.

4. **Segment the Task if Needed:**

   For large tasks (e.g., setting up a display area), divide into sub-tasks—layout planning, material sourcing, site coordination—and delegate accordingly.

Example:

One team member handles design, another places vendor orders, and a third supervises installation.

5. **Define Roles and Expectations Clearly:**

   Ensure that each person knows what part they're responsible for and how it contributes to the overall project.

Example:

The site supervisor must ensure timely delivery and quality checks of materials, while the designer coordinates aesthetics.

Fig. 8.1.5:

UNIT 8.2: Management and Monitoring

Unit Objectives

At the end of this unit, the participants will be able to:

1. Explain the role of effective knowledge management in the workplace.
2. List all the common knowledge-sharing tools for effective communication with team members on assigned tasks.
3. Define the term KPI and its role in performance management and monitoring.
4. List various performance management software for effective work monitoring of team members.

8.2.1 Knowledge Management

Knowledge Management refers to the systematic process of capturing, organizing, sharing, and applying information and expertise within an organization. It ensures that employees have access to the right knowledge at the right time to make informed decisions, improve productivity, and foster innovation. Key roles of knowledge management in the workplace are as follows:

Fig. 8.2.1: Key roles of knowledge management in the workplace

- **Promotes Organizational Learning:**

  It enables continuous learning by documenting best practices, lessons learned, and project insights that can be reused across teams.

  Example: A designer shares insights from a challenging client brief, helping others avoid similar issues in future projects.

- **Enhances Efficiency and Reduces Rework:**

  Employees can access past project files, templates, or client preferences without starting from scratch.

  Example: Reusing an approved material sheet format reduces time spent recreating one.

- **Improves Onboarding and Training:**

  Centralized knowledge systems help new hires quickly understand workflows, tools, and expectations.

  Example: An onboarding manual helps a new assistant interior designer learn firm standards and tools in less time.

- **Supports Decision-Making:**

  Ready access to reliable information allows teams to make quicker and smarter decisions.

  Example: Before finalizing a procurement decision, a team checks vendor performance notes in the knowledge base.

- **Fosters Collaboration and Innovation:**

  By sharing insights, suggestions, and expertise, teams collaborate better and innovate more effectively.

  Example: Designers from different locations contribute to a shared mood board for a pan-India hotel chain.

Common Knowledge-Sharing Tools for Effective Communication with Team Members on Assigned Tasks

Following table lists the commonly used tools and platforms for knowledge sharing and communication across teams:

Tool	Purpose
Google Drive / OneDrive	Cloud storage and real-time collaboration on documents, drawings, and reports
Microsoft Teams	Team chat, video meetings, and file sharing integrated with Office apps
Slack	Quick team communication via channels, with integrations for task updates
Notion	Wiki-like documentation, project tracking, and knowledge base creation
Trello	Visual task boards for sharing updates, notes, and files for ongoing work
Asana / ClickUp	Task tracking with comment threads, attachments, and team assignments

Confluence	Structured documentation and collaborative spaces (common in larger firms)
Miro / FigJam	Visual collaboration tools for brainstorming, mood boards, and process mapping
Email	Formal communication and record of approvals, summaries, or decisions
WhatsApp / Telegram	Informal quick updates, reminders, and group discussions (often used on site)

Table. 8.2.1:

8.2.2 Performance Management and Monitoring

KPI stands for Key Performance Indicator. It is a measurable value that indicates how effectively an individual, team, or organization is achieving specific goals and objectives.

Role of KPIs in Performance Management and Monitoring:

Fig. 8.2.2: Role of KPIs in Performance Management and Monitoring

- **Set Clear Expectations:**

  KPIs help define what success looks like for a role or project, ensuring every team member understands their goals.

  Example: A KPI for a project coordinator could be "Project delivery within ±5% of budget."

- **Measure Progress Objectively:**

  They provide quantifiable data to track how well individuals or teams are performing over time.

  Example: Tracking the number of design revisions before final client approval.

- Enable Data-Driven Decisions:

  KPIs highlight strengths and areas needing improvement, helping managers allocate resources effectively.

Example: If a team consistently misses deadlines, the KPI reveals the need for process adjustments.

- **Support Feedback and Appraisals:**

  Regular KPI reviews allow fair, fact-based performance evaluations and development discussions.

  Example: A designer meeting 90% of delivery timelines can be considered for leadership roles.

- **Align Efforts with Organizational Goals:**

  Well-defined KPIs ensure all team activities contribute toward broader business outcomes.

  Example: "Client Satisfaction Score ≥ 4.5/5" aligns the team's work quality with customer service goals.

- **KPIs for Assistant Interior Designer**
- Following table list the practical and role-specific Key Performance Indicators (KPIs) for an Assistant Interior Designer, designed to align with performance monitoring, project efficiency, and client satisfaction:

KPI	Description	Target / Goal	Relevance
1. Design Task Completion Rate	Percentage of assigned design tasks completed within the planned timeline.	90%+ on-time delivery	Measures time management and productivity.
2. Accuracy in Drafting/Layout Work	Number of design revisions due to errors or omissions in drafting.	< 2 revisions per project	Reflects attention to detail and drawing quality.
3. Client Feedback Score	Average rating from client or senior designer for draft quality and responsiveness.	≥ 4.5/5	Gauges professionalism and design understanding.
4. Material Specification Accuracy	Correct identification and listing of materials based on project specifications.	95% accuracy	Ensures effective procurement coordination.
5. Compliance with Design Guidelines	Adherence to firm standards, codes, and client design briefs.	100% compliance	Ensures consistency and professionalism.
6. Collaboration Efficiency	Responsiveness and effectiveness in team communication (e.g., updates shared on time, tasks acknowledged).	Positive peer feedback or weekly task reporting	Tracks teamwork and accountability.
7. Site Visit Documentation Timeliness	Timely submission of reports, measurements, or photos from site visits.	Within 24 hours of visit	Supports real-time coordination and accuracy.
8. Concept Draft Turnaround Time	Average time taken to deliver first draft design or mood board.	≤ 3 days from brief	Measures responsiveness and creativity.

9. Number of Projects Assisted	Count of active or completed projects supported during a quarter.	4–6 projects	Helps measure workload balance and versatility.
10. Software Proficiency Growth	Demonstrated learning or usage of tools like AutoCAD, SketchUp, or Photoshop.	Regular usage or certification update	Supports continuous professional development.

Table. 8.2.2:

Performance Management Software for Effective Work Monitoring of Team Members

Following table lists the widely used software tools that support performance management and work monitoring across teams:

Software	Purpose / Features
Keka HR	Indian HRMS with performance reviews, goal tracking, and feedback
Zoho People	Employee performance tracking, appraisals, and attendance monitoring
BambooHR	Goal-setting, performance appraisals, and peer feedback (popular with mid-sized companies)
Workday	Enterprise-level performance and talent management with deep analytics
Lattice	Real-time feedback, goal tracking (OKRs), performance reviews, and engagement tools
15Five	Weekly check-ins, one-on-ones, goal progress, and peer recognition
Trakstar	Competency-based performance management and appraisal tools
PerformYard	Customizable review cycles, goal tracking, and feedback tools
ClickUp	Combines task/project tracking with time logging and performance visibility
Asana	Task completion, project milestones, and productivity monitoring through dashboards

Table. 8.2.2:

Summary

- Effective Task Delegation involves identifying suitable team members based on skills, experience, and workload to ensure timely and high-quality project execution.
- Delegation Process includes reviewing the FSOW, analyzing team capabilities, assigning tasks using tools (like Trello, Asana), and clearly defining roles and expectations.
- Factors Influencing Delegation include team member skillsets, availability, workload, task complexity, deadlines, resource access, and communication skills.
- Input Collection from internal and external stakeholders requires clear purpose definition, identifying contributors, setting channels, sharing documents, and tracking responses.
- Hands-on Delegation Activities enhance learning by simulating real-life task assignment using FSOW documents, digital tools, and mock team profiles.
- Knowledge Management ensures teams can reuse past work, improve decisions, and accelerate onboarding through organized, accessible information systems.
- Knowledge-Sharing Tools include Google Drive, Notion, Microsoft Teams, Trello, Confluence, Miro, Slack, and email—each serving collaborative and documentation purposes.
- KPIs (Key Performance Indicators) are measurable values that track task progress, help with appraisals, and align individual efforts with broader project goals.
- KPIs for Assistant Interior Designers include metrics like task completion rate, drafting accuracy, material specification correctness, client feedback, and site reporting timelines.
- Performance Monitoring Tools such as Zoho People, Keka HR, ClickUp, BambooHR, and Lattice help managers track productivity, goal achievement, and peer feedback.

Exercise

A. Multiple Choice Questions (MCQs)

1. You're assigning a task that involves vendor negotiation and site material follow-ups. What factor should most influence your choice of team member?
   a. Their years of experience
   b. Their availability next month
   c. Their communication and negotiation skills
   d. Their drafting accuracy

2. Your new intern struggles to use AutoCAD for basic layout editing. What knowledge management solution can best support their learning?
   a. Sending them client emails for reference
   b. Giving them a week off to study
   c. Sharing your firm's onboarding manual and template repository
   d. Asking them to attend vendor meetings

3. After a site visit, your assistant delays submitting the photo documentation by three days. Which KPI does this impact?
   a. Site visit documentation timeliness
   b. Drafting accuracy
   c. Client satisfaction score
   d. Mood board creativity

4. Your project management tool shows that a designer is assigned more tasks than others, leading to errors. What delegation principle has likely been overlooked?
   a. Skillset alignment
   b. Workload balancing
   c. Experience factor
   d. Trust level

5. You are setting up a dashboard to monitor weekly task completion and team performance. Which software would be most suitable?
   a. Adobe Illustrator
   b. MS Word
   c. ClickUp or Asana
   d. WhatsApp

Hands-on Activity: Scope-to-Task Delegation Using Project Tools

Objectives:

- Analyse and interpret the Final Scope of Work (FSOW) to determine team and task delegations
- Perform delegation of tasks to team members using appropriate software tools and techniques

Materials Needed:

- A sample Final Scope of Work (FSOW) document (can be printed or shared digitally)
- List of fictional team members with skillsets, availability, and roles
- Access to a (e.g., Trello, Asana, ClickUp, or MS Project) or a simulated task board (Excel or printed template)
- Laptops/tablets or printed project management tool templates
- Sticky notes, markers (for offline execution)

Instructions:

Step 1: Understand the FSOW

Each group receives a detailed Final Scope of Work document. They must:

- Identify major work packages and deliverables
- Break down the scope into manageable tasks/sub-tasks
- Understand deadlines, dependencies, and deliverable expectations

Step 2: Analyze Team Capabilities

Participants review team member profiles:

- Skills, tools expertise, availability, work style
- Identify best-fit members for each task

Step 3: Delegate Using a Tool

Use a digital tool (e.g., Trello/Asana) or a physical board to:

- Create tasks/sub-tasks
- Assign each task to a suitable team member
- Set timelines, dependencies, and priorities
- Label or categorize tasks (e.g., “Urgent”, “Design Phase”)
- Track effort vs. availability

Step 4: Presentation & Justification

Each group presents their:

- Delegation decisions
- Justification for role-task mapping
- How the FSOW influenced their task plan

Notes

Scan the QR codes or click on the link to watch the related videos

https://www.youtube.com/watch?v=l7Xqv6nzd6U

Boost Team Productivity

https://www.youtube.com/watch?v=WYMr8NZdG54

Performance Management

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

9. Prepare and Validate the Design Drafts and Drawings

Unit 9.1: Approved for Construction (AFC) Drawings
Unit 9.2: SOP for Modification and Approvals

FFS/N0213

Key Learning Outcomes

At the end of this module, the participant will be able to:

1. Explain the roles of different construction elements like electrical, plumbing, Reflected Ceiling Plan (RCP), flooring, etc. in interior designing.
2. Perform worksite inspection to interpret various construction elements affecting interior design.
3. Identify the process of preparing and maintaining the Approved for Construction (AFC) drawings.
4. Explain the role of MEP details in the Approved for Construction (AFC) drawings.
5. Explain the process of preparing Approved for Construction (AFC) drawings.
6. List all the required documentation to perform validation of design drafts.
7. Explain the SOP for modification and approvals of drawings/designs.
8. State the importance of maintaining revised drawings in providing a safe, practical, and efficient workplace.
9. Perform validation of design drafts based on required design specifications.
10. Examine the approved drawings/designs for the incorporation of proposed changes, if any.

UNIT 9.1: Approved for Construction (AFC) Drawings

Unit Objectives

At the end of this unit, the participants will be able to:

1. Explain the roles of different construction elements like electrical, plumbing, Reflected Ceiling Plan (RCP), flooring, etc. in interior designing.
2. Perform worksite inspection to interpret various construction elements affecting interior design.
3. Identify the process of preparing and maintaining the Approved for Construction (AFC) drawings.
4. Explain the role of MEP details in the Approved for Construction (AFC) drawings.
5. List all the required documentation to perform validation of design drafts.
6. Perform validation of design drafts based on required design specifications.
7. Examine the approved drawings/designs for the incorporation of proposed changes, if any.
8. Explain the process of Corrective Action Preventive Action (CAPA) for approved drawings/ concepts.

9.1.1 Role of Various Elements in Construction Structures Affecting Interior Designing

Interior design is not an isolated activity; it is deeply interconnected with the underlying construction structure. The following elements significantly influence the design approach, feasibility, and aesthetics of interior spaces:



Fig. 9.1.1:

Structural Columns and Beams

- Determine space division, ceiling levels, and furniture layout.
- In open-plan spaces, load-bearing columns can either restrict or inspire creative design elements like cladding or false column treatments.

Walls and Partitions

- Load-bearing vs. non-load-bearing walls affect whether walls can be demolished or altered.
- Wall thickness determines insulation capacity and built-in storage options.

Slab Height and Ceiling Levels

- Impacts design of lighting fixtures, HVAC ducts, and false ceilings.
- Low slab heights restrict hanging fixtures or layered ceiling designs.

Doors and Window Openings

- Influence natural lighting, ventilation, and furniture placement.
- Standard sizes or unusual placements may require customization of window treatments or joinery.

Flooring Base and Finish Levels

- Affect the selection and installation of final floor finishes.
- Uneven levels can lead to safety issues or design inconsistencies.

Staircases and Vertical Circulation

- Structural placement impacts the visual flow and functional division.
- May be used as focal points if aligned well with the design theme.

Electrical, Plumbing, and HVAC Services

- MEP (Mechanical, Electrical, Plumbing) placements define what is feasible in terms of kitchen, bathroom, lighting, and air conditioning layouts.
- Service shaft locations often dictate space planning and appliance positioning.

In summary: Structural elements act as both constraints and design opportunities, guiding the layout, aesthetics, and technical feasibility of an interior design project.

Importance of Adherence to Standard Construction Parameters for Effective Interior Designing

Adhering to standard construction parameters is critical to ensure that interior design is safe, functional, and seamlessly integrated with the building's structure and services. These standards define dimensions, load capacities, service routes, and safety requirements, forming the foundation upon which design decisions are made.

Following are the key reasons:

1. **Structural Integrity:** It ensures that design elements do not compromise the strength or stability of the building.
2. **Design Feasibility:** It allows designers to work within accurate dimensions, avoiding conflicts with beams, columns, or MEP installations.
3. **Precision in Fit-Outs:** It refers to standard floor-to-ceiling heights, wall thicknesses, and door sizes support accurate detailing and reduce rework.
4. **Service Coordination:** It refers to proper alignment with plumbing, electrical, and HVAC systems enhances functionality and prevents costly on-site modifications.

5. **Compliance with Building Codes:** It follows regulatory norms related to fire safety, accessibility, ventilation, and egress routes.
6. **Cost and Time Efficiency:** It reduces material wastage, construction errors, and project delays due to misalignment between design and site realities.
7. **Ease of Maintenance:** It facilitates future servicing and repairs due to predictable and standardized service layouts.

9.1.2 Process of Designing and Maintaining the Approved for Construction (AFC) Drawings

AFC (Approved for Construction) drawings are the final set of technical drawings that have been reviewed, approved, and authorized for use in the actual construction or implementation phase of a project. These drawings are legally binding and serve as the reference document for contractors, vendors, and site teams during project execution.



Fig. 9.1.2:



Fig. 9.1.3:

Following are the key steps for Designing and Maintaining of AFC drawings

1. **Initial Design Development:** Create concept and schematic drawings based on client requirements and site constraints.
2. **Detailed Design and Drafting:** Develop technical drawings including plans, elevations, sections, joinery, MEP layouts, and material specifications.
3. **Internal Review and Coordination:** Cross-check with structural, electrical, HVAC, and plumbing consultants to resolve overlaps or clashes.
4. **Client & Consultant Approvals:** Incorporate feedback from client and consultants; finalize all details and notes.
5. **Stamp as AFC Drawings:** Once approved, label the drawings as “AFC” with date, version, and responsible sign-off authority.
6. **Distribution and Implementation:** Share with site team, contractors, and vendors for on-ground implementation.
7. **Ongoing Maintenance:** Maintain AFC drawing logs, issue-controlled copies, and update with any site-level amendments or change orders.

Sample: Design Review Checklist

Item to Review	Checked (Yes/No)	Comments
Layout matches approved floor plan		
All dimensions are correctly labeled		
Material specifications align with BOQ		
Furniture layout and spacing is accurate		
Electrical points and switches are shown		
Plumbing fixtures are positioned correctly		
HVAC vents and ducts are incorporated		
Drawing legend and symbols are complete		
Scale and orientation are mentioned		
Client feedback is incorporated		

Table 9.1.1:

Sample: AFC Drawing Log

Drawing No.	Drawing Title	Version	Date Issued	Validated By	Remarks
IDR-GF-001	Ground Floor Layout Plan	V1.0	20/05/2025	A. Sharma	Approved Ready for Execution
IDR-FF-002	First Floor Reflected Ceiling Plan	V1.2	22/05/2025	R. Mehta	Updated lighting points Approved
IDR-SEC-003	Sectional Elevation through Lobby	V1.1	24/05/2025	K. Joshi	Minor revision in floor finish noted

Table 9.1.2:

Validation of Approved for Construction (AFC) Drawings Based on Specified Instructions

Validation is the process of checking whether AFC drawings are correct, complete, and aligned with given project instructions.



Fig. 9.1.4:

Sample: Validation Form

Drawing No.	Drawing Title	Project Name	Checked By	Date	Version	Key Validation Points	Validation Status (Pass/ Fail)	Comments/ Actions Required
RCP-01	Reflected Ceiling Plan (RCP)	Tech-Square Co-Working Office	Rohini	25/05/2025	V2.0	Grid layout matches archite-ctural drawing - Light fixtures and ceiling tiles are evenly distributed - Service cut-outs are correctly marked - Symbols and notations conform to drawing standards	Pass	Verified for site use. No issues found.

Table 9.1.3:

Steps for Validation of AFC drawings:

1. Compare with Final Client Brief: Check if all approved layouts and specifications match client's signed-off scope.
2. Cross-Check Services Integration: Ensure electrical, plumbing, and HVAC components are properly placed with no design clashes.
3. Check Dimensions and Levels: Verify all measurements, floor levels, and fitment details against site conditions.
4. Ensure Material Specifications Match: Confirm all material types, finishes, and installation details as per the final BOQ.
5. Highlight Deviations: Document any mismatch or missing elements and inform the design head for rectification.
6. Record Validation Status: Mark drawings as "Validated" with checker name, date, and version.

Importance of Validating Final Drawings

Avoid Cost Overruns:	• Prevents material mismatches or incorrect execution that can lead to expensive corrections.
Ensure Timely Execution:	• Identifies delays or missing components early, avoiding onsite rework and project hold-ups.
Maintain Quality and Design Intent:	• Ensures the built output matches approved visual, functional, and material expectations.
Regulatory Compliance:	• Helps meet building codes, safety standards, and approvals.
Vendor & Contractor Clarity:	• Ensures that construction partners have the correct, unambiguous documentation to execute the project.

Fig. 9.1.5:

Process of Checking Project Designs Based on Specified Instructions

Steps to Check Designs:

1. **Read and Understand the Instruction Set:** Review client brief, consultant notes, regulatory requirements, and any addendums.
2. **Review Each Drawing Set:** Go through plans, elevations, MEP drawings, and furniture layouts line-by-line.
3. **Validate Against Scope & BOQ:** Check if specified items are present (e.g., modular furniture type, finish codes, light placements).
4. **Use a Checklist for QA:** Use a standard design review checklist to verify: dimensions, materials, service points, finish levels.

5. **Raise Queries (RFI):** Document any inconsistencies and send Requests for Information (RFI) to the designer or consultant.
6. **Sign Off or Mark for Revision:** Approve if no issues are found; else, mark revisions clearly.

Examination Points for Approved Drawings

- **Room-wise Layout Verification:** Confirm that room sizes, orientation, and furniture placements follow approved plans.
- **Material and Finish Matching:** Ensure wall, flooring, ceiling, and fixture specifications match client choices.
- **Service Point Coordination:** Check electrical, plumbing, and HVAC layouts are as per service consultant inputs.
- **Labeling and Legends:** All drawings must include updated legends, notes, symbols, and scaling.
- **Accessibility and Ergonomics:** Confirm that circulation spaces, heights, and reachability comply with design codes.

UNIT 9.2: SOP for Modification and Approvals

Unit Objectives

At the end of this unit, the participants will be able to:

1. Explain the SOP for modification and approvals of drawings/designs.
2. State the importance of maintaining revised drawings in providing a safe, practical, and efficient workplace.
3. Explain the process of Corrective Action Preventive Action (CAPA) for approved drawings/ concepts.

9.2.1 SOP for Modification and Approvals of Drawings/ Designs

A Standard Operating Procedure (SOP) for modifying and approving drawings ensures a controlled, consistent, and traceable process to handle design changes during a project lifecycle. This avoids confusion, reduces errors on-site, and ensures that all stakeholders work from the most current version of the design. Following are the steps involved in modification and Approval of Drawings or Designs:



Fig. 9.2.1: Steps Involved in Modification and Approval of Drawings or Designs

1. **Initiation of Change Request:** The process begins when a change is identified by the client, site supervisor, or any internal team member. This modification requirement can arise due to functional requirements, on-site limitations, or evolving client preferences. A formal request is then submitted either through a change request form, official email, or meeting note to initiate the modification process.
2. **Design Review:** Once the change request is received, the design team conducts a thorough review to assess its feasibility. This includes analyzing technical constraints, structural impacts,

and whether the proposed change aligns with the project's objectives and design intent. Additionally, the team evaluates any potential effects on cost, timelines, or procurement schedules before proceeding.

3. **Preparation of Revised Drawings:** Following the approval of feasibility, the design team prepares revised drawings using professional design software such as AutoCAD. All modifications are clearly marked using cloud bubbles, revision tags, or color codes to differentiate them from the original design. This ensures that changes are easily recognizable by reviewers and on-site teams.
4. **Internal Review and Validation:** Before being shared externally, the revised drawings undergo an internal quality check. A senior designer, design manager, or project head validates the changes for accuracy, technical compliance, and consistency with the Final Scope of Work (FSOW). This step helps catch errors early and ensures that all team members are aligned.
5. **Client Review and Approval:** The updated drawings are then presented to the client along with a clear summary of the changes made. The client is asked to review the documents and provide formal approval either in writing, via email, or through digital markup confirmation. This approval confirms that the revisions meet client expectations and can be executed on-site.
6. **Issuance and Distribution:** Once approved, the revised drawings are issued as the latest version. They are updated with a new revision number, date, and version code (e.g., "Final – Rev 01" or "Rev 03"). These updated documents are then distributed to all relevant parties including site teams, contractors, vendors, and supervisors to ensure that everyone is working with the latest approved information.
7. **Documentation and Archiving:** To maintain version control and legal traceability, all previous versions of the drawings are archived properly. The newly revised drawings are stored in a centralized digital folder, such as a shared cloud drive or office server, so that all stakeholders have easy access to the most current documents for execution, inspection, or future reference.

Sample Drawing Revision Log

Drawing Title	Drawing No.	Revision No.	Date of Revision	Reason for Revision	Approved By	Remarks
Living Room Electrical Layout	DRW-EL-101	Rev-01	10/05/2025	Changed light point positions as per client feedback	Lead Designer	Updated drawing shared with electrician and site team
Kitchen Modular Layout	DRW-KT-202	Rev-02	15/05/2025	Updated cabinet layout to include built-in oven	Project Manager	Issued for final approval before fabrication
Toilet Plumbing Line Plan	DRW-PL-305	Rev-01	18/05/2025	Modified pipeline routing to avoid structural beam	MEP Consultant	GFC issued for execution

Table 9.2.1:

9.2.2 Importance of Maintaining Revised Drawings in Providing a Safe, Practical, and Efficient Workplace

Maintaining accurate and updated (revised) drawings is essential for ensuring safety, quality, and workflow efficiency throughout project execution and post-occupancy phases.

Importance of Maintaining Revised Drawings in Providing a Safe, Practical, and Efficient Workplace are as follows:

1. **Ensures On-Site Accuracy:** Maintaining revised drawings ensures that all execution teams are working from the latest approved plans, significantly reducing errors during implementation. Accurate and up-to-date drawings eliminate guesswork and prevent the use of outdated information on-site. For example, if a duct placement is revised and the change is not communicated through updated drawings, it may lead to clashes with electrical fixtures or require costly rework later.
2. **Enhances Workplace Safety:** Revised service layouts play a vital role in ensuring workplace safety, especially when dealing with electrical wiring, plumbing systems, or fire safety installations. Accurate drawings prevent accidental drilling, short circuits, or structural damage. For instance, a revised lighting layout that reflects the correct placement of switchboards helps the team avoid unsafe or faulty electrical connections.
3. **Supports Effective Project Coordination:** Maintaining and distributing revised drawings ensures that all stakeholders—designers, contractors, vendors, and site supervisors—are aligned with the latest project updates. This coordination minimizes confusion, avoids duplicate efforts, and helps keep the project on track. For example, when a false ceiling layout is revised and shared promptly, the vendor can correctly align lighting fixtures as per the updated plan, avoiding misplacement.
4. **Avoids Legal and Financial Risks:** Revised drawings provide a record of agreed changes and serve as formal documentation in case of disputes, audits, or compliance checks. This traceability protects both the client and the service provider from potential legal or financial liabilities. For example, if a partition wall is relocated but not documented in a revised plan, it could lead to billing disputes or client dissatisfaction over unexpected cost increases.
5. **Improves Future Maintenance and Repairs:** Once the project is completed, the final set of revised drawings becomes the official "as-built" record. These are crucial for facility management, future renovations, or repairs. Having access to accurate layouts helps maintenance teams identify the location of concealed utilities like pipes or cables. For example, during a renovation, a team can safely avoid damaging embedded water lines by referring to the updated plumbing layout.

Process of Corrective Action and Preventive Action (CAPA) for Approved Drawings/Concepts

Corrective Action and Preventive Action (CAPA) is a quality management process used to investigate, address, and eliminate issues that may arise from errors, deviations, or gaps in approved drawings or concepts. It ensures both immediate resolution (corrective) and future prevention (preventive) of similar occurrences.



Fig. 9.2.2: CAPA for Approved Drawings/Concpets

1. **Identification of the Issue**

   The process begins when a deviation, error, or non-conformance is detected in the execution based on the approved drawing or concept. This could be identified during a site inspection, client feedback session, quality audit, or vendor query.

   Example: A false ceiling light point is misplaced due to an incorrect measurement in the approved drawing.

2. **Root Cause Analysis (RCA)**

   A structured investigation is carried out to determine the underlying cause of the error. Tools such as the 5 Whys or Fishbone Diagram can be used to trace the issue back to its origin—be it drafting error, approval oversight, communication gap, or outdated drawing reference.

   Example: RCA reveals that the electrical layout was finalized before receiving the revised false ceiling dimensions.

3. **Implementation of Corrective Action**

   Once the root cause is identified, an immediate corrective measure is taken to address the issue and restore conformity on-site or in the documentation.

   Corrective Action Example: Issue a revised electrical layout with corrected light point positioning and redistribute it with a “Rev-2” tag. Update the site team and vendor immediately.

4. **Verification of Effectiveness**

   The effectiveness of the corrective action is verified through on-site checks, team feedback, or client validation. This ensures the issue is fully resolved and the updated design is implemented correctly.

   Example: The supervisor verifies that the new drawing was followed correctly, and the lights are installed as per the new layout.

5. **Planning and Execution of Preventive Action**

   To prevent recurrence, systemic improvements are made. These may include updating standard checklists, improving review protocols, or training the design/drafting team.

   Preventive Action Example: Introduce a step in the workflow requiring cross-verification of all service layouts after changes in civil or ceiling drawings. Create a checklist for internal design reviews.

6. **Documentation and Closure**

   All actions taken (corrective and preventive) are documented in a CAPA log. This record helps in internal audits, client reporting, and continuous improvement of project delivery processes.

Summary

- Structural components like beams, slab heights, electrical and plumbing services impact design feasibility, space planning, and aesthetics.
- Mechanical, Electrical, and Plumbing (MEP) layouts guide the positioning of fixtures, appliances, and service routes in interior projects.
- AFC (Approved for Construction) Drawings are final, signed-off technical documents used on-site for execution. They include layout plans, service details, and material specifications.
- Creating AFC Drawings begin with concept development, followed by technical detailing, stakeholder approvals, stamping as AFC, distribution, and revision control.
- Validation of AFC Drawings includes checking alignment with client scope, material specs, measurements, MEP integration, and using standardized checklists for review.
- Validation ensures accurate execution, eliminates on-site rework, and maintains consistency between the design intent and real-world build.
- SOP for Drawing Modifications includes change request initiation, internal review, revised drawings with markups, client approval, distribution, and archival.
- Maintaining Revised Drawings prevents errors, supports site safety, improves coordination, protects from legal risks, and aids future maintenance.
- CAPA (Corrective and Preventive Action) Process is used when an error in approved drawings causes execution problems. It includes identifying issues, root cause analysis, corrections, and long-term preventive actions.
- All revisions, validations, and CAPA actions are documented in drawing logs, revision registers, and validation forms for audit readiness and traceability.

Exercise

A. Multiple Choice Questions (MCQs)

1. A light fixture is wrongly placed on-site because the false ceiling layout was not updated. What document should have been referred to?

   a. Mood Board

   b. Revised AFC Drawing

   c. Vendor Quotation

   d. Purchase Order

   Answer: b. Revised AFC Drawing

2. While validating AFC drawings, you notice mismatched plumbing points. What should you do?

   a. Inform the procurement team

   b. Proceed with execution anyway

   c. Document the error and raise it with the design head

   d. Delete the drawing

   Answer: c. Document the error and raise it with the design head

3. What is the first step in the Corrective Action Preventive Action (CAPA) process?

   a. Update the BOQ

   b. Archive all old drawings

   c. Identify the issue or non-conformance

   d. Call a client meeting

   Answer: c. Identify the issue or non-conformance

4. Which of the following is not a component typically included in AFC drawings?

   a. Electrical point layout

   b. Client feedback email

   c. Reflected ceiling plan

   d. HVAC duct routing

   Answer: b. Client feedback email

5. Your team received a client-approved drawing with the label “Final – Rev 03.” What does this indicate?

   a. It’s the third copy made for the client

   b. It has been revised three times and is now approved for use

   c. It’s still under discussion

   d. It is the first version

   Answer: b. It has been revised three times and is now approved for use

6. Which tool is commonly used during root cause analysis in the CAPA process?
   a. SWOT Analysis
   b. 5 Whys Technique
   c. Pie Chart
   d. Bar Graph
   Answer: b. 5 Whys Technique

7. Why are slab height and ceiling levels important in AFC drawing review?
   a. They impact the floor finish texture
   b. They determine lighting, HVAC, and ceiling design feasibility
   c. They define the number of doors required
   d. They don't affect interior layout
   Answer: b. They determine lighting, HVAC, and ceiling design feasibility

8. A cabinet layout was revised but the change wasn't shared with the vendor. What risk does this pose?
   a. Material mismatch
   b. Delayed installation
   c. Fabrication errors and cost overrun
   d. All of the above
   Answer: d. All of the above

9. What must be included in a drawing validation checklist?
   a. Team attendance
   b. Material supplier names
   c. Service point placement, legends, dimensions
   d. Design themes
   Answer: c. Service point placement, legends, dimensions

10. After modifying a drawing, which of the following actions is most important?
    a. Discard the previous version
    b. Only verbally inform site workers
    c. Assign a new revision number and archive the old drawing
    d. Highlight changes using emojis
    Answer: c. Assign a new revision number and archive the old drawing

Notes

Scan the QR codes or click on the link to watch the related videos

https://www.youtube.com/watch?v=vHEq3bQNIj4

GFC, IFC, As Built, Concept, AFC, Design Drawings
I Types of Drawings in Construction

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

10. Procurement Management and Monitoring of on-Site Project Work

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

Unit 10.1: Procurement and Tender Documentation
Unit 10.2: Quality Check
Unit 10.3: Project Installation and Handover

FFS/N8207

Key Learning Outcomes

At the end of this module, the participant will be able to:

1. List all the documentation formalities required for material procurement.
2. Explain the role of necessary documents like Bill of Quantity (BOQ), specification sheet, tender documents, etc., in the material procurement process.
3. State the importance of compatibility between vendor quotations and approved product drawings.
4. Discuss the process of interpreting and analyzing a vendor quotation.
5. List all the key quality indicators for Quality Checking (QC) of procured materials.
6. Define the term Knowledge Sharing and its impact on an organization's communication.
7. Differentiate between internal and external communication methods.
8. Analyze the variables that are driving project cost for material optimization.
9. Employ suitable techniques to estimate the material requirements.
10. Explain how to prepare various documentation formalities for the material procurement process.
11. Examine the vendor quotation with the approved product drawing for any discrepancies.
12. Identify and inspect the procured materials for given quality indicators.
13. State the importance of client walk-throughs in the efficiency of the project execution.
14. Discuss the role of intrinsic quality checking for inefficiency in project execution.
15. Explain the documentation formalities associated with the project closure and handover.
16. Identify the steps involved in performing client walk-throughs.
17. Identify the on-site assembly and installation process based on various intrinsic quality parameters.
18. Prepare project closure and handover report upon project completion.

UNIT 10.1: Procurement and Tender Documentation

Unit Objectives

At the end of this unit, the participants will be able to:

1. List all the documentation formalities required for material procurement.
2. Explain the role of necessary documents like Bill of Quantity (BOQ), specification sheet, tender documents, etc., in the material procurement process
3. Explain how to prepare various documentation formalities for the material procurement process.
4. Analyze the variables that are driving project cost for material optimization.
5. Employ suitable techniques to estimate the material requirements.

10.1.1 Procurement Plan and Process

Procurement refers to the structured process of acquiring goods, materials, or services needed to execute a design project. In interior design, this includes the sourcing and purchase of furniture, fixtures, equipment decor items, and finishing materials.

The procurement process involves the following steps:

Fig. 10.1.1: Procurement Process

1. **Identifying Project Requirements:** At a first step you define the materials, finishes, equipment, and services required based on the interior design brief, layout plans, and client preferences. This ensures that procurement aligns with the overall design intent and functionality needs.

2. **Market Research and Vendor Identification:** Second step is to research potential suppliers, assess market rates, and shortlist vendors based on quality, price, reliability, and delivery capabilities. This step supports cost-effective decisions and builds a pool of trusted vendors for procurement. Market research during procurement process helps identify the following that ensures informed purchasing decisions and budget alignment:

Fig. 10.1.2: Role of market research during the procurement process

3. **Requesting and Reviewing Quotations:** Once the vendors are identified, send RFQs (Request for Quotations) to selected vendors and evaluate received quotes based on specifications, costs, delivery timelines, and terms. This ensures transparency and comparison across vendors before finalizing purchases.
4. **Negotiating Terms and Costs:** Engage in discussions with shortlisted vendors to agree on pricing, discounts, warranties, payment terms, and delivery schedules. The goal is to secure the best value without compromising quality or timeline.
5. **Preparing Purchase Orders/Contracts:** Once the vendors are finalised, issue formal purchase orders or sign contracts that clearly state quantities, rates, delivery deadlines, payment terms, and responsibilities. This documentation protects both the designer and supplier legally and financially.

Sample: Purchase Order (PO)

Purchase Order (PO)	**PO No.: 001245**			
Date:	23-June-2025			
Buyer:	XYZ Interiors Pvt. Ltd. 45 Design Street, Mumbai - 400021			
Vendor:	Creative Furnishings 12 Industrial Estate, Pune - 411001			
S. No.	**Item Description**	**Qty**	**Unit Price (INR)**	**Total (INR)**
1.	Office Workstations (6x2 ft)	10	12,000	1,20,000
2.	Ergonomic Office Chairs	10	6,500	65,000
3.	Storage Cabinets (3-door)	5	8,000	40,000
	Total Amount			**2,25,000**

Table 10.1.1:

Delivery Date: Within 15 days from order

Payment Terms: 50% advance, 50% on delivery

Delivery Address: XYZ Interiors Pvt. Ltd., Site Office, Mumbai

Authorized Signatory:

(Signature & Stamp)

Additionally, a Proforma Invoice (PI) is often requested from the vendor before placing the final purchase order. The PI provides a detailed quotation that includes item descriptions, quantities, pricing, taxes, and payment terms. It helps the buyer review costs, plan the budget, and initiate internal approvals before confirming the order. A well-documented PI ensures clarity and prevents disputes regarding pricing or scope.

Sample: Proforma Invoice (PI)

Proforma Invoice	**PI No.: CF/PI/2025/038**			
Date:	23-June-2025			
Seller:	Creative Furnishings 12 Industrial Estate, Pune - 411001			
Buyer:	XYZ Interiors Pvt. Ltd. 45 Design Street, Mumbai - 400021			
S. No.	**Item Description**	**Qty**	**Unit Price (INR)**	**Total (INR)**
1.	Office Workstations (6x2 ft)	10	12,000	1,20,000
2.	Ergonomic Office Chairs	10	6,500	65,000
3.	Storage Cabinets (3-door)	5	8,000	40,000
	Total Amount			**2,25,000**

Table 10.1.2:

Tax (18% GST): INR 40,500

Grand Total: INR 2,65,500

Bank Details:

Bank: HDFC Bank | A/C No.: 1234567890 | IFSC: HDFC0001234

Validity: This PI is valid for 15 days

Prepared by: Sales Team, Creative Furnishings

(Signature & Stamp)

6. **Tracking Deliveries:** Monitor the dispatch and arrival of ordered materials using shipment updates or vendor communication. Ensure that deliveries align with the project schedule and are ready for installation or use on-site.
7. **Quality Checking of Received Materials:** Inspect the delivered materials for quality, quantity, and conformance to specifications. Reject defective items and document discrepancies to maintain standards and avoid project delays or cost overruns.
8. **Final Payment and Documentation:** Once materials are verified and accepted, release the final payment as per agreed terms. Maintain proper documentation such as invoices, delivery challans, and inspection reports for accounting and audit purposes.

Elements of a procurement plan

A procurement plan is a strategic document that outlies how and when procurement activities will take place in a project. Following are the key elements of a procurement plan:

Fig. 10.1.3: Elements of a procurement plan

Key factors and sub-factors contributing to the evaluation of a procurement plan

The effectiveness of a procurement plan is judged based on the various factors as listed in the following table:

Key Factors	Sub-Factors
Cost Efficiency	Competitive pricing, budget compliance, negotiated discounts
Quality of Goods/ Services	Material durability, brand reputation, certification compliance
Vendor Reliability	Delivery timelines, service quality, past performance
Risk Management	Backup plans, vendor cancellation clauses, buffer timelines
Procurement Timelines	Delivery scheduling, lead times, integration with project phases
Regulatory Compliance	Tax documentation, contracts, safety and environmental standards

Table 10.1.3: Key factors and sub-factors contributing to the evaluation of a procurement plan

Sample: Procurement Plan

Item Name	Specifications	Estimated Cost (INR)	Proposed Vendor	Timeline (Delivery)	Approval & Delivery Notes
Modular Sofa Set	L-shaped, fabric upholstered, 5-seater, 2800mm x 1800mm	85000	Urban Living Furnishings	10 working days	Design approved by client; delivery to site directly
Track Lighting Fixtures	Black matte finish, 4 spots per unit, adjustable angle	24000	Lumos Lighting Co.	7 working days	Pending lighting layout confirmation; expedite delivery
Engineered Wood Flooring	Oak finish, 12mm thick, 1200mm x 200mm planks	96000	Floora Interiors Pvt. Ltd.	12 working days	Client requested wood shade sample; send for approval
Wall Paneling (Laminate Finish)	Walnut shade, 8ft x 4ft panels, fire-retardant	72000	DecoWall India	9 working days	Requires site-level measurement before dispatch
Conference Table	Solid wood top, 10-seater, built-in cable ports	55000	OfficeCraft Systems	15 working days	Approved design; delivery post flooring completion

Table 10.1.4:

Evaluating the procurement plan

An appropriate strategy to evaluate a procurement plan may include the following checks:

- Checklist-Based Review: Verify all elements like vendor credentials, documentation, schedules, and budgets
- Risk Assessment Matrix: Evaluate probability and impact of procurement delays or failures
- Cost-Benefit Analysis: Weigh supplier offerings in terms of cost vs quality
- Benchmarking: Compare against industry standards or past successful projects
- Stakeholder Feedback: Include inputs from design, finance, and site execution teams

Sample: Evaluation Checklist Template

Evaluation Criteria	Evaluation Questions	Evaluation Score (1-5)	Remarks
Cost-effectiveness	Is the cost within budget and reasonable compared to market rates?		
Timeline feasibility	Can the vendor deliver within the required timeframe?		
Vendor reliability	Does the vendor have a track record of successful and timely deliveries?		
Quality standards	Are the materials/products compliant with the expected quality benchmarks?		
Risk and contingency measures	Are there alternate vendors or buffer measures in case of delay or defect?		
Compliance with design specs	Do the items match the approved design specifications and requirements?		

Table 10.1.5:

10.1.2 Material Calculation and Optimization Processes

Accurate material calculation and optimization are essential for successful project execution. It prevents material shortage or excess, where underestimation can delay work and overestimation results in waste and higher costs. With optimized calculations one reduces site waste and supports environmental sustainability through smart layout planning and controlled wastage factors. Accurate estimates support timely procurement, ensuring vendors deliver materials on schedule. Proper batch planning ensures consistency by avoiding mismatched textures or colors. On-site efficiency is improved when materials are well-planned, labeled, and delivered for specific zones. These practices help in accurate budgeting, smoother scheduling, and building client trust and finally reducing the risk of delays, rework, or contract penalties.

The material calculation and optimization in interior design projects require technical understanding of:

- **Area and Volume Calculations:** Accurate room dimensions are used to determine material quantity (e.g., flooring in sq. ft., paint in liters).
- **Material Coverage Rate:** Each material has a coverage rate (e.g., 1 liter of paint covers 100 sq. ft.); this must be considered for accurate estimates.
- **Wastage Factors:** A standard buffer (5–10%) is added to accommodate cutting loss, breakage, or future patching needs.
- **Batch Matching:** Materials like tiles or fabrics should come from the same batch to ensure color/texture consistency.
- **Cutting and Joint Optimization:** Layout drawings help minimize waste by adjusting sizes and cutting directions.
- **Unit Conversion:** Converting between units (e.g., meters to feet, sheets to sqm) is essential during procurement documentation.

Let us understand with the help of an example for wooden flooring:

Step-by-Step:

1. **Measure Room Area:** Room size = 20 ft x 15 ft → 300 sq. ft.
2. **Check Material Coverage:** 1 box of engineered wooden planks covers = 20 sq. ft.
3. **Calculate Base Requirement:** 300 ÷ 20 = 15 boxes
4. **Add Wastage Factor (10%):** 15 x 1.10 = 16.5 → round up = 17 boxes
5. **Optimization:** Use layout plans to arrange planks with minimum cutting and align direction to reduce joins.
6. **Batch Consistency:** Mention “same batch code” in purchase order to avoid visual mismatch.

Hence, for a 20 ft × 15 ft room (300 sq. ft.), and with each box of wooden planks covering 20 sq. ft., the base requirement is 15 boxes. Adding a 10% wastage factor increases the total to 17 boxes. Optimization is done by planning the layout to minimize cuts and joins. To ensure visual consistency, the same batch code should be requested during procurement.

10.1.3 Tender Docket

A tender docket refers to the complete set of official documents issued to potential vendors or contractors when an organization invites bids for a specific project or procurement. It acts as a comprehensive bidding package that includes all the necessary information a vendor needs to understand the project scope, technical and material specifications, timelines, legal terms, and submission guidelines.

A tender docket typically includes the following essential documents:

Invitation to Tender (ITT)	**Scope of Work (SOW)**	**Technical Specifications**	**Bill of Quantities (BOQ)**
Drawings and Layout Plans	**Terms and Conditions**	**Eligibility Criteria & Vendor Qualifications**	**Timeline and Milestones**
Material Specifications and Finishes	**Tender Submission Format and Instructions**	**Evaluation Criteria**	**Contractual Clauses (payment terms, penalties, warranty, etc.)**
	Compliance and Legal Declarations	**Previous Work Samples/References (if required)**	

Fig. 10.1.4: Documents in tender docket

Each document supports decision-making, risk mitigation, and ensures fair and comparable bid submissions.

Role of Different Documentations in a Tender Document

- Invitation to Tender outlines the purpose and scope, inviting eligible vendors to participate.
- Scope of Work defines the detailed tasks, deliverables, and project expectations.
- Technical Specifications ensure that the vendor understands the exact material and quality requirements.
- BOQ allows all bidders to quote uniformly based on a standard list of materials and quantities.
- Drawings and Layouts help bidders visualize spatial requirements and plan logistics.
- Terms and Conditions protect both parties legally by specifying contract obligations.
- Evaluation Criteria clarify how bids will be assessed, ensuring transparency.
- Compliance Declarations confirm that vendors meet statutory and regulatory requirements.

Process of Tender Document Preparation Based on Required Material Specifications

The following figure represents the process of tender document preparation based on required material specifications

Fig. 10.1.5: Process of Tender Document Preparation

1. **Requirement Gathering:** Collect design specifications, material details, and client preferences from project leads and design teams.
2. **Prepare Technical Specifications:** Define product types, finishes, dimensions, quality standards, and application zones.
3. **Draft BOQ:** Break down materials by location and usage, specify units of measurement, and estimated quantities.
4. **Include Reference Drawings:** Add CAD-generated floor plans, elevations, or 3D views that reflect design intent.
5. **Define Eligibility Criteria:** Set vendor qualification norms based on past experience, financial capability, and specialization.
6. **Add Legal and Commercial Terms:** Include timelines, payment terms, penalties for delays, warranty clauses, etc.
7. **Review with Project Stakeholders:** Internal review to verify accuracy and alignment with design and execution plans.
8. **Float the Tender:** Issue tender to shortlisted vendors or publish it on relevant portals for bidding.
9. **Clarifications and Corrections (Pre-bid):** Address vendor queries and, if needed, revise the tender before the submission deadline.

This structured preparation ensures procurement aligns with project quality, budget, and timelines.

UNIT 10.2: Quality Check

Unit Objectives

At the end of this unit, the participants will be able to:

1. List all the key quality indicators for Quality Checking (QC) of procured materials.
2. Identify and inspect the procured materials for given quality indicators.
3. Discuss the role of intrinsic quality checking for inefficiency in project execution.
4. Discuss the role of intrinsic quality checking for inefficiency in project execution.
5. Identify the on-site assembly and installation process based on various intrinsic quality parameters.

10.2.1 Quality Check

Key quality parameters are set to ensure that procured materials meet design specifications, safety standards, and functional requirements. They help prevent defects, ensure consistency, support cost control, and contribute to the overall durability and success of the interior design project.

Key Quality Parameters are as follows:

1. **Material Specification Compliance:** Check if the material meets design specifications (e.g., size, texture, thickness, grade).
2. **Surface Finish & Appearance:** Ensure there are no scratches, cracks, or discoloration.
3. **Dimensional Accuracy:** Measure to verify length, width, thickness, or other geometric tolerances.
4. **Strength & Durability:** Assessed based on manufacturer standards or tests.
5. **Moisture Content (for wood):** Wood should meet moisture threshold (generally 8–12%) to avoid warping or decay.
6. **Batch/Brand Consistency:** Materials from different batches should not have color or texture mismatch.
7. **Packaging & Labeling:** Materials should be sealed, labeled correctly, and free from transport damage.
8. **Documentation Compliance:** Check for invoices, warranty cards, batch test certificates, MSDS (Material Safety Data Sheet), etc.
9. **Certification Verification:** Ensure that all materials and products are certified by government-authorized agencies or third-party quality assurance bodies. Look for compliance with industry standards such as ISO certification, ISI mark, or other equivalent quality certifications. This step helps validate the safety, reliability, and performance of the materials being used.

Following is the list of internationally accepted standards associated with the Quality Control (QC) of procured materials used in interior design and construction. These standards ensure consistency, safety, durability, and regulatory compliance in materials selection and usage.

Wood and Plywood

Test / Parameter	Standard	Description
Moisture Content	ASTM D4442 / ISO 16979	Standard test method for direct moisture content determination in wood.
Boiling Water Resistance (BWR)	IS 303 (Indian Standard), ANSI/HPVA HP-1	Checks if plywood can withstand water exposure.
Formaldehyde Emission	EN 717-1 / ASTM D6007	Measures release of formaldehyde from wood panels.

Table 10.2.6: Test Parameters and Standards for Wood and Plywood

Tiles and Stone

Test / Parameter	Standard	Description
Water Absorption	ISO 10545-3 / ASTM C373	Determines porosity for ceramic and stone tiles.
Breaking Strength	ISO 10545-4 / ASTM C648	Evaluates load-bearing capacity of tiles.
Scratch Resistance	MOHS Scale / EN 101	Measures hardness and surface durability.

Table 10.2.7: Test Parameters and Standards for Tiles and Stone

Paints and Coatings

Test / Parameter	Standard	Description
Adhesion Test	ASTM D3359	Measures bonding of paint to the surface.
VOC Content	ASTM D3960 / ISO 11890-2	Controls Volatile Organic Compounds emissions.
Finish and Gloss Consistency	ASTM D523	Tests gloss level of a painted surface.

Table 10.2.8: Test Parameters and Standards for Paints and Coatings

Fabrics and Upholstery

Test / Parameter	Standard	Description
Rub Test (Abrasion Resistance)	Martindale (ISO 12947) / Wyzenbeek (ASTM D4157)	Determines wear and durability of fabric.
Color Fastness	ISO 105 Series	Checks color retention against washing, rubbing, light.

Table 10.2.9: Test Parameters and Standards for Fabrics and Upholstery

Glass and Glazing Materials

Test / Parameter	Standard	Description
Toughened / Tempered Glass Test	EN 12150 / ASTM C1048	Ensures glass safety through fragmentation pattern.
Impact Resistance	EN 12600	Tests how glass performs against impact.
Thickness Tolerance	ASTM E1300	Defines load resistance based on glass thickness.

Table 10.2.10: Test Parameters and Standards for Glass and Glazing Materials

Metals (Steel, Aluminum)

Test / Parameter	Standard	Description
Tensile Strength	ASTM A370	Standard for mechanical testing of steel products.
Corrosion Resistance	ASTM B117 (Salt Spray Test)	Evaluates protective coatings on metal surfaces.

Table 10.2.11: Test Parameters and Standards for Metals

General Construction Materials

Test / Parameter	Standard	Description
Material Identification & Traceability	ISO 9001:2015 / ISO 14001:2015	Quality Management System standards ensure traceability and sustainability.
Safety & Sustainability Compliance	LEED / BREEAM / IGBC	Evaluates environmental impact and compliance with green building practices.

Table 10.2.12: Test Parameters and Standards for General Construction Material

Quality Check Procedure of Procured Materials:

1. **Inspection on Delivery**
   - Visual inspection at the time of receipt at site/store for any damage or mismatch.
2. **Cross-Check with PO & Specifications**
   - Match materials against the Purchase Order and tender specifications.
3. **Sampling for Testing**
   - Select random samples for lab or field testing.
4. **Dimensional & Physical Verification**
   - Use measuring tools (scale, caliper, moisture meter) to verify material dimensions and condition.
5. **Documentation Verification**
   - Verify test reports, warranty certificates, and compliance documents from the vendor.
6. **Tagging and Logging**
   - Tag approved materials and record in QC register. Reject defective ones and raise NCR (Non-Conformance Report).

7. **Client/Consultant Approval (if required)**
    - o High-value or design-sensitive items may require consultant/client sign-off.

The following table lists the suitable quality tests to ensure standards of procured materials

Material Type	Test	Purpose
Wood	Moisture Content Test (via Moisture Meter)	Prevents warping, cracking
Tiles & Stone	Water Absorption Test, Scratch Test	Ensures durability and slip resistance
Paints & Coatings	Adhesion Test, Finish Uniformity Check	Ensures proper bonding and aesthetics
Glass	Temper Test, Thickness Gauge	Safety and impact resistance
Fabrics & Upholstery	Rub Test (Martindale), Colorfastness Test	Checks wear resistance and color durability
Plywood/Boards	Boiling Water Resistance Test (for BWR grade)	Confirms grade and strength under moisture
Metals	Thickness Test, Rust Test	Confirms gauge and corrosion resistance

Table 10.2.13: Quality Tests

10.2.2 Quality Control During Project Execution

Regular quality checks are essential to ensure that the interior design project is executed as per approved specifications, drawings, and standards. These checks help in:

- **Identifying defects early –** Catching errors before they escalate reduces rework and saves cost.
- **Ensuring compliance –** Verifies that the work aligns with design, material, and regulatory standards.
- **Maintaining consistency –** Regular checks across all zones of the site ensure uniform workmanship.
- **Improving client satisfaction –** Quality work enhances visual and functional appeal, building client trust.
- **Preventing delays –** Timely issue resolution keeps the project on track.
- **Supporting documentation – Quality checklists form part of project records, useful for audits and handover.**

Perform Quality Check During Project Installation Stage Using Appropriate Tools and Equipment

Quality checks during installation focus on the actual implementation of design elements such as flooring, furniture, lighting, or partitions. Following is the Step-by-Step Quality Check Process:

1. **Review Approved Drawings and BOQ:** Cross-check what's being installed against the approved design, layout, and material specifications.

2. **Use Measuring Tools:**
    - Laser levels or spirit levels for alignment and leveling (e.g., ceiling panels, wall partitions)
    - Measuring tapes and distance meters for dimensions
    - Plumb bobs for verticality (e.g., cabinet installation)
3. **Material Verification:** Confirm materials match the approved samples in texture, color, thickness, and batch codes (e.g., tiles, laminates).
4. **Surface and Finish Inspection:** Check for the following:
    - Scratches, dents, or stains
    - Proper edge finishes
    - Paint/coating consistency
5. **Functionality Checks:** Test drawers, doors, lights, and switches for smooth operation.
6. **Safety and Compliance:** Ensure electrical and fire safety standards are met using tools like:
    - Circuit testers
    - Thermal scanners (if applicable)
7. **Documentation:** Use quality control checklists, inspection reports, and photo documentation to record the outcome.

Field Visit Activity: On-Site Inspection of Installation Execution

Objective:

To enable participants to observe and document whether interior design installations are being executed as per the approved design specifications and quality standards.

Instructions

1. **Pre-Visit Preparation:**
    - Review approved layout drawings, BOQ, and design specifications.
    - Prepare a Site Observation Checklist (provided below).
    - Carry measuring tools (tape, laser level), safety gear (helmet, boots), and notepad or tablet.
2. **On-Site Tasks:**
    - Walk through the ongoing installation zones (e.g., ceiling, flooring, partitions, lighting).
    - Check if:
        - Materials used match the design specs
        - Dimensions and placement are as per drawings
        - Finishing quality is acceptable (no dents, scratches, stains)
        - Alignment and level are accurate
        - Services (electrical, plumbing) are installed as per design
3. **Use of Tools:**
    - Tape measure / laser meter: for verifying dimensions
    - Spirit level / laser level: for checking alignment
    - Plumb bob: for vertical alignment
    - Camera: for photo documentation

4. **Recording Observations:**
   - Fill out the checklist
   - Take photographs with annotations
   - Note any deviations or areas of concern
5. **Post-Visit:**
   - Submit a brief report highlighting:
     - Conformities and non-conformities
     - Suggestions for corrective action
     - Questions or doubts for the site engineer

Sample Site Observation Checklist:

Installation Item	As per Design? (Y/N)	Quality OK? (Y/N)	Comments/Deviation
False Ceiling Layout			
Electrical Switchboards			
Tile Flooring			
Furniture Placement			
Wall Paneling Finish			
Paint/Polish Quality			

Table 10.2.14:

UNIT 10.3: Project Installation and Handover

Unit Objectives

At the end of this unit, the participants will be able to:

1. Explain the documentation formalities associated with the project closure and handover.
2. Identify the steps involved in performing client walk-throughs.
3. Prepare project closure and handover report upon project completion.
4. Define the term Knowledge Sharing and its impact on an organization's communication.
5. Differentiate between internal and external communication methods.

10.3.1 Managing Project Execution, Variations, and Handover

Redressal of Variations in project execution refers to the process of identifying, evaluating, and resolving any deviations or changes that occur during the implementation of a project, particularly when compared to the original approved design, scope, specifications, budget, or timeline.

Variations in project execution refer to deviations from the approved design, timeline, or scope. The steps involved in addressing them include:

Fig. 10.3.1:

- **Identification:** Identify the deviation during routine checks or through stakeholder input.
- **Documentation:** Record the variation with reference to original design/specification.
- **Analysis:** Assess its impact on time, cost, and quality.
- **Consultation:** Involve relevant teams (design, execution, client) to propose corrective actions.
- **Approval:** Get formal approval for the changes from the project authority or client.
- **Implementation:** Apply the changes with revised scope, drawings, or materials.
- **Verification:** Inspect and ensure the variation is correctly executed as per the revised plan.

Let us understand with an Example of False Ceiling Design Variation in a Commercial Office Project

Original Plan: The approved interior design for a commercial office includes a plain gypsum board false ceiling with embedded LED panel lights.

During Execution: The client requests a change to include a grid-style acoustic ceiling for better sound absorption in the conference rooms.

Redressal Process:

1. **Identification:**

   Site engineer flags the change request from the client as a design variation.

2. **Documentation:**

   The new ceiling type and materials are documented against the original design, with updated specifications and impact notes.

3. **Analysis:**

   The design team evaluates the impact:

   - Material cost increases by 15%
   - Ceiling height will reduce slightly
   - Electrical wiring layout needs rework

4. **Consultation & Approval:**

   The change is discussed with the client, procurement team, and contractor. Approval is obtained with revised drawings.

5. **Implementation:**

   The new ceiling is installed using acoustic panels, and wiring is adjusted accordingly.

6. **Verification:**

   Post-installation, a quality check confirms that the change meets acoustic performance and aesthetic expectations.

Result:

Variation is successfully redressed without project delay, client satisfaction is maintained, and records are updated for billing and future reference.

Importance of Time Management and Usage of Effective Record Keeping Techniques for Project Execution

Time management is crucial in interior design projects to meet delivery deadlines and avoid cost overruns. Proper scheduling ensures timely procurement, workforce planning, and task coordination. Record-keeping supports this by:

- **Maintaining accurate logs of site activities, delays, and issues**
- **Tracking procurement and installation timelines**
- **Documenting communications, approvals, and decisions**
- **Ensuring transparency and accountability**
- **Generating reports and updates for supervisors and clients**

Fig. 10.3.2: Benefits of Record-Keeping

Effective record-keeping involves maintaining both physical and digital records of all project-related activities, including:

Daily site reports:	Document work progress, manpower, and equipment used
Material logs:	Track receipt, inspection, and usage of materials
Quality checklists:	Maintain inspection and test records
Communication records:	Emails, minutes of meetings, or approvals

Fig. 10.3.3: Report and Records

Timely reporting supports informed decision-making and ensures smooth coordination across teams. It includes:

- Submitting weekly/monthly progress reports
- Raising alerts for deviations, delays, or safety concerns
- Sharing updates on milestone completion
- Reporting snag lists or rectifications completed

10.3.2 Role of Effective Communication Skills Required for Interior Designer

Effective communication is an essential skill for interior designers, as it directly impacts the success of their projects. The role of a designer involves working closely with clients, contractors, suppliers, and various team members to bring the vision to life while meeting functional, aesthetic, and budgetary requirements. Below is a detailed discussion on the importance of communication skills in interior design, highlighting various communication aspects and their relevance to different aspects of the job.

Client Interaction and Understanding Needs

Effective Communication in Client Consultation – The first step in any interior design project is understanding the client's vision, preferences, and expectations. An Assistant Interior Designer must listen actively, ask the right questions, and express their understanding clearly. Effective communication at this stage helps to:

- **Clarify client requirements –** Understanding the style, function, and budget is crucial for any successful design.
- **Manage client expectations –** Ensuring that the client's vision aligns with practical and design limitations, including budget constraints, space limitations, and timeline.
- **Build rapport and trust –** Open and transparent communication fosters a positive working relationship, making it easier to collaborate throughout the project.

Example – In an interior design project for a luxury apartment in, the Assistant Interior Designer's communication skills are essential in understanding the client's desire for a modern yet luxurious space. Clear discussions about materials, budget, and timeline would ensure The Assistant Interior Designer's vision aligns with the client's needs.

Presenting Ideas and Design Concepts

Interior designers must present their ideas to clients using various forms of communication, from mood boards to 3D renderings, and verbal explanations. Effective presentation skills include:

- **Clear articulation of design ideas:** Communicating how the design meets the client's requirements and explaining design choices (materials, colours, layout).
- **Visual aids:** Using tools like sketches, drawings, 3D models, and physical samples to help clients visualize the space.
- **Effective storytelling:** Being able to tell a compelling story about how the design will transform the space and meet their personal or functional needs.

Example – In a residential project, the Assistant Interior Designer might use a 3D rendering to show the client how their apartment will look after the redesign. The Assistant Interior Designer must explain the material choices, layout changes, and the rationale behind every design decision.

Coordinating with Contractors and Suppliers

An APM often acts as the middleman between the client and the contractors. Effective communication with contractors and suppliers ensures:

- **Clarity in instructions:** Designers must communicate their design intent clearly to contractors to avoid misunderstandings and errors during construction or installation.
- **Setting expectations and timelines:** It is important to discuss time frames, budgets, and quality expectations upfront to ensure the project proceeds smoothly.
- **Conflict resolution:** Communication skills are critical when issues arise between the client, contractor, or suppliers, helping to resolve conflicts promptly and professionally.

Example – For a hospitality project, where the design includes custom-built furniture, The APM must clearly communicate detailed measurements, material specifications, and timelines to ensure the contractor delivers as per the agreed design.

Collaborating with Team Members

In many cases, interior designers work alongside other professionals, such as architects, lighting designers, and landscape designers. Effective collaboration involves:

Fig. 10.3.4:

- **Coordinating ideas:** Designers need to ensure that their vision aligns with that of other team members, such as architects ensuring that structural constraints align with the interior design.
- **Problem-solving:** Interior designers must work with engineers and contractors to solve any challenges that arise during construction, whether it's related to material delivery or technical difficulties.
- **Feedback exchange:** Designers must both give and receive feedback from various team members to refine designs, improve execution, and ensure quality.

Example – In a commercial office project, The APM must communicate with the lighting consultant to ensure that lighting complements the overall interior design. Clear discussions ensure that the lighting enhances the design aesthetics and provides adequate functionality.

Negotiation Skills with Clients and Suppliers

As part of their role, interior designers are often required to negotiate on behalf of their clients to ensure they get the best value for their budget. This may involve:

- Negotiating with suppliers for the best prices on furniture, fixtures, and materials while maintaining quality.

- Managing costs and discussing possible compromises with clients to stay within the budget.
- Managing timelines: Negotiating realistic timelines with contractors to meet the client's expectations without compromising the quality of the project.

Example – For a restaurant design project, The Interior Designer along with APM and purchase manager may need to negotiate with the furniture supplier for better prices on high-end seating or a timely delivery of materials to meet the project's schedule.

Managing Expectations and Handling Criticism

Designers often need to manage clients' expectations throughout the project and adjust the design if necessary. Effective communication in this aspect involves:

- **Accepting and interpreting feedback:** Listening to the client's feedback or concerns and responding thoughtfully while offering solutions.
- **Educating clients:** Explaining design decisions and helping clients understand why certain compromises need to be made (e.g., due to budget or space constraints).
- **Reassuring clients:** Addressing concerns or doubts by providing clear explanations about timelines, materials, or design elements.

Example – In a residential redesign project, the client may request several changes after seeing the initial design concept. The APM must respond politely, explaining why certain changes are or are not feasible and suggesting suitable alternatives.

Written Communication for Documentation and Proposals

Interior designers also need strong written communication skills for tasks such as:

- **Design proposals:** Writing clear and detailed design proposals that outline the scope of work, timeline, materials, and costs.
- **Contract agreements:** Preparing contracts that clearly define deliverables, timelines, and expectations to ensure all parties are on the same page.
- **Project updates:** Providing written progress reports to clients or stakeholders detailing the status, any changes, and upcoming milestones.

Example – In a residential renovation project, the APM sends weekly progress reports to the client outlining completed work, upcoming tasks, and any adjustments to the budget or timeline.

Marketing and Client Acquisition

For independent designers or design firms, effective communication also plays a role in marketing and client acquisition. This includes:

- **Promotional materials:** Those materials which an Interior designer promotes in a paid collaboration or in general collaboration.
- **Portfolios:** These includes work and pictures of various projects and helps reflect a designer's unique style & capability.
- **Networking:** Effective verbal communication in meetings, conferences, or industry events can help build connections and secure new clients.
- **Pitching ideas:** When meeting potential clients, being able to pitch ideas in a clear, confident, and engaging way can make a big difference in attracting business.

Example – A designer may create an online portfolio that communicates their design philosophy and past work effectively, attracting potential clients who appreciate their style.

Summary

- Procurement planning involves identifying project needs, researching vendors, requesting quotes, negotiating terms, issuing purchase orders, tracking deliveries, and quality checks.
- Essential documentation in procurement includes BOQ, specification sheets, tender documents, contracts, and vendor invoices to ensure transparency and budget compliance.
- Procurement plan evaluation is based on factors like cost-efficiency, vendor reliability, quality standards, risk management, regulatory compliance, and delivery timelines.
- Material Calculation & Optimization uses area/volume calculations, material coverage rates, wastage factors, and batch consistency for precise procurement and reduced on-site wastage.
- Tender Docket Preparation includes the invitation to tender, scope of work, technical specs, BOQ, drawings, legal terms, and evaluation criteria to guide vendor bidding and selection.
- Material quality is assessed using international standards (e.g., ASTM, ISO) for parameters like strength, finish, moisture content, VOC levels, and batch uniformity.
- Quality Check Tools includes Measuring tapes, spirit levels, plumb bobs, moisture meters, and documentation like QC checklists and NCR reports ensure accuracy during installation.
- Installation Quality Assurance includes verifying materials, checking alignment, finish, and functionality to match the approved drawings and specifications.
- Managing deviations includes identification, documentation, stakeholder consultation, implementation, and verification of variations.
- Effective verbal and written communication support client interaction, supplier coordination, team collaboration, negotiation, documentation, and project marketing.

Exercise

Multiple Choice Questions (MCQs)

1. During procurement, which of the following documents ensures that all vendors quote based on uniform specifications and quantities?

   a) Warranty card

   b) Material Safety Data Sheet

   c) Bill of Quantity (BOQ)

   d) Purchase Order

   Answer: c) Bill of Quantity (BOQ)

2. Which parameter ensures that wooden materials will not warp due to moisture absorption?

   a) Adhesion test

   b) Moisture content test

   c) Scratch resistance test

   d) Rub test

   Answer: b) Moisture content test

3. What is the primary objective of preparing a tender docket?

   a) To finalize interior design themes

   b) To maintain records of client meetings

   c) To invite vendors for project bidding and specify all requirements

   d) To calculate site area and volume

   Answer: c) To invite vendors for project bidding and specify all requirements

4. In quality control, which tool is used to check the vertical alignment of wall panels?

   a) Spirit level

   b) Moisture meter

   c) Plumb bob

   d) Laser cutter

   Answer: c) Plumb bob

5. Why is effective record-keeping important in project execution?

   a) It helps in increasing product sales

   b) It reduces the amount of procurement paperwork

   c) It supports coordination, accountability, and informed decision-making

   d) It allows avoiding the use of technical specifications altogether

   Answer: c) It supports coordination, accountability, and informed decision-making

Hands-On Activity: Evaluate a Procurement Plan Using a Strategy Framework

Objective:

To apply a structured evaluation strategy to assess the accuracy, completeness, feasibility, and risk level of a procurement plan for an interior design project.

Materials Provided to Each Group:

- A sample procurement plan (real or simulated) that includes:
  - Item list with specifications
  - Cost estimates
  - Vendor list
  - Timeline
  - Approval and delivery notes
- Evaluation Strategy Checklist Template:
  - Cost-effectiveness
  - Timeline feasibility
  - Vendor reliability
  - Quality standards
  - Risk and contingency measures
  - Compliance with design specs

Activity Steps:

1. **Review the Procurement Plan**
   - Go through the sample plan in your group using the provided strategy checklist.
2. **Apply the Evaluation Strategy**
   - Assess whether the procurement plan:
     - Aligns with budget
     - Covers all required items
     - Has realistic timelines
     - Includes reliable vendors
     - Has backup options
     - Matches the interior design specifications
   - Mark risks and improvement areas.
3. **Prepare Summary of Evaluation**
   - Draft 5–7 key observations with suggestions for improvement.
4. **Present Your Evaluation**
   - Each group gives a 2-minute verbal presentation.

Exercise

Multiple Choice Questions (MCQs)

1. What is the primary purpose of a site recce?
   a. To install the furniture
   b. To finalize the budget only
   c. To assess physical site conditions and constraints
   d. To begin civil construction

2. Why is a regular site survey important during execution?
   a. To hire more workers
   b. To check salary disbursement
   c. To detect errors and ensure quality work
   d. To conduct interior photoshoots

3. What is the primary reason for delegating tasks based on individual skill sets?
   a. To avoid employee dissatisfaction
   b. To increase documentation workload
   c. To improve task efficiency and project execution
   d. To follow labor laws

4. What is the purpose of preparing a recce/site survey report?
   a. To estimate team size
   b. To finalize the project layout
   c. To assess the site and avoid miscommunication or delays
   d. To replace the need for a site visit

5. Which document serves as a client's confirmation that the site survey was conducted?
   a. Measurement sheet
   b. Observation notes
   c. Client or POC acknowledgment
   d. Approval log

Notes

Scan the QR codes or click on the link to watch the related videos

https://www.youtube.com/watch?v=AxOeDE8cP8k

Project Procurement Basics

https://www.youtube.com/watch?v=mQUUs7MLDK8&t=5s

Handover pack for your interior designers

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

11. Health, Safety and Hygiene Protocols while Designing

Unit 11.1: Health and Safety Protocols
Unit 11.2: Hygiene, PPE and Worksite Practices
Unit 11.3: Emergency Preparedness and Response
Unit 11.4: Safety Signs

FFS/N8207

Key Learning Outcomes

At the end of this module, the participant will be able to:

1. Identify all the health and safety protocols associated with working at the worksite.
2. Appraise suitable health and hygiene protocols while working at the worksite.
3. Explain various health and safety hazards associated with the project execution during construction and subsequent maintenance.
4. Analyze and identify worksite site hazards during construction and subsequent maintenance.
5. Explain the importance of an effective health and safety plan during project execution.
6. Explain how to design and implement a health and safety plan for the worksite
7. Identify the poor organizational practices concerning hygiene, food handling, cleaning.
8. Explain the importance of using Personal Protective Equipment (PPE) based on the manufacturer's instructions and how to use it at the worksite.
9. Identify the health and safety measures associated with the project designs.
10. Examine the project design for proper implementation of health and safety measures.
11. Explain the significance of maintaining work ethics, dress code, and personal hygiene.
12. Explain the importance of workplace sanitization and demonstrate the correct way of sanitizing and washing hands.
13. Explain the operational guidelines for the usage of emergency tools and equipment.
14. Explain the steps involved in responding to an emergency (fire, short circuit, accidents, earthquake, etc.) process in line with organizational protocols.
15. Explain the first aid procedures in case of emergency and demonstrate CPR.
16. Identify all the concerned control measures while working at the worksite.
17. Identify suitable methods to communicate necessary control measures to concerned team members.
18. Explain the types of hand signals and signage and their application.
19. Identity and interpret the given pictorial representations of safety signs and hand signals.

UNIT 11.1: Health and Safety Protocols

Unit Objectives

At the end of this unit, the participants will be able to:

1. Identify all the health and safety protocols associated with working at the worksite.
2. Appraise suitable health and hygiene protocols while working at the worksite.
3. Explain various health and safety hazards associated with the project execution during construction and subsequent maintenance.
4. Analyze and identify worksite site hazards during construction and subsequent maintenance.
5. Explain the importance of an effective health and safety plan during project execution.
6. Explain how to design and implement a health and safety plan for the worksite

11.1.1 Health and Safety Protocols for Worksite (Interior Design)

Health and safety protocols refer to a set of guidelines, rules, and practices put in place to ensure the safety, well-being, and protection of individuals in various environments, such as workplaces, public spaces, homes, or during activities. These protocols are designed to prevent accidents, injuries, or health issues and to mitigate risks. The health and protocols associated with working at the worksite are:

Personal Protective Equipment (PPE) – The following items must be worn at all costs while working at the worksite:

Safety Gloves - To protect hands from sharp objects, chemicals, or rough surfaces.

Safety Goggles - To protect eyes from dust, debris, and fumes, especially when working with certain materials like paint or adhesives.

Dust Masks/Respirators - To protect against inhaling dust, fumes, and hazardous particles, especially in poorly ventilated areas.

Protective Footwear Non-slip, steel-toe boots to protect feet from heavy objects or accidental injury.

Fig. 11.1.1: PPE for interior design projects

Site Organisation – The worksite should be maintained and organised in a way that stops any accidents from happening. The walkways and working areas should be free of unnecessary clutter. The raw materials and objects must be organized and stored in secure locations to avoid accidents, such as heavy objects falling or causing obstruction and there should be a use of warning signs, especially in areas where hazards like electrical wiring, wet floors, or equipment use are present.

The following images show us examples of warning signs and how they are used

A traffic cone on a road is an example of a warning sign - it signals the drivers or pedestrians that there is construction work ahead.

A stop sign is used to indicate that a person or a passerby must stop before crossing a certain area.

Fig. 11.1.2: Examples of warning signs

Equipment Safety – It is important to ensure that that power tools and machinery have proper guarding in place to prevent injuries. Power tools and hand tools should also have proper maintenance and inspection to ensure they are in safe working condition. There should be a training on using ladders and scaffolds and ensuring that they are safe to use.

A ladder

A worker using a scaffold

Fig. 11.1.3: Examples of warning signs

Hazardous Materials Handling – To safely handle paints, solvents, and adhesives, use proper ventilation and follow manufacturer instructions for handling and storing chemicals. To be safe from chemical spills and burns, ensure all team members have access to MSDS (Material Safety Data Sheet) for chemicals used and know how to handle emergencies such as spills or exposure.

Hygiene and Sanitation – To maintain hygiene and sanitation, these following points are followed:



Fig. 11.1.4: Hygiene and sanitation best practices

11.1.2 Health and Hygiene Protocols

When working on an interior design project, it is essential to follow suitable health and hygiene protocols to ensure the safety and well-being of everyone on the worksite. This includes the designer, contractors, workers, and clients.

Sanitation and Cleanliness

Regular Handwashing: Ensure that workers wash their hands regularly, especially after handling chemicals, materials, or eating. Provide handwashing stations with soap and water or alcohol-based hand sanitizers on-site.

Disinfecting Surfaces: Frequently disinfect commonly touched surfaces like door handles, light switches, tools, and work areas to prevent the spread of germs and bacteria.

Work Area Cleanliness: Maintain a tidy worksite by ensuring all tools, materials, and waste are properly stored or disposed of. A clutter-free space reduces the risk of tripping and keeps the environment hygienic.

Fig. 11.1.5: Cleanliness best practices

Ventilation

Adequate Ventilation: Ensure that the worksite is well-ventilated, especially when using products like paints, adhesives, varnishes, or solvents that can emit harmful fumes. Open windows, use exhaust fans, or provide fans to circulate fresh air.

Air Filtration Systems: For high-risk environments or areas where chemicals are heavily used, air filtration systems can help filter out harmful airborne particles and fumes.

Open windows

Install air ducts

Fig. 11.1.6: Ventilation best practices

Hygiene Protocols for Clients (When Working in Residential or Commercial Spaces):

- **Personal Hygiene:** Ensure workers maintain good personal hygiene, including clean uniforms, handwashing, and keeping their work area organized.
- **Minimize Dust and Debris:** When working indoors, minimize dust and debris by using dust barriers, plastic sheeting, and vacuuming workspaces as needed to avoid the spread of dust and allergens.
- **Consider Clients' Health:** If working in a home or office, be mindful of allergies or respiratory issues that clients may have. Choose low-VOC paints, non-toxic materials, and avoid using products that could trigger reactions.

Waste Management:

- **Waste Disposal Protocols:** Establish a system for waste disposal to ensure that items like packaging materials, old fixtures, or broken items are properly discarded. Separate recyclables and non-recyclables and dispose of them according to local guidelines.
- **Recycling Materials:** Where possible, encourage recycling of materials like cardboard, metal, and plastic. Make sure all workers are aware of proper recycling protocols.

Breaks and Rest Periods:

- **Scheduled Breaks:** To maintain good health and avoid exhaustion, ensure that workers take regular breaks, especially when working long hours or in stressful conditions. Proper rest is essential for physical and mental well-being.
- **Hydration and Nutrition:** Provide access to clean drinking water and encourage workers to stay hydrated. Offer nutritious snacks and meals to maintain energy levels throughout the day.

11.1.3 Identifying Health and Safety Hazards

Some of the hazards during project execution include workers being exposed to harmful particles when sanding or painting. Heavy lifting of furniture, materials, or equipment can cause strain and injury, especially if workers are not trained in proper lifting techniques. When cables, tools, and materials are left around the worksite, there may be accidents that can occur. Some sharp objects like cutting tools could cause cuts or puncture wounds. When installing lighting, wiring, or electrical fixtures, workers may be exposed to the risk of electrocution. During maintenance these following hazards can occur in the worksite:

Structural Integrity Issues	If maintenance involves handling or repairing the building's structural elements, such as walls or ceilings, there may be risk of collapse or injury.
Confined Spaces	Workers may need to enter smaller, confined areas like ducts, ceiling spaces, or basements, where ventilation and accessibility could pose risks.
Exposure to Mold or Asbestos	During renovation or maintenance, older buildings may have mold or asbestos, which can lead to respiratory issues or other health problems

Fig. 11.1.7: Hazards at construction site

In the following image, you can learn the different ways in which hazards can be identified:



Fig. 11.1.8: Identifying hazards

The assessment of risks and their mitigation measures are:



Fig. 11.1.9: Mitigating risks and hazards

The importance of an effective health and safety plan during project execution is given in the following figure:

Prevents Accidents and Injuries

A well-established health and safety plan reduces the likelihood of accidents, which protects workers and helps avoid costly delays due to injury or damage.

Compliance with Legal and Regulatory Requirement

Many countries have strict regulations on workplace health and safety. An effective plan ensures compliance with OSHA (Occupational Safety and Health Administration) guidelines or local regulations, helping avoid legal repercussions.

Reduces Financial Costs

By preventing accidents, a safety plan minimizes medical bills, insurance claims, and potential fines due to non-compliance.

Enhances Worker Morale

Workers are more likely to feel valued and secure if they know their employer is committed to their safety and well-being.

Promotes Efficient Project Execution

A safe working environment means fewer disruptions, more productivity, and a smoother workflow for the project.

Fig. 11.1.10: Importance of an effective health and safety plan

The steps for designing and implementing a health and safety plan for the worksite are as follows:

Step 1: Conduct a Site Risk Assessment



Fig. 11.1.11: Risk assessment

Step 2: Develop Safe Work Practices



Fig. 11.1.12: Safe work practices

Step 3: Assign Responsibilities

Designate a safety officer to oversee health and safety practices.

Assign specific safety tasks to supervisors and workers, such as conducting tool inspections or managing waste disposal.

Fig. 11.1.13: Assigning responsibilities

Step 4: Provide Training and Resources

- Conduct regular safety training sessions, ensuring workers are educated on the risks and protocols.
- Supply workers with the necessary PPE and ensure it is properly maintained.

Step 5: Emergency Procedures and First Aid

- Develop clear emergency protocols, including evacuation routes, first aid procedures, and contact information for emergency services.
- Ensure first aid kits are stocked and that workers are trained in basic first aid.

Step 6: Regular Monitoring and Auditing

- Monitor the worksite continuously for compliance with safety standards.
- Conduct regular audits and inspections to identify any new hazards or areas needing improvement.

Step 7: Review and Revise the Safety Plan

- After every significant project phase or after any accident, review the safety plan to ensure it remains effective.
- Update the plan as necessary based on new risks, lessons learned, or changes to regulations.

By implementing a comprehensive health and safety plan, interior design projects can proceed smoothly while prioritizing the well-being of workers and ensuring a safe environment throughout construction and maintenanceTop of Form

UNIT 11.2: Hygiene, PPE and Worksite Practices

Unit Objectives

At the end of this unit, the participants will be able to:

1. Identify the poor organizational practices concerning hygiene, food handling, cleaning.
2. Explain the importance of using Personal Protective Equipment (PPE) based on the manufacturer's instructions and how to use it at the worksite.
3. Identify the health and safety measures associated with the project designs.
4. Examine the project design for proper implementation of health and safety measures.
5. Explain the significance of maintaining work ethics, dress code, and personal hygiene.
6. Explain the importance of workplace sanitization and demonstrate the correct way of sanitizing and washing hands.

11.2.1 Organizational Practices for Hygiene, Food Handling and Cleaning

Poor organizational practices concerning hygiene, food handling, and cleaning often lead to worksite miscoordination and timeline delays since the team keeps falling sick. Some of the poor practices include:

- **Hygiene -** Poor hygiene practices include not maintaining clean workspaces, lack of personal cleanliness among workers, improper disposal of waste, and failure to clean and sanitize tools or surfaces.
- **Food Handling -** If food is handled improperly on-site, it may lead to contamination, especially in areas where food is served or eaten. Practices like using unclean utensils, storing food incorrectly, or not following food safety protocols contribute to this issue.
- **Cleaning -** Inadequate or improper cleaning of the site can result in the accumulation of dust, debris, and hazardous materials, compromising the work environment and the health of employees.

Do the following to maintain hygiene and cleanliness:

Maintain personal hygiene

Store food in airtight containers

Keep the work area clean

Fig. 11.2.1: Hygiene and cleanliness best practices

Examine the worksite for poor organizational practices, such as:

- **Disorganization:** Tools, materials, or cleaning supplies may be scattered around, leading to inefficiency and increased risk of accidents.
- **Improper Waste Disposal:** Hazardous materials like chemicals, paints, or construction waste might not be disposed of properly, posing environmental and health risks.
- **Inconsistent Cleaning Practices:** Work surfaces, tools, and equipment may not be sanitized regularly, increasing the risk of contamination or illness.

Also, you should use PPE while working. This helps in:

- **Prevention of Injury:** PPE protects workers from physical harm, such as cuts, burns, or exposure to toxic materials.
- **Manufacturer's Guidelines:** PPE must be used as per the manufacturer's instructions to ensure maximum protection. Improper use can lead to reduced effectiveness and may even increase the risk of injury.

Health and safety measures associated with project designs are:

- **Ventilation:** Proper air circulation to minimize exposure to harmful fumes or dust.
- **Ergonomics:** Ensure workspaces are designed to reduce physical strain and prevent injuries.
- **Chemical Safety:** If the project involves chemicals, clear labelling and proper storage of these substances are essential.
- **Electrical Safety:** Proper installation and maintenance of electrical systems to avoid shocks or fire hazards.

To examine the project design for proper implementation of health and safety measures, do the following:

- Check if the design accommodates safety features such as easy exits, fire extinguishers, and safety signage.
- Ensure that proper safety barriers or warning systems are in place, especially when dealing with hazardous materials or heavy machinery.

The significance of maintaining work ethics, dress code, and personal hygiene are:

- **Work Ethics:** Professionals in the interior design industry must adhere to ethical standards, such as honesty, integrity, and respect for clients and colleagues.
- **Dress Code:** Wearing appropriate clothing, such as durable and protective clothing, ensures safety and presents a professional image.
- **Personal Hygiene:** Regular handwashing, clean uniforms, and maintaining a clean personal appearance prevent the spread of germs and promote a healthier work environment.

Importance of workplace sanitization:



Fig. 11.2.2: Workplace best practices

Demonstrating the Correct Way of Sanitizing and Washing Hands

These following steps show the correct way of sanitizing and washing hands:



Fig. 11.2.3: Washing hands process

UNIT 11.3: Emergency Preparedness and Response

Unit Objectives

At the end of this unit, the participants will be able to:

1. Explain the operational guidelines for the usage of emergency tools and equipment.
2. Explain the steps involved in responding to an emergency (fire, short circuit, accidents, earthquake, etc.) process in line with organizational protocols.
3. Explain the first aid procedures in case of emergency and demonstrate CPR.
4. Identify all the concerned control measures while working at the worksite.
5. Identify suitable methods to communicate necessary control measures to concerned team members.

11.3.1 Operational Guidelines for Emergency Tools/Equipment

Effective emergency preparedness is crucial to minimize harm during unexpected incidents at the worksite. Knowing how to properly use emergency tools and equipment can save lives, reduce injuries, and help contain damage. Some key emergency tools and rules are:

Fire Extinguishers - Used to put out small fires before they spread.

First Aid Kits - Contains supplies to treat minor injuries, burns, cuts, and sprains on-site.

Fire Alarms and Smoke Detectors - Used to alert workers of a fire and provide the early warning necessary for evacuation.

Emergency Exit Routes - Clearly marked exits/escape routes for quick evacuation in case of fire, gas leaks, or other emergencies.

Eye Wash Stations - Used for immediate flushing of the eyes if exposed to harmful chemicals or substances.

Spill Kits- Used to contain and clean up hazardous material spills, including chemicals or solvents

Fig. 11.3.1: Emergency tools

Some operational guidelines involving these tools are as follows

- Regular Inspection - Ensure all emergency equipment is inspected routinely for functionality. For example, fire extinguishers should be checked for the correct pressure, and first aid kits should be replenished with necessary supplies. Ensure tools and equipment are easily accessible and clearly marked.
- Proper Placement - Emergency equipment must be placed in accessible areas and near high-risk zones (e.g., fire extinguishers near heat-producing equipment).
- Fire exits and evacuation routes should be unobstructed and clearly marked.
- Training - Workers and managers should be trained to recognize when and how to use emergency equipment. This includes identifying fire risks, chemical hazards, or electrical malfunctions.
- Emergency drills (e.g., fire drills, first aid training) should be conducted regularly to ensure readiness in an actual emergency.
- Emergency Procedures - Outline clear emergency procedures for various types of incidents, such as fire, electrical failure, chemical spills, or accidents.
- Establish roles and responsibilities for workers during an emergency. This can include directing evacuations, administering first aid, or calling emergency services.
- Documentation - Maintain records of all emergency equipment inspections, training sessions, and drills. This ensures compliance and readiness in case of an incident.

An Interior designer should be able to demonstrate the correct use of various emergency tools and equipment, ensuring that workers are prepared to handle emergencies effectively. A practical demonstration of the tools can be done in the following ways:

Fire Extinguisher Use – For fire extinguishers, use the PASS Method. The PASS method involves pulling the pin from the handle, aiming the nozzle at the base of the fire, squeezing the handle to release the extinguishing agent and sweeping from side to side at the base of the fire until it is completely extinguished

It is important to make sure to use the right type of fire extinguisher for the type of fire (e.g., Class A for general fires, Class B for flammable liquids). If the fire is too large to handle, evacuate immediately and call the fire department.

Using First Aid Kits - For minor cuts or scrapes, clean the wound with antiseptic wipes, apply pressure to stop bleeding, and cover with a sterile bandage. For burns, use a cool compress to reduce heat. For serious burns, cover the area with a clean, non-stick cloth and seek medical attention immediately. For sprains, apply ice to reduce swelling, and use bandages or splints to immobilize the area. Always prioritize getting professional medical attention for serious injuries and know the contents of the first aid kit and how to use each item effectively.

Fire Alarm and Evacuation Protocol - In order to trigger a fire alarm, locate the nearest fire alarm, pull the lever, and ensure it triggers the system. Inform all workers immediately to evacuate the building. For Evacuation, it is also important to identify and make note of the nearest exit routes. It is important to note that elevators should not be used during a fire emergency.

Eye Wash Station - In the case of exposure to chemicals or harmful substances in the eyes, quickly locate the nearest eye wash station. Activate the station by pulling the lever and flushing both eyes with water for at least 15 minutes. Do not rub the eyes; instead, flush them continuously with clean, cool water. Seek medical attention if irritation persists.

Spill Kit Use - Identify the material that has spilled and determine the appropriate response (whether it's a chemical, oil, or water-based spill). Use absorbent pads, socks, or materials from the spill kit to contain the spill and prevent it from spreading. Once contained, clean the spill using the appropriate

neutralizer or absorbent materials provided in the kit. Always wear appropriate PPE (gloves, masks) when cleaning spills to avoid contact with hazardous materials.

General Emergency Response Steps

The step undertaken in case of emergency are:

Step 1: Stay Calm and Assess the Situation		
Keep your calm and maintain composure	Assess the situation	Identify the nature of the emergency

Step 2: Alert Others and Initiate Evacuation (if required)			
Alert workers	Evacuate the site (if necessary)	Lead workers to assembly points	Count heads

Step 3: Call for Help		
Call emergency services	For fire, dial 101 (fire department in India)	For medical, dial 108 (ambulance services in India)

Step 4: Action (If Safe and Trained to Do So)		
For fire, use the PASS method. (only if the fire is controllable)	For electrical accident, cut off the power supply	For minor injuries, administer first aid

Fig. 11.3.2: Steps to be taken in case of an emergency

In an emergency, the Interior designer must ensure that all personnel follow the prescribed evacuation procedures to safely exit the site, reduce risks, and protect lives. The evacuation process should be well-structured and in line with organizational protocols to ensure a quick, organized, and efficient response during a crisis.

The evacuation steps to follow in an emergency are but not limited to are:



Fig. 11.3.3: Steps for evacuation

Some organisation protocols for emergency evacuation include

- **Conducting regular drills -** Conduct regular fire drills, evacuation drills, and first-aid training to ensure that all workers know what to do in case of an emergency. Practice different types of emergencies to ensure workers are prepared for various scenarios.

- **Assigning clear roles and responsibilities -** Assign specific evacuation duties to certain personnel (e.g., a floor warden, first aid officer, or safety coordinator).
- **Keeping and maintaining records -** Document the evacuation process and any incidents that occur during the evacuation.
- **Training and Awareness -** Provide comprehensive training for all workers about evacuation procedures, safety protocols, and emergency contact information.
- **Visible signage -** Display clear, visible signage indicating exit routes, assembly points, and emergency exits around the worksite.

11.3.2 Designing a Contingency Plan for Emergencies

A Contingency Plan is a critical aspect of ensuring that an Interior designer and the entire team are prepared to respond to various emergencies, such as fires, electrical short circuits, accidents, and natural disasters like earthquakes.

The contingency plan should provide clear, actionable steps for handling emergencies effectively to minimize damage, ensure safety, and maintain project continuity. The steps should include:

1. **Identify Potential Emergencies**

   The first step in designing a contingency plan is to identify all possible emergencies that could occur on the worksite.

In the interior design industry, these emergencies could include:



Fig. 11.3.4: Steps for evacuation

By anticipating each type of emergency, you can create specific responses for each.

2. **Establish Response Procedures for Each Emergency**

   A. **Fire Emergency Procedures -** Ensure proper handling and storage of flammable materials (paints, solvents, and fuels). Regularly check electrical systems to avoid fire hazards.

Immediate Actions:

- **Alert:** Activate the fire alarm system.
- **Evacuate:** Direct personnel to nearest exits and assembly points.
- **Contain:** If it's safe, use a fire extinguisher (following the PASS method – Pull, Aim, Squeeze, Sweep).

B. **Electrical Short Circuit Procedures –** Make sure there is regular inspection of wiring, circuits, and electrical equipment.

Immediate Actions:

- **Shut off power:** If possible, turn off the main electrical supply to stop the short circuit from causing further damage.
- **Evacuate:** If necessary, evacuate the site to prevent electrocution risks.
- **Use proper equipment:** Only trained personnel should handle electrical issues.

C. **Accident/Workplace Injury Procedures -** Ensure all personnel wear PPE (Personal Protective Equipment) and follow safe work practices.

Immediate Actions:

- **Assess the injury:** Evaluate whether it is minor (cuts, scrapes) or serious (broken bones, severe bleeding).
- **Administer first aid:** Use the first aid kit to treat minor injuries. For severe injuries, call for emergency medical help immediately (Dial 108 in India).
- **Evacuate:** Move the injured person to a safe location if necessary and facilitate medical assistance.

D. **Earthquake Emergency Procedures -** Ensure the structural integrity of buildings and the use of earthquake-resistant materials where possible.

Immediate Actions:

- **Drop, Cover, and Hold On:** In the event of an earthquake, instruct all personnel to drop to the ground, cover their heads, and hold onto something stable.
- **Evacuate:** Once shaking stops, evacuate personnel to a safe area away from structures or potential falling debris.

E. **Chemical Spill Procedures -** Use proper containers for hazardous materials and ensure adequate ventilation in areas where chemicals are used.

Immediate Actions:

- **Contain the spill:** Use spill kits or absorbent materials to prevent the chemical from spreading.
- **Alert workers:** Evacuate the immediate area and inform them about the hazard.
- **Use PPE:** Ensure all responders wear gloves, goggles, and masks while handling the spill.
- **Call for help:** Notify emergency services if the spill involves dangerous chemicals or is too large to manage.

F. **Gas Leak Procedures -** Regularly check the storage and handling of gases like LPG or other flammable gases used at the site.

Immediate Actions:

- **Turn off the gas supply:** If safe, turn off the gas supply to stop further leakage.

- **Evacuate:** Evacuate the site immediately, ensuring everyone is at a safe distance.
- **Ventilate:** Open doors and windows to allow gas to disperse (without causing sparks or fires).

G. Flood Emergency Procedures - Ensure proper drainage systems and elevated structures to minimize flood risks.

Immediate Actions:

- **Evacuate personnel:** Move to higher ground immediately if flooding is imminent or already occurring.
- **Shut off utilities:** Turn off electricity, water, and gas supply to avoid additional hazards.

3. General Contingency Plan Components

Each emergency should have a clear and organized procedure with the following components:

Designated Emergency Response Team (ERT)	Assign roles to key personnel, such as floor wardens, safety officers, and first-aid responders.
Floor Wardens	Responsible for guiding workers to exits and ensuring no one is left behind.
First Aid Responders	Trained personnel who will take initial medical action for injuries.
Emergency Contacts	Maintain a list of emergency numbers (e.g., fire department, ambulance, local hospitals, utility providers, etc.).
Communication Plan	Develop a communication plan for notifying all employees, including using mobile apps, radios, and public address systems during an emergency.
Evacuation Routes and Assembly Points	Clearly mark evacuation routes and assembly points on-site. Ensure all workers are familiar with these locations.
Training and Drills	Conduct regular emergency drills to ensure everyone is familiar with the emergency response protocols.
Resource Availability	Ensure essential safety equipment, such as fire extinguishers, first aid kits, spill kits, PPE, and emergency signage, are available and easily accessible.

Fig. 11.3.5: Steps for evacuation

4. Regular Review and Update of the Contingency Plan

A contingency plan is not static and should be regularly reviewed and updated based on:

- **Site-specific risks:** Changes in the worksite layout or new hazards.
- **Lessons learned from past incidents:** Review past emergencies to improve response procedures.
- **Regulatory changes:** Update the plan to comply with the latest health, safety, and environmental regulations.

11.3.3 First Aid Procedures in Case of Emergency

In the event of an emergency on an interior design worksite, it is essential to know how to provide immediate first aid to injured individuals until professional medical help arrives. The Interior designer plays a vital role in ensuring that workers receive timely assistance, especially in high-risk environments like construction or interior design sites where accidents are common. The step-by-step guide to first aid procedures for common injuries such as cuts, burns, fractures, and heart attacks includes:

First Aid for Cuts and Laceration – The most common causes for cuts and lacerations include tools (knives, glass, metal), falling objects, or machinery.

The steps for treating cuts are:

Apply direct pressure to the cut with a clean cloth or sterile gauze. If blood soaks through, do not remove the cloth; simply add more layers.

Once the bleeding has slowed or stopped, rinse the wound with clean water to remove any dirt or debris. Avoid using soap directly in the wound. Use antiseptic to disinfect the area if available.

Apply a sterile bandage or gauze over the wound to keep it clean and protect against infection.

If the cut is deep, continues to bleed heavily, or involves more severe injuries (e.g., tendon or muscle damage), seek medical attention immediately

Fig. 11.3.6: Treating cuts

First Aid for Burns – It can occur because of contact with hot surfaces, fire, steam, chemicals, or electrical sources. The steps for treating burns are:

1. **Assess the severity –** First-degree burns are red, painful skin with no blisters (like mild sunburn). Second-degree burns: are red, blistered skin with swelling. Third-degree burns are white, charred skin that may be numb due to nerve damage.
2. **Cool the burn –** Immediately cool the burn with running cold water for 10-20 minutes to reduce pain and prevent further tissue damage. For chemical burns: Rinse with plenty of clean water. Remove contaminated clothing if safe.
3. **Cover the burn –** After cooling, cover the burn with a sterile, non-stick bandage or clean cloth to prevent infection. Avoid using ice directly on the burn, as it may cause further damage.
4. **Pain relief –** For mild burns, over-the-counter pain relief (e.g., ibuprofen or acetaminophen) can be used. Never apply butter or greasy substances to the burn, as it can trap heat and worsen the injury.
5. **Seek professional medical attention –** For severe burns (second or third degree), or if the burn covers a large area of the body or face, call for emergency help immediately.

First Aid for Fractures – Fractures happen due to reasons like falling from heights, impact from heavy equipment, or blunt force trauma. The steps for treating fractures are:

- **Immobilize the injured area -** Do not try to move the person unless absolutely necessary. If you need to move them, immobilize the fracture by securing it with a splint made from available materials (like a wooden stick or metal rod). Stop bleeding (if necessary) - If the fracture involves an open wound (compound fracture), apply direct pressure to stop bleeding using a clean cloth or sterile gauze. Apply dressings around the wound and avoid touching bone or exposing the injury further.
- Apply ice - Apply ice wrapped in a cloth (not directly on the skin) to reduce swelling and pain. Seek professional medical help - Call for emergency assistance if the fracture is severe or the bone is visible. Even if the fracture appears minor, it is important to seek medical care to confirm the diagnosis and to prevent complications.

First Aid for Heart Attacks – Heart attacks happen due to stress, physical strain, high blood pressure, pre-existing heart conditions, or blocked arteries. The steps for treating a heart attack are:

Recognize the signs of a heart attack - This includes chest pain (heaviness, tightness, or pressure), shortness of breath, sweating, nausea, dizziness, or discomfort in the arms, neck, back, or stomach.

Call emergency services immediately - Dial 108 or the emergency medical service number in your region. The faster the person gets medical attention, the better the outcome.

Perform CPR (if necessary) - Push hard and fast at the centre of the chest (about 2 inches deep and 100-120 compressions per minute).

Fig. 11.3.7: Treating a heart attack

General First Aid Tips for All Injuries

- **Stay calm: I**n all emergency situations, staying calm allows you to think clearly and act quickly.
- **Call for help:** Always call emergency services as soon as possible, especially in severe cases or when you're unsure how to handle the injury.
- **Use Personal Protective Equipment (PPE):** If available, wear gloves to avoid direct contact with blood, bodily fluids, or chemicals.
- **Avoid self-treatment for severe injuries:** In cases of severe burns, fractures, heart attacks, or head injuries, always seek professional medical help immediately.
- **Clean and disinfect:** If you're dealing with cuts, abrasions, or open wounds, always clean and disinfect the area before applying bandages to prevent infection.

Demonstrating First Aid and CPR

Hands-on demonstrations of first aid and CPR (Cardiopulmonary Resuscitation) techniques are essential parts of safety training for workers in high-risk environments like construction or interior design worksites. These demonstrations ensure that team members are prepared to act quickly and effectively in case of emergencies, potentially saving lives.

1. Preparation for the Demonstration

Before starting the demonstration, ensure the following:

- Ensure you have a first aid kit, CPR manikin (if available), and other demonstration materials.
- The person leading the demonstration should be trained and certified in first aid and CPR by a recognized body.
- Conduct the training in a safe, quiet area where the demonstration can be clearly seen by all participants.
- Encourage active participation from the workers, asking them to practice as you demonstrate, to ensure they retain the skills.

Fig. 11.3.8: Arranging for demonstration of CPR technique

2. Demonstrating First Aid Techniques

First Aid for Cuts

- Use a clean cloth, bandage, or sterile gauze to apply direct pressure on the wound. If bleeding does not stop, add more layers of gauze, do not remove the original dressing. Demonstrate how to clean the wound gently with clean water (avoid using strong disinfectants directly in the wound). Demonstrate how to apply antiseptic.
- Show how to apply a sterile bandage or gauze, wrapping it tightly to hold it in place without cutting off circulation. Emphasize when to seek medical attention, especially for deep, large, or infected cuts.

First Aid for Burns

- Demonstrate how to immediately run cool water over the burn for 10–20 minutes (for first-degree and second-degree burns). For chemical burns, rinse with plenty of clean water and remove contaminated clothing. Show how to cover the burn with a sterile non-stick bandage or clean cloth.
- Explain the importance of seeking professional help for third-degree burns and how to avoid applying ointments or butter to the burn.

First Aid for Fractures

Demonstrate how to immobilize the fractured limb using available materials (e.g., wood, metal rods) to prevent movement and further damage. Use bandages to secure the splint or immobilization device. If the fracture involves an open wound, apply direct pressure to stop the bleeding. Show how to properly arrange for the injured person to be transported to a hospital or clinic for professional treatment.

Basic CPR Steps for Adults

1. Assess the Situation
    - Check responsiveness - Tap the person and shout to see if they respond. If they do not respond, call for emergency help immediately (Dial 108 or your local emergency services number).
    - Position the Person - Lay the person flat on their back on a firm surface (e.g., the floor).
    - Check for Breathing - Look, listen, and feel for breathing by placing your ear near the person's mouth and nose.
    - If the person is not breathing or is only gasping, begin CPR.
2. Chest Compressions – Kneel beside the person and place your heel of one hand on the centre of the person's chest (between the nipples).
    - Place your other hand on top of the first hand, interlocking your fingers.
    - Press down hard and fast (at least 2 inches deep) at a rate of 100-120 compressions per minute. Let the chest rise fully after each compression but do not lift your hands off the chest.
3. Rescue Breaths (if trained) – After 30 chest compressions, open the person's airway by tilting their head back and lifting the chin.

    Pinch their nose and give 2 rescue breaths, ensuring the chest rises with each breath. If you are unable to perform rescue breaths, continue chest compressions.
4. Continue CPR – Continue with 30 chest compressions and 2 rescue breaths until help arrives or the person starts breathing.

If you are not trained in rescue breaths, perform hands-only CPR. Start by positioning your hands on the centre of the chest as explained above. Provide chest compressions at a rate of 100-120 compressions per minute until emergency responders arrive.

Demonstrating AED (Automated External Defibrillator)

An AED is a portable device that can analyse the heart's rhythm and deliver an electric shock to restore normal rhythm. If available on the worksite, demonstrate how to use the AED. Turn on the AED by opening the device and follow the spoken or visual instructions. Place the pads on the person's chest (one on the upper right side and one on the lower left side). Let the AED analyse the heart's rhythm. Ensure no one is touching the person when the AED analyses and follow the AED's instructions to either administer a shock or continue CPR.

Hands-On Practice for Participants

- Have participants practice first aid and CPR techniques in small groups. Give them the opportunity to perform CPR on manikins and practice bandaging, splinting, and using a first aid kit.
- Walk around and give individual feedback to ensure the techniques are being applied correctly.
- Create realistic scenarios (e.g., a person has collapsed, or a burn occurred) and have participants respond as if they are handling a real emergency.

Key Safety Reminders During Demonstrations

- Emphasize the importance of staying calm in an emergency. Panic can hinder the effectiveness of first aid and CPR.
- Always use gloves (when available) to avoid contact with bodily fluids. If no gloves are available, use a cloth to provide assistance.

- Ensure the participants understand that they should continue CPR and other first aid procedures until professional help arrives or the person begins to show signs of life.
- Remind participants that performing first aid and CPR is a skill that needs to be practiced regularly to maintain proficiency. Encourage periodic training sessions to keep the skills fresh.

Control Measures While Working at the Worksite

Control measures are essential practices implemented on the worksite to reduce or eliminate hazards, ensuring a safe and healthy environment for workers. As an Interior designer in interior design, it's important to identify and implement the appropriate control measures based on potential risks, which can range from physical hazards (such as machinery) to health-related issues (like exposure to harmful substances). The primary types of control measures and their application are:

Eliminate Hazards

The best control measure is to remove the hazard altogether. For example, if a particular tool or material presents a safety risk, remove it from the worksite or replace it with a safer option. Example: Replacing toxic paints with non-toxic alternatives to reduce health risks.

Substitution

If elimination is not possible, substitute the hazardous material or process with a safer one. This reduces the exposure to harmful chemicals, tools, or equipment. Example: Substituting hazardous solvent-based paints with water-based paints to minimize fumes and skin irritation.

Fig. 11.3.9: Types of control measures

Engineering Controls

These controls involve modifying the worksite or equipment to minimize risk. They are:



Ventilation Systems

Machine Guards and Barriers

Ergonomic Tools and Equipment

Noise Reduction

Fig. 11.3.10: Engineering controls

Administrative Controls

These measures involve changing the way work is done to minimize risk:

- Workplace Safety Training
- Work Schedule Adjustments
- Clear Signage
- Safety Procedures and Protocols

Communicating Control Measures to Team Members

Effective communication is key to ensuring that control measures are successfully implemented and adhered to by all workers on site. Here are some ways to communicate control measures effectively:

Pre-Project Meetings and Briefings

- Safety Induction Training - Before starting a project, ensure that all workers participate in a safety induction where you explain the specific hazards and the control measures in place.
- Daily Safety Briefings - Conduct daily briefings or "toolbox talks" at the start of each workday.
- Clear Communication Channels - Use radio communication or walkie-talkies to facilitate easy communication between team members on large work sites.

Visual Communication

- Signage and Posters - Display clear signage around the worksite to highlight hazards, such as areas where PPE is mandatory (e.g., helmets, gloves, and safety boots).
- Color-Coding - Use color-coded tags or markings to distinguish between safe zones, hazardous areas, or restricted spaces.

Written Communication

- Safety Documentation - Provide workers with written copies of the site safety plan, which outlines control measures, protocols, and emergency procedures.
- Job Safety Analysis (JSA) or Risk Assessment Forms - Distribute JSA or risk assessment forms that clearly state the potential risks and corresponding control measures for each specific task.

Training and Drills

- Practical Demonstrations - Regularly hold practical demonstrations of control measures, such as the proper use of PPE, operating machinery safely, or executing emergency procedures.

Feedback and Reporting Systems

- Safety Feedback - Encourage workers to provide feedback on safety practices.
- Reporting Hazards - Implement an easy-to-use system for workers to report hazards.

Fig. 11.3.11: Communicating control measures

UNIT 11.4: Safety Signs

Unit Objectives

At the end of this unit, the participants will be able to:

1. Explain the types of hand signals and signage and their application.
2. Identity and interpret the given pictorial representations of safety signs and hand signals.

11.4.1 Types of Hand Signals and Safety Signage

Effective communication is vital in a worksite, particularly in noisy environments like construction or interior design sites. Hand signals and safety signage are essential tools for conveying critical information, ensuring safety, and preventing accidents. As an Interior designer, you must ensure that these are clearly communicated to your team and effectively implemented.

Types of Hand Signals

Hand signals are a common method of communication in environments where verbal communication is difficult due to noise or distance. The key hand signals include:

Signal	How to perform	Application
Stop Signal	Hold up one arm with the palm facing forward, fingers extended.	Used to indicate the need to stop work immediately, and is used when operating machinery or directing traffic.
Move Forward	Extend one arm straight forward, and move it in a forward direction.	Indicates that machinery or workers should move forward or proceed with their task.
Move Backwards	Extend one arm straight, palm facing down, and move it in a backward motion.	Signals the need for machinery or personnel to move backward, often used when manoeuvring large equipment or trucks.
Lift or Raise	Raise one arm with the fist closed and point upwards.	Indicates that a load should be lifted or raised, and is used when guiding cranes/ hoisting materials.
Lower	Extend one arm downward with the palm facing down and move the hand downward	Signals that a load should be lowered, such as during crane operations/lifting heavy objects.
Warning	Rotate both arms in a circular motion.	Used to indicate a potential hazard or need to be cautious. This is useful for alerting workers about an impending danger.
All Clear	Place one hand at eye level, then wave it horizontally.	Signifies that it is safe to proceed with work or that an area is clear of hazards.
Emergency Stop	Make a fist and raise it above the head.	Used to stop all work or machinery immediately, typically in an emergency situation.

Table 11.4.1:

11.4.2 Identifying and Interpreting Pictorial Safety Signs and Hand Signals

Pictorial safety signs use universally recognized symbols to communicate important safety messages. These signs transcend language barriers, ensuring clarity regardless of the workers' primary language. Some common pictorial signs are:

Prohibition signs

No smoking sign



Restricted area sign

No pedestrian allowed beyong this point sign

Fall hazard sign

A caution sign

Fig. 11.4.1: Examples of pictorial signs

Fire and emergency signs

Fire escape sign

Go right for exit sign

Fire alarm sign

Fig. 11.4.2: Examples of emergency signs

Summary

- Health and safety protocols include using Personal Protective Equipment (PPE), organizing the worksite to prevent accidents, and ensuring equipment safety by maintaining and inspecting tools and machinery regularly.
- Hazardous materials, like paints and adhesives, should be handled with proper ventilation and following safety data sheets (SDS), while ensuring hygiene practices such as waste disposal and keeping work areas clean to prevent health issues.
- A well-designed health and safety plan is essential, including risk assessments, safe work practices, assigned responsibilities, safety training, emergency procedures, and regular monitoring.
- Identifying and mitigating risks, such as exposure to harmful particles, heavy lifting injuries, and electrical hazards, is critical during both
- Poor organizational practices, such as improper waste disposal, unclean workspaces, and lack of sanitation, lead to inefficiency and health risks, affecting the overall safety and productivity of the worksite.
- The importance of PPE in preventing injuries is emphasized, and proper usage based on the manufacturer's instructions is critical to ensure worker protection.
- Proper hygiene practices include maintaining personal cleanliness, organizing workspaces, and controlling dust and debris. Waste management practices also ensure the safe disposal and recycling of materials.
- Health and safety measures in project design should address proper ventilation, ergonomic workspace design, and chemical safety, while also ensuring that the design meets all safety standards for electrical and fire hazards.
- Emergency preparedness includes understanding the operational guidelines for emergency tools and equipment, ensuring they are inspected and accessible for use during a crisis.
- Key emergency response steps, such as evacuation, first aid, and CPR, are outlined, and workers must be trained in these procedures to ensure timely and effective action during incidents.
- A contingency plan should cover various emergencies such as fires, electrical failures, accidents, and natural disasters, with clear response procedures and roles assigned to workers.
- Regular drills, clear signage, and adequate communication are essential to ensure readiness for emergencies and to maintain safety during an incident.
- Safety signs and hand signals are critical for communication, especially in noisy or hazardous environments. They help convey important messages quickly and effectively.
- Hand signals such as "stop," "move forward," and "emergency stop" are used to communicate instructions during operations involving machinery or large equipment.
- Pictorial safety signs are universally recognized symbols used to communicate safety instructions, such as fire exits or hazardous materials, which transcend language barriers.
- Proper interpretation and use of safety signs and hand signals are essential for maintaining a safe work environment and preventing accidents.

Exercise

Multiple Choice Questions (MCQs)

1. What is a primary purpose of health and safety protocols at the worksite?
   a. To ensure aesthetics of the workspace
   b. To prevent accidents, injuries, and health issues
   c. To promote personal hygiene only
   d. To increase worksite productivity only

2. Which of the following is a key responsibility when using Personal Protective Equipment (PPE)?
   a. Ignore the manufacturer's instructions
   b. Use it as per the manufacturer's guidelines
   c. Use it only when convenient
   d. Share PPE with other workers

3. What is essential for mitigating health and safety hazards on the worksite?
   a. Regular cleaning of the worksite
   b. Ignoring safety protocols to speed up work
   c. Using tools without maintenance
   d. Leaving hazardous materials unmarked

4. Which emergency procedure should workers be trained in?
   a. Evacuating only when convenient
   b. Using emergency equipment and performing CPR
   c. Waiting for professional help only
   d. Ignoring emergency drills

5. What is the function of safety signage and hand signals at a worksite?
   a. To distract workers
   b. To communicate safety instructions and prevent accidents
   c. To make the workspace look attractive
   d. To provide entertainment during breaks

Activity: Demonstration

1. Execute a fire drill and how to use a fire extinguisher
2. Demonstrate how to give CPR.

Notes

Scan the QR codes or click on the link to watch the related videos

https://www.youtube.com/watch?v=hTS6gtaTHcI

Cardiopulmonary Resuscitation (CPR)

https://www.youtube.com/watch?v=w4jHpHoYZhk

How to Use a Fire Extinguisher

https://www.youtube.com/watch?v=SqZ5np_lCr0

Essential Safety Signs

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

12. Material Conservation and Resources Optimization

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

Unit 12.1: Resource Optimization
Unit 12.2: Sources of Energy and Consumption

FFS/N8207

Key Learning Outcomes

At the end of this module, the participant will be able to:

1. Explain the importance of efficient utilization and conservation of material.
2. Identify various techniques of effective utilization of resources.
3. Explain the various elements involved in electricity and fuel consumption data for analyzing the process.
4. Explain the difference between renewable and non-renewable sources of energy.
5. Explain the process of collecting and analyzing the energy utilization data.

UNIT 12.1: Resource Optimization

Unit Objectives

At the end of this unit, the participants will be able to:

1. Explain the importance of efficient utilization and conservation of material.
2. Identify various techniques of effective utilization of resources.

12.1.1 Conservation of Material

Conservation of material refers to the careful and efficient use of resources to reduce waste, minimize environmental impact, and ensure that materials are used in a sustainable way. It involves using only the amount of material needed for a given purpose, reducing unnecessary consumption, and recycling or reusing materials to extend their lifespan.

The key aspects of conservation of material are as follows:

Efficient Use of Resources - This means utilizing materials in the most efficient way possible, ensuring that no excess material is used beyond what is necessary for a project or task. For example, in construction, using precise measurements and avoiding over-ordering materials can reduce waste.

Waste Reduction - One of the main goals of material conservation is to minimize waste. This can involve using leftover materials in creative ways or finding methods to reduce the amount of waste generated in the first place. For example, using scrap wood from a project to create smaller items like furniture or storage solutions.

Recycling and Reusing - Recycled materials are used to create new products, reducing the need for virgin materials. Items that can be reused, such as containers, packaging, or old machinery parts, are conserved rather than disposed of.

Sustainable Sourcing - Materials should be sourced sustainably, meaning they come from renewable sources or from suppliers that follow eco-friendly practices. This reduces the depletion of natural resources and minimizes environmental harm. For example: Using sustainably sourced wood or recycled metals.

Product Design and Durability - Designing products that use fewer materials and have longer lifespans is another important aspect of conservation For example, designing appliances or furniture to be long-lasting and repairable rather than disposable.

Circular Economy - This concept revolves around designing systems where materials are reused, refurbished, and recycled instead of being discarded. By maintaining the value of materials within the economy, less new raw material is needed. Companies that design products with the intention that the materials can be fully recovered and reused at the end of the product's life.

Fig. 12.1.1: key aspects of conservation of material

12.1.2 Efficient Utilization and Conservation of Materials

The efficient utilization and conservation of materials are critical for several reasons. This includes:

- **Environmental Impact:** Using materials efficiently reduces waste, which in turn helps to minimize pollution, habitat destruction, and other environmental issues caused by excessive resource extraction and manufacturing processes.
- **Cost Savings:** Efficient use of materials lowers production costs. When materials are wasted or inefficiently used, it increases the overall cost of manufacturing and resource procurement. Conservation also reduces the need for costly raw materials.
- **Sustainability:** Efficient utilization helps preserve resources for future generations. By conserving materials, we ensure that these resources remain available for long-term use and prevent depletion.
- **Energy Conservation:** The extraction, transportation, and processing of materials consume energy. Using materials more efficiently reduces the energy needed in these processes, contributing to overall energy conservation.
- **Circular Economy:** Efficient material use encourages recycling and reuse, contributing to a circular economy where materials are continuously reused, reducing the need for new resources.



Fig. 12.1.2: Efficient utilization and conservation of materials

12.1.3 Techniques of Effective Utilization of Resources

Effective resource utilization is a cornerstone of successful interior design project management. For an Interior designer, the ability to plan, allocate, and manage resources—such as time, materials, manpower, and finances—is essential to ensure that projects are completed within budget and on schedule, without compromising on quality.

Following are some of the techniques that enable optimal use of available resources, minimize wastage, and enhance overall efficiency on-site and off-site throughout the interior design execution process:

1. **Project Scheduling and Resource Allocation**
    - Develop detailed project timelines and assign resources (labour, materials, equipment) as per activity requirements. Use project management tools (e.g., MS Project, Trello) to ensure resources are used optimally without delays or overlaps.

2. **Material Management**
   - Source materials based on accurate estimation to avoid over-ordering or wastage. Ensure timely delivery and proper storage to maintain quality and reduce loss.
3. **Budget Monitoring**
   - Monitor resource expenditure against the allocated budget. Track costs for material, manpower, and vendor services to identify areas of overspending and take corrective action.
4. **Vendor Coordination**
   - Select reliable vendors with efficient delivery schedules and quality assurance, reducing rework and delays. Optimize the use of subcontractor services by scheduling their inputs strategically.
5. **Workforce Efficiency**
   - Assign tasks to skilled workers based on their strengths. Provide on-site supervision to avoid idle time, rework, or misuse of resources.
6. **Space Utilization on Site**
   - Organize site layout effectively to store materials safely and allow smooth workflow. Avoid clutter and ensure space is used for functional purposes like work zones, storage, and movement.
7. **Energy and Equipment Use**
   - Encourage the use of energy-efficient lighting and tools. Turn off machines when not in use. Maintain equipment to extend its life and avoid frequent replacements.
8. **Reuse and Recycling**
   - Reuse leftover materials such as plywood, tiles, or fixtures in other parts of the project. Promote recycling of packaging, scrap, and other non-reusable waste.
9. **Process Optimization**
   - Streamline workflow by sequencing tasks smartly – e.g., scheduling electrical layout before false ceiling installation. Avoid duplication and ensure smooth handovers between teams.
10. **Continuous Monitoring and Improvement**
    - Conduct regular site audits to check resource usage. Use insights to refine future planning, reduce resource wastage, and improve productivity.

UNIT 12.2: Sources of Energy and Consumption

Unit Objectives

At the end of this unit, the participants will be able to:

1. Explain the various elements involved in electricity and fuel consumption data for analyzing the process.
2. Explain the difference between renewable and non-renewable sources of energy.
3. Explain the process of collecting and analyzing the energy utilization data.

12.2.1 Elements Involved in Electricity and Fuel Consumption Data

Analyzing electricity and fuel consumption data is essential for effective resource management, operational cost control, and sustainable practices. The key elements typically involved in this analysis include:

- **Type of Energy**
  - Identifying the energy sources being used such as:
    - Electricity (measured in kilowatt-hours – kWh)
    - Fuels like diesel, petrol, LPG, CNG, etc. (measured in liters or kilograms)
- **Source of Consumption**
  - Categorizing where and how the energy is being used:
    - Equipment and machinery
    - Lighting and HVAC systems
    - Generators or vehicles
    - Office appliances or temporary site setups
- **Quantity Consumed**
  - Tracking the total amount of electricity or fuel used during a defined period (daily, weekly, monthly). This is the basis for cost and efficiency analysis.
- **Operating Hours**
  - Measuring how long energy-consuming devices or systems run. Longer operating hours typically mean higher energy consumption.
- **Load Factor and Equipment Efficiency**
  - Understanding how much of an equipment's full capacity is being used and how efficiently it operates. Inefficient or overused systems lead to higher energy use.
- **Usage Patterns**
  - Observing trends in consumption over time (e.g., peak hours, seasonal spikes, idle periods) to identify opportunities for optimization.

- **Cost Data**
  - Recording the cost per unit of electricity or fuel used. Helps correlate energy use with total expenditure and evaluate cost-saving measures.
- **Energy Consumption per Output Unit**
  - Calculating how much energy is used per unit of work or production. This helps assess productivity and energy efficiency (e.g., kWh per square meter of interior design work completed).
- **Carbon Emission Factor**
  - Estimating the environmental impact of energy usage by applying emission factors, especially for fuel types. Useful for sustainability reporting and compliance.
- **Monitoring and Control Systems**
  - Use of meters, digital sensors, fuel logs, and software to track consumption in real-time and ensure data accuracy for decision-making.

12.2.2 Renewable and Non – Renewable Energy

Renewable Energy is the energy derived from resources that are naturally replenished on a human timescale. Renewable sources are sustainable and can be replenished naturally over time, making them more environmentally friendly and long-lasting., Some examples of renewable energy are solar energy, wind energy, hydropower, geothermal energy, and biomass. These examples are depicted in the following images:

Solar energy

Wind energy

Hydropower

Geothermal energy (Energy from earth's heat)

Biomass

Fig. 12.1.3: Example of Renewable Energy

Non-Renewable Energy is the energy derived from sources that cannot be replenished on a human timescale and are finite. Non-renewable resources are finite and their extraction and use can lead to environmental damage, including air pollution and greenhouse gas emissions. Some examples of non-renewable energy are oil, coal, natural gas, and nuclear energy (which relies on uranium). These examples are depicted in the following images:

Natural gas in a pipe

Coal

oil storage

Nuclear energy in a reactor

Fig. 12.1.4: Example of Non-Renewable Energy

Practical Activity: Energy Audit of a Project Site

Objective:

- Illustrate the process of collecting and analyzing the energy utilization data

Materials Required:

- Observation checklist or energy audit template
- Sample data sheet or logbook (can be pre-filled or blank for actual recording)
- Calculator or spreadsheet software (Excel/Google Sheets)
- Measuring tools if available (e.g., portable energy meter, fuel log)

Instructions:

Step 1: Identify Energy Use Points

- Visit a simulated or actual interior design site (or use a case study).

- List all major energy-consuming elements (e.g., lighting, drilling machines, sanding machines, HVAC, generator).

Step 2: Record Consumption Data

- Note down the equipment name, power rating (in watts or kilowatts), hours of daily operation.
- If fuel-powered equipment is used, record fuel type and estimated daily consumption in liters.

Step 3: Calculate Total Energy Usage

- For electricity:

$$\text{Energy (kWh)} = \text{Power (kW)} \times \text{Hours of Use}$$

- For fuel:

  Sum up total liters used per day or week.

Step 4: Analyze the Data

- Identify which equipment or activity uses the most energy.
- Look for patterns—e.g., excessive usage, idle time, or equipment left on unnecessarily.

Step 5: Recommend Improvements

- Suggest at least three energy-saving strategies, such as switching to LED lights, using timers, scheduling heavy work during daylight hours, or maintaining tools regularly.

Summary

- Conservation of material is about using resources efficiently to reduce waste and environmental impact.
- Efficient use of materials helps lower production costs and prevents resource depletion.
- Conservation practices encourage sustainability by reducing the need for new resources and promoting a circular economy.
- Effective resource utilization is crucial for interior design project management, including resource allocation, scheduling, and minimizing wastage.
- Key techniques include project scheduling, material management, and continuous monitoring to optimize resource usage.
- Electricity and fuel consumption data analysis is essential for managing costs and improving efficiency.
- Renewable energy sources like solar, wind, and geothermal are replenishable and environmentally friendly.
- Non-renewable energy sources like oil and coal are finite and can cause environmental harm.
- Effective energy audits involve identifying energy consumption points, recording data, and recommending energy-saving measures.
- Practical steps for energy conservation include using energy-efficient appliances, improving insulation, and adopting renewable energy solutions.

Exercise

A. Multiple Choice Questions (MCQs)

1. What is the main goal of resource optimization in material management?
   a. To increase waste
   b. To reduce environmental impact and conserve resources
   c. To use more raw materials
   d. To extend production time

2. Which of the following is NOT a renewable energy source?
   a. Solar energy
   b. Wind energy
   c. Coal
   d. Geothermal energy

3. What is a key technique for optimizing resource usage in interior design projects?
   a. Ignoring project timelines
   b. Budget monitoring and tracking
   c. Using more materials than needed
   d. Hiring unskilled labor

4. Which of the following is an example of non-renewable energy?
   a. Biomass
   b. Hydropower
   c. Oil
   d. Wind energy

5. What does an energy audit help with?
   a. Reducing material wastage
   b. Tracking energy consumption and identifying savings
   c. Increasing energy consumption
   d. Ignoring energy consumption patterns

B. Short Answer Questions

1. What is material conservation, and why is it important?
2. Explain the difference between renewable and non-renewable energy.
3. List two techniques for effective utilization of resources in interior design projects.
4. What are the benefits of using energy-efficient appliances?
5. Describe the process of conducting an energy audit on a project site.

Notes

Scan the QR codes or click on the link to watch the related videos

https://www.youtube.com/watch?v=YaZ9tKBCJx8

Materials and Resources

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

13. Employability Skills

DGT/VSQ/N0102

Employability Skills is available at the following location

https://www.skillindiadigital.gov.in/content/list

Employability Skills

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

14. Technicalities in a Residence and Kitchen Project

Unit 14.1: Business Development and Client Requirement Analysis for Residence and Kitchen Project

Unit 14.2: Project Execution, Estimation, and Task Demarcation for Residence and Kitchen Project

FFS/N0216

Key Learning Outcomes

At the end of this module, the participant will be able to:

1. Analyse and prepare a business development plan based on specified marketing and development strategies for residence and kitchen project.
2. Explain the critical parameters for analysing first-hand info from clients for residence and kitchen project.
3. Analyse and interpret client requirements in terms of layouts, blueprints, product types, etc. for residence and kitchen project.
4. Identify the scope of work for the project by analysing the client requirement and specifications.
5. Identify the process of preparing a project estimate and related documents in consultation with internal teams.
6. Explain the guidelines for performing client visits, inspection, and reporting of assigned residence and kitchen project.
7. Identify and demark tasks and responsibilities based on technicalities of the assigned residence and kitchen project.
8. Identify design docket and specifications based on client requirements and project execution parameters for residence and kitchen project.

UNIT 14.1: Business Development and Client Requirement Analysis for Residence and Kitchen Project

Unit Objectives

At the end of this unit, the participants will be able to:

1. Analyse and prepare a business development plan based on specified marketing and development strategies for residence and kitchen project.
2. Explain the critical parameters for analysing first-hand info from clients for residence and kitchen project.
3. Analyse and interpret client requirements in terms of layouts, blueprints, product types, etc. for residence and kitchen project.
4. Identify the scope of work for the project by analysing the client requirement and specifications.
5. Identify the process of preparing a project estimate and related documents in consultation with internal teams.

Case Study: Residence and Kitchen Interior Design Project

Project Overview

A couple contacts a mid-size interior design firm to renovate their 2BHK apartment. Their goals are to:

- Transform a closed kitchen into an open, functional space.
- Redesign the living area with compact storage solutions.
- Use sustainable and easy-to-maintain materials.
- Ensure the project is delivered within a fixed budget and timeline.

The firm assigns the Assistant Project Manager (APM) to coordinate business development, client engagement, and project execution.

Step by Step Solution to the Client Requirement

Business Development Plan

- **Project Objective:** Offer sustainable, modular kitchen and living solutions.
- **Market Research:** Identified demand for eco-friendly, open-plan kitchens among young professionals.
- **Development Strategy:** Included offerings like quartz countertops, customizable storage, and IoT-enabled lighting.
- **Marketing Tactics:** Campaigns on social media, local SEO, tie-ups with real estate developers.
- **Sales Strategy:** Pre-sales consultation + visual design mock-ups; defined support roles and AMC (annual maintenance contract).

- **Financial Planning:** Budgeted for social media ads, 3D rendering tools, and vendor commissions.
- **Risk Mitigation:** Accounted for supplier delays, client indecision, and regulatory approvals.

Client Requirement Analysis

- **Initial Meeting:** Conducted in-person consultation to gather first-hand data—client's pain points included poor kitchen ventilation and lack of light in the living area.
- **Site Visit:** the Draftsman or Assistant Interior Designer takes measurements of light flow, load-bearing walls, and existing plumbing/electrical outlets.
- **Requirement Capture Template Used:** Preferences included L-shaped open kitchen, bright tones, and matte finishes.
- **Technical Review:** Floor plan marked for appliance placement, storage zones, and natural light usage.

Interpreting Requirements and Preparing Design Brief

- **Layouts Prepared:** 2D and 3D views showing kitchen openness, breakfast counter, compact wardrobe solutions.
- **Style Preference:** Minimalist Scandinavian design with light textures.
- **Product Preferences:** Mid-range appliances, LED lighting, VOC-free paints.
- **Design Brief Documented:** Includes zoning, furniture details, and technical compliance requirements.



KITCHEN







Fig. 14.1.1:

Sample Design Brief: Residence Kitchen Interior Project

Project Name: Modular Kitchen Renovation

Client Type: Residential – Urban Family

Project Type: Renovation of Existing Kitchen

Location: Not specified (generic, globally adaptable)

Designer/Team: Interior Design Studio (with in-house execution team)

Date: [Insert Date]

1. **Project Objective**

   To renovate the existing kitchen into a modern, modular L-shaped kitchen that offers:

   - Efficient storage
   - Seamless appliance integration
   - Optimized workflow (based on kitchen triangle: hob-sink-refrigerator)
   - Aesthetically pleasing finishes with easy maintenance

2. **Functional Zoning**

   Based on the final layout plan and above/below counter drawings:

Zone	Components
Cooking Area	Hob with chimney, utensil drawers
Preparation Area	Countertop space near sink and hob
Storage – Dry	Pantry cabinet, bottle pull-out, napkin pull-out, overhead units
Storage – Cold	Refrigerator position retained
Cleaning Area	Sink zone with under-sink storage
Appliance Station	Built-in oven, microwave, toaster, mixer shelf

3. Layout & Dimensions

- Configuration: L-shaped layout with an extended storage wall
- Below Counter Zones: Labeled A–H with specific uses (vegetable pull-out, bottle pull-out, electrical gadget cabinet, etc.)
- Above Counter Zones: Overhead storage aligned for electrical gadgets and pantry

4. Material & Finish Specifications

Element	Specification
Cabinet Finish	Matte laminate in beige
Countertop	Black granite/quartz finish
Backsplash	marble-look tile
Hardware	SS handles, soft-close drawers
Flooring	Grey matte-finish vitrified tiles

5. Furniture & Appliance Integration

- **Overhead Units:** For pantry, chimney cover, and microwave shelf
- **Tall Unit:** Integrated oven and microwave cabinet
- **Modular Accessories:** Vegetable basket, napkin pull-out, bottle pull-out
- **Breakfast Counter:** (Optional, subject to space) – not shown in this layout

6. Technical Compliance & Safety

Electricals: All points aligned with modular plan; concealed wiring with IS-compliant switches

- **Ventilation:** Provided via external duct for chimney and operable window
- **Lighting:** Under-cabinet LED lighting; overhead task lighting
- **Plumbing:** RO system connection point, drainage, and concealed pipeline

7. Client Preferences

- **Color Scheme:** Warm neutral tones – beige and black
- **Style:** Minimalist, modern, clutter-free

- **Sustainability:** Low-VOC finishes, energy-efficient LED fittings
- **Storage Priority:** Dedicated sections for dry goods, napkins, and appliances

8. **Approval Status**
   - **Design:** Final 2D & 3D views approved
   - Material Samples: Signed off by the client
   - Timeline: 5 weeks from project start date
   - Budget: Within estimated range; contingency of 5%

4. **Scope of Work (SOW)**

Included:

- Dismantling old kitchen wall.
- Shifting sink and gas pipeline.
- Fabrication and installation of cabinets, shelves, and counters.
- False ceiling and lighting for the living room.
- Painting and flooring upgrade.

Format: Listed as a bullet-point checklist with timelines, dependencies, and assigned team leads.

5. **Project Estimation**

- **BOQ Prepared:** Modular units, countertop, hardware, paint, flooring, appliances, labor.
- **Vendor Coordination:** Got quotes from 3 suppliers. Evaluated price vs. lead time.
- **Estimate Format:** Quantity x Unit Price model (refer Fig. 13.1.6 for detail).

Sample Estimate – Residence & Kitchen Interior Design Project

Client Name: Mr. & Mrs. XYZ

Project Name: 2BHK Residence & Kitchen Renovation

Date: 21 May 2025

Prepared by: Assistant Project Manager

Approval Status: Approved

Category	Description	Quantity	Unit Rate (₹)	Total (₹)
Kitchen Cabinets	Base + Overhead Units (laminate finish)	12 ft	₹9,000	₹1,08,000
Countertop	Quartz – 18 mm	10 ft	₹7,500	₹75,000
Backsplash Tiles	Ceramic – 2x2 ft	20 sq.ft	₹400	₹8,000
Modular Hardware	Hinges, channels, handles	1 set	₹18,000	₹18,000

Lighting	Under-cabinet LED strip (warm white)	2 units	₹2,000	₹4,000
Plumbing Fixtures	SS Sink with mixer tap	1 set	₹12,000	₹12,000
Living Area Paint	VOC-free emulsion	300 sq.ft	₹55	₹16,500
False Ceiling	Gypsum with cove lighting	150 sq.ft	₹350	₹52,500
Electrical Work	Rewiring, sockets, switchboards	1 lot	₹30,000	₹30,000
Labor Charges	Civil, plumbing, electrical	1 project	₹85,000	₹85,000
Design Fee	2D/3D design, coordination	1 project	₹65,000	₹65,000
Contingency (5%)				₹23,900
GST (18%)				₹94,662

Table 14.1.1:

Total Estimate (including GST and contingency): ₹6,92,562

Notes:

- The estimate is inclusive of labor, design, and taxes.
- Valid for 15 days. Subject to material availability and client approvals.
- GST @18% calculated on subtotal before contingency.
- **Included Documents:** Final quote, contract agreement, payment schedule, and 3D visuals.
- **Internal Review:** Estimation vetted by accounts, procurement, and legal teams.

6. Client Visits, Inspection, and Reporting

- **Before Visit:** Reviewed layouts, BOQ, and team readiness. Checklist and PPE carried.
- **During Visit:** APM led walkthrough—client checked kitchen fittings and cabinet finishes.
- **Inspection Report Prepared:** Included % completion, photos, issues, and next steps (as per Table 13.2.2).

Sample - Site Visit & Inspection Report

Project Name: 2BHK Residence & Kitchen Renovation

Project Location: _____

Date of Visit: 21 May 2025

Purpose of Visit: Progress Check and Client Feedback

Work Completed

- Modular kitchen carcass installed (70%)
- Electrical rewiring for kitchen and living area completed (100%)
- False ceiling framework in living area (50%)
- Plumbing points finalized and roughed-in (90%)

Issues Found

- Misalignment noted in one kitchen overhead cabinet.
- Delay in backsplash tile delivery.
- Client requested change in sink position.

Client Feedback

- Happy with lighting layout and modular finish.
- Requested update on wardrobe material sample.
- Requested written confirmation of revised sink position.

Recommendations / Next Steps

- Realign the overhead cabinet by 23 May.
- Confirm sink position change with design team.
- Expedite tile delivery and update ETA.

Assigned Action Items

Action Item	Person Responsible	Deadline
Fix cabinet alignment	Site Engineer	23 May 2025
Update sink layout in design plan	Interior Designer	22 May 2025
Follow up with tile vendor	Procurement Lead	21 May 2025

Table 14.1.2:

- **Feedback:** One adjustment request for shelf depth. Recorded and updated in tracker.

7. Task Demarcation & Delegation

Task	Assigned To	Reason
Kitchen layout and 3D renders	Interior Designer	Space planning expertise
Modular cabinet fitting	Vendor A	Factory-finished unit supply
Electrical and lighting work	MEP Technician	Compliance and safety
Countertop and backsplash	Civil Contractor	Skilled stone and tile work
Final Finishing & QA	Site Engineer	Quality assurance and site safety

Table 14.1.3:

Live Tracker Maintained: Google Sheet with daily status and remarks (as per Table 13.2.5).

Sample – Tracker

Task	Description	Assigned To	Deadline	Status	Remarks
Kitchen layout finalization	Get client approval on revised kitchen layout	Interior Designer	22 May 2025	In Progress	Client requested minor changes in sink area
Wardrobe carcass fitting	Install base structure of wardrobe in Bedroom 1	Modular Team	24 May 2025	Scheduled	
Electrical rough-in	Initial wiring for living and kitchen areas	Electrician	23 May 2025	Not Started	Awaiting final plan confirmation
False ceiling installation	Install ceiling frame and gypsum boards in living	False Ceiling Contractor	26 May 2025	Scheduled	
Appliance wiring	Connect wiring for hob, chimney, refrigerator	MEP Technician	27 May 2025	Not Started	
Paint primer coat	Apply base coat in kitchen and living	Painter	28 May 2025	Not Started	

Table 14.1.4:

8. **Design Docket Review and Approval**
   - **Design Docket Included:**
     - Finalized floor plan and 3D renders.
     - Product specs: Laminates, appliances, hardware.
     - Material board images.
     - Site measurement sketch and utility plan.
   - **Client Review Meeting:** Held at site with printouts and tablet visuals
   - **Final Sign-Off:** Recorded in approval sheet and sent via email.

14.1.1 Business Development Plan

A business development plan needs to be prepared based on specified marketing and development strategies for residence and kitchen project during an interior designing activity. The process of creating a business development plan are:

1. Define Project Overview and Objectives – Describe the scope of the residence and kitchen project, e.g., is it a new construction, renovation, modular kitchen solution or a smart home integration. Also, clarify what you want to achieve with this design like business development or new design launch etc.
2. Perform Market Research and Analysis – Find out about trends in residential housing and kitchen solutions. And then identify the target market like the demographics, preferences, budget etc. Then, you need to develop a benchmark pricing, service quality and marketing tactics of key competitors. Along with this activity, do a SWOT (Strengths, Weaknesses, Opportunities, Threats) analysis.
3. Define Development Strategies – Find answer to questions like what are you offering? (e.g., eco-friendly kitchens, customizable layouts, smart appliances) and the decide the use of design software, 3D visualization, smart home integration.
4. Develop a Marketing Strategy – Write your unique selling propositions (USPs) for your residence and kitchen project. Next, decide on channels such as social media like SEO, social media, Google Ads, website or conventional ones like brochures, newspaper ads, trade shows. You may want to collaborate with interior designers, real estate agents, or appliance brands.
5. Create a Sales Strategy – Typical process includes:

Fig. 14.1.2: Sales Strategy

   Next, define roles for the project such as BDMs, Sales Executives, Support etc. Also, decide the after-sales service, warranties, maintenance plans that would like to provide.
6. Estimate Financial Projections – Plan a budget and define an estimate for marketing, construction, salaries, materials, etc. based on market size and expected conversion rates.
7. Draw an Implementation Timeline – Set milestone dates for launch, campaign rollouts, sales targets.
8. Plan for Monitoring and Evaluation – Devise ways to compute conversion rates, sales numbers, customer feedback.

9. Identify Risks – Such as supply chain issues, regulation changes, market demand shifts and accordingly plan for backup suppliers, flexible payment plans, insurance.



Fig. 14.1.3: Activity

When working on a residence project or a kitchen assignment, there are some parameters that help in analyzing first-hand information from clients—their expectation and requirements. These include:



Fig. 14.1.4: Parameters Help in Analysing First-Hand Information

14.1.2 Analysing Client Requirements

Analyzing and interpreting client requirements for residence and kitchen projects is vital for delivering functional, aesthetic and personalized spaces. An example of an approach to effectively analyze and interpret client needs based on layouts, blueprints, product preferences, etc. is as follows:

1. **Initial Client Consultation:**
   a. Understand the Vision –Ask open-ended questions: "What's your lifestyle like?" "What are your daily routines in the kitchen/home?"
   b. Discuss Goals & Priorities – Are they focused on functionality, style, budget, sustainability, smart tech, etc.?

2. **Site Visit & Assessment:**
    a. Visual Inspection – Take measurements, photos, and note existing structures.
    b. Evaluate Space Constraints – Check plumbing, electrical outlets, wall load-bearing capacity, ventilation, etc.
    c. Note Natural Light & Traffic Flow – This helps guide layout optimization.

3. **Review and Interpret Layouts & Blueprints:**
    a. Understand the Floor Plan – Identify room dimensions, orientation, access points.
    b. Highlight Key Zones – Work triangle in kitchens (sink-stove-fridge), seating areas, walkways.
    c. Interpret Client Annotations – Mark-ups, notes, sketches—ask for clarification if needed.

4. **Identify Product Requirements:**
    a. Categorize Product Types – Cabinets, countertops, flooring, appliances, lighting, fixtures.
    b. Style Preferences – Modern, rustic, industrial, Scandinavian, etc.
    c. Material Preferences – Wood vs. laminate, quartz vs. granite, matte vs. gloss.
    d. Budget and Brand Considerations –Check if they prefer premium brands or budget-friendly options.

5. **Functionality & Storage Needs:**
    a. Storage Requirements – Pantry, pull-out units, appliance garages, drawer organizers.
    b. Usage Patterns – Frequent entertaining guests? Family size?
    c. Accessibility & Ergonomics – Design for ease of use (especially for elderly, kids, or people with disabilities).

6. **Translate Requirements into Design Concepts:**
    a. Create Mood Boards – Combine visuals of layouts, materials, finishes, and appliances.
    b. Design Drafts – Present 2D/3D mockups with alternative options.
    c. Review & Revise – Discuss drafts with the client and gather feedback for adjustments.

7. **Technical & Regulatory Considerations:**
    a. Check Local Building Codes – Compliance with electrical, plumbing, ventilation, and fire safety standards.
    b. Sustainability Goals – Eco-friendly materials, energy-efficient appliances, waste management.

8. **Document Final Requirements:**
    a. Create a Design Brief – Summarizes all client requirements, specifications, product types, budget limits, and design directions.
    b. Approval Sign-Off – Ensure mutual agreement before proceeding to execution.

Some templates for recording client requirements are:

Client Details

Field	Information
Client Name	
Contact Number	
Email	
Project Location	
Date of Consultation	

Table 14.1.5:

Project Scope

Area	Description
Project Type	☐ New Construction ☐ Renovation ☐ Modular Installation
Scope of Work	☐ Full Residence ☐ Kitchen Only ☐ Living + Kitchen ☐ Others: _____
Preferred Completion Date	

Table 14.1.6:

Product & Material Preferences

Category	Preferred Type/Brand	Remarks
Kitchen Cabinets		
Countertops		
Appliances		
Faucets & Sinks		
Storage Solutions		
Flooring		
Lighting Fixtures		

Table 14.1.7:

Technical Considerations

Field	Notes
Electrical Points / Load Requirements	
Plumbing Requirements	
Ventilation & Chimney	
Smart Features Desired (e.g., IoT, voice control)	
Compliance/Regulations	

Table 14.1.8:

Attachments Checklist

- ☐ Site Photos
- ☐ Existing Layout or Blueprint
- ☐ Inspirational/Mood board Images
- ☐ Measurement Sketches
- ☐ Product References

Client Confirmation

I confirm that the preceding information is as per my preferences and requirements.

Client Signature: _____

Date: _____

Based on the client requirements and the information gathered a scope of work document needs to be prepared. A professional Scope of Work (SOW) document for a kitchen and residence interior design project, custom-made to reflect client requirements and specifications typically looks like shown in the following figure:

Kitchen & Residence Interior Design Project

Project Title: Interior Design of Residence and Kitchen
Client Name: _____
Project Location: _____
Project Duration: _____ weeks / months
Start Date: _____
Expected Completion: _____

Objective:
To design and execute a comprehensive interior solution for the client's residence and kitchen, integrating functional layout planning, aesthetic enhancements, customized furniture, and modern design elements as per client specifications.

Project Scope

A. Kitchen Area

- **Layout Planning**
  - Optimize work triangle (sink–stove–refrigerator)
  - Design for ventilation and natural light
- **Cabinetry & Storage**
  - Modular cabinets with soft-close hinges
  - Overhead and under-counter storage units
  - Pantry pull-outs, spice racks, and corner units
- **Countertops & Backsplash**
  - Material: (e.g., Quartz / Granite / Marble – as per client preference)
  - Backsplash tiling and finish details
- **Appliance Integration**
  - Built-in hob, oven, chimney, dishwasher, etc.
  - Electrical point mapping and installation
- **Lighting**
  - Task lighting, ambient lighting, under-cabinet lights
- **Flooring**
  - Slip-resistant, easy-to-clean material (as per client choice)
- **Plumbing & Fixtures**
  - Sink installation, water purifiers, taps/faucets

B. Residence Interiors

1. Living Room

- Ceiling design with ambient lighting
- TV unit and feature wall
- Furniture selection and layout
- Curtains/blinds, rugs, accessories

2. Bedrooms (Master + Others)

- Wardrobe design (sliding/hinged)
- Bed with headboard, side tables, study unit (if required)
- False ceiling and lighting
- Furnishing and décor

3. Dining Area

- Table and seating layout
- Crockery/storage unit
- Pendant or chandelier lighting

4. Bathrooms

- Vanity unit, mirror, accessories
- Storage shelves/cabinets
- Tiling and waterproofing
- Sanitary fittings (as per specifications)

5. Balcony/Utility Areas

- Basic seating/decking
- Planters or vertical garden setup
- Storage (if needed)

3. Deliverables

- Concept design presentation (mood boards, 3D renders, layout plans)
- Finalized 2D & 3D designs with client approval
- BOQ (Bill of Quantities)
- Procurement assistance or turnkey execution
- Supervision & progress updates

4. Client-Specified Materials & Preferences

Category	Client Preference
Design Style	Modern / Minimalist / Traditional / etc.
Color Palette	Neutral / Warm / Bold / etc.
Materials	(e.g., Marine ply, laminate, PU, acrylic, etc.)
Brands	(E.g., Hettich, Hafele, Faber, Kajaria, etc.)

5. Exclusions (if any)

- Civil modifications or structural changes
- External façade work
- Major electrical rewiring
- Appliances purchase (if not included in scope)

6. Timeline & Milestones

Milestone	Estimated Date
Design Finalization	_____
Material Selection	_____
Site Execution Start	_____
Mid-Execution Review	_____
Final Handover	_____

7. Client Approval

I, the client, confirm the above scope of work and authorize the project to proceed as per agreed specifications.

Client Signature: _____
Designer/Agency Signature: _____
Date: _____

Fig. 14.1.5: SOW for Kitchen Project

14.1.3 Project Estimation

To prepare a project estimate and related documents in consultation with internal teams, perform the following steps:

1. **Review Client Requirements**
   a. Analyze the final client-approved scope of work, layouts, and product preferences.
   b. Review inputs from the Design team (layouts, material selections, renders), Civil and MEP (Mechanical, Electrical, Plumbing) teams and any custom or modular furniture specifications team.
2. **Site Survey Verification**
   a. Cross-check site measurements taken earlier.
   b. Validate space dimensions, utility points, and any potential site-related challenges.
   c. Confirm with execution/civil teams if any structural changes or reinforcements are needed.

3. **Create a Detailed BOQ (Bill of Quantities) – Break the estimate into clear work packages, such as:**
   - Kitchen – Modular cabinet fabrication (materials, sizes, finishes), hardware and accessories, countertop and backsplash, appliances (optional), plumbing fixtures, electrical work, labor charges
   - Residence – Furniture (beds, wardrobes, sofas, study units, etc.), false ceiling & lighting, painting & wall finishes, flooring or overlays, soft furnishings (curtains, rugs, etc.), decorative items (optional)

4. **Consult with Procurement & Vendor Teams**
   - Get quotations for all materials and products from vendors/suppliers.
   - Confirm the lead time, brand availability, discounts and warranty and support terms

5. **Coordinate with Execution & Project Teams**



Fig. 14.1.6: Coordination with Team

6. **Apply Markups and Overheads – Add margins for:**
   - Design fees (if applicable)
   - Project management
   - Contingency (typically 5–10%)
   - Taxes (GST or local taxes)

7. **Prepare Final Estimate Document – Structure the estimate for clarity:**

Category	Description	Quantity	Unit Rate	Total
Kitchen Cabinets	Base + Overhead Units	10 ft	₹_____	₹_____
Wardrobe	Master Bedroom, 3-Door	1 unit	₹_____	₹_____
...	...	...	...	...
Total				₹_____

Table 14.1.9: Sample Estimate Document

8. **Prepare Related Project Documents – Alongside the estimate, prepare:**
   a. Project Proposal/Quotation – A client-facing document summarizing the offering and final price.
   b. Work Contract/Agreement – With terms, payment milestones, warranty info, and delivery schedule.

c. Timeline – Project schedule with key dates for each phase.

d. Material & Finish Schedule – Final list of selected laminates, paints, tiles, fabrics, etc.

e. Design Drawings & 3D Views – Finalized and approved layouts, elevations, and renders.

9. Internal Review & Approval – Review final documents with:

- Accounts team (for pricing validation)
- Legal (if contracts involved)
- Project head (for scope and resource allocation)

After completing the estimation, present the estimate with a walk-through of costs and scope and clarify inclusions/exclusions. Then, obtain signed approval and advance payment to initiate work.

UNIT 14.2: Project Execution, Estimation, and Task Demarcation for Residence and Kitchen Project

Unit Objectives

At the end of this unit, the participants will be able to:

1. Explain the guidelines for performing client visits, inspection, and reporting of assigned residence and kitchen project.
2. Identify and demark tasks and responsibilities based on technicalities of the assigned residence and kitchen project.
3. Identify design docket and specifications based on client requirements and project execution parameters for residence and kitchen project.

14.2.1 Guidelines for Client Visits and Inspection

To successfully execute the project, you need to develop some guidelines for client visits, inspection and reporting. Some common guidelines are:

- **Before visiting the site:**
  - Review Project Documents such as layouts, BOQ, timelines, previous reports.
  - Coordinate with Team Leads and confirm updates with design, civil, and electrical teams.
  - Check Materials & Tools—carry checklist forms, camera, measurement tape, PPE (helmet/shoes), notepad or tablet.
- **During the Site Visit:**
  - Greet the client and restate the visit's purpose.
  - Brief them on current progress and upcoming work.
  - Clarify any recent change requests or concerns.

Visual Inspection Checklist

Area	Inspection Points
Kitchen	Cabinet alignment, hardware fitting, countertop finish, appliance cut-outs, backsplash installation, plumbing/electrical points
Living/Bedrooms	Furniture fitting, wall finish, ceiling quality, lighting points, flooring
Bathrooms	Sanitary fittings, tile alignment, waterproofing, vanity units
Paint/Finishes	Scratches, peeling, shade match, clean corners
Electrical	Switchboard positions, load checks, safety covers

Table 14.2.1: Visual Inspection Checklist

Use photos to document issues or progress.

- **Quality & Safety Compliance:**
  - Check work against approved design/specs (materials, finishes, layout)
  - Safety Standards, no loose wires, unstable ladders, or open plumbing
  - Cleanliness & Site Organization, debris removal, safe storage of tools/materials
- **Progress Tracking:**
  - Compare actual work completed vs. project timeline.
  - Track % completion of modular work, false ceiling, painting, electrical/plumbing
  - Note delays or bottlenecks.
- **Client Feedback & Sign-Off:**
  - Ask the client to review key installations or work done.
  - Record their satisfaction level and/or any concerns or additional requests. If needed, get written approval or comments.
- **Reporting Post-Visit –** Prepare a structured Site Visit & Inspection Report including:

Section	Content
Project Name & Location	
Date of Visit	
Purpose of Visit	(e.g., Progress Check, Final Inspection, Snag List)
Work Completed	Description + %
Issues Found	Description + Photos
Client Feedback	
Recommendations/Next Steps	
Assigned Action Items	Person Responsible + Deadline

Table 14.2.2: Sample Site Visit Report

14.2.2 Delegating Work and Tasks

When a project for a specific residence or kitchen project is assigned, you need to break down the tasks and responsibilities based on the project's technical aspects. You need to divide the project into stages, assigning roles to different team members (e.g., materials procurement, space planning, budget management).

To delegate tasks, note down the key technical areas, such as:



Fig. 14.2.1: Delegating Work and Tasks

Next, list the key roles and team members, for example, as follows:

Role	Responsibility
Project Manager	Overall coordination, timeline and cost control
Interior Designer	Layouts, 3D renders, product/material selection
Site Engineer	On-site supervision, quality checks
Civil Contractor	Wall modifications, tile laying, civil repairs
Modular Technician	Kitchen cabinets, wardrobes, fittings
MEP Expert	Electrical, plumbing, HVAC
Painter/Finisher	Painting, wallpaper, texture finishes
Procurement Lead	Vendor coordination, material sourcing
Client Liaison Officer	Regular updates, site visits, feedback loop

Table 14.2.3: Role and Responsibilities

You can also plan out area wise tasks, for example, in the kitchen area:

Task	Assigned To	Skill/Reason
Layout design and appliance positioning	Interior Designer	Space planning expertise
Modular cabinet manufacturing	Modular Technician	Factory and site handling
Countertop installation	Civil/Stone Contractor	Experience with cutting, polishing
Electrical wiring for appliances	MEP Technician	Safety-critical work
Plumbing for sink & dishwasher	Plumber	Technical water fitting skills
Final inspection	Site Engineer	QA/QC checks

Table 14.2.4: Kitchen Area Task Allocation

Create a live tracker (Excel/Google Sheet/Project Management Tool) with the following format:

Task	Description	Assigned To	Deadline	Status	Remarks
Kitchen layout finalization	Get client approval	Designer	Apr 2	In Progress	Awaiting samples
Wardrobe carcass fitting	Bedroom 1	Modular Team	Apr 5	Scheduled	
Electrical rough-in	Living + Kitchen	Electrician	Apr 4	Not Started	

Table 14.2.5: Tracker

After planning delegation, ensure each member knows:

- What they are doing
- When it's due
- Whom to coordinate with

Assign a Site Coordinator or Project Manager to monitor progress.

- Have regular check-ins (daily site reports or weekly reviews).
- Be available to:
  - Remove roadblocks
  - Reassign tasks if workload is unbalanced
  - Clarify scope creep or change requests

  Keep task delegation, revisions and decisions well-documented.

14.2.3 Review and Approval of Design Docket

A visualized process flow helps in review and approval of a design docket and specifications document for a residence and kitchen interior design project, based on client requirements and execution feasibility.

A flow typically looks as follows:



Fig. 14.2.2: Approval of a Design Docket for Kitchen Project

Collect Client Requirements and Specifications



Fig. 14.2.3: Client Requirement and Specifications

Prepare Preliminary Design Docket



Fig. 14.2.4: Preparation of Preliminary Design Docket

Internal Design Review



Fig. 14.2.5: Internal Design Review

Client Presentation and Review

Fig. 14.2.6: Client Presentation and Review

Final Design Approval and Sign-Off

Documentation Includes:

- Approved drawings (2D + 3D)
- Final finish/material list
- Hardware & brand list
- Specification sheet (per room/ module)
- Signature from client & project lead

Status: “Approved for Execution”

Fig. 14.2.7: Final Approval and Sign-Offs

Activity

Role-play

1. One participant is the client and the other is an interior designer.
2. The designer gathers information such as client needs, preferences and functional requirements.
3. Analyze and present the critical parameters such as layout preferences, style and material choices.

Summary

- A business development plan for residence and kitchen projects includes market research, defining the project scope, and setting financial projections while developing a targeted marketing and sales strategy.
- Analyzing client requirements involves conducting an initial consultation, evaluating the site, reviewing blueprints, and identifying product preferences such as material types, style, and budget constraints.
- Translating client requirements into design concepts involves creating mood boards, draft designs, and ensuring regulatory compliance, all documented for client sign-off.
- The preparation of a project estimate includes reviewing client requirements, coordinating with the design and technical teams, and creating a detailed Bill of Quantities (BOQ) for clear cost breakdowns.
- Client visits and inspections should include reviewing project documents, performing a visual inspection of the site, and tracking progress against the timeline, with client feedback documented for approval.
- Task delegation in the project involves breaking down responsibilities based on the project's technical aspects and assigning clear roles to team members for specific tasks such as design, procurement, and construction.
- Review and approval of the design docket require a structured process including internal design reviews, client presentations, and final approval before moving forward with execution.
- Monitoring project execution through task trackers ensures accountability, keeps the project on schedule, and allows for timely adjustments as needed.

Exercise

A. Multiple Choice Questions (MCQs)

1. What is the first step in creating a business development plan for a residence and kitchen project?
   a. Conducting market research
   b. Defining the project scope and objectives
   c. Preparing financial projections
   d. Developing a sales strategy

2. Which factor is most important when analyzing client requirements for a residence and kitchen project?
   a. Understanding the client's budget and preferred product types
   b. The site location and available suppliers
   c. The contractor's preferred design style
   d. The general market trends

3. What is the primary purpose of a Bill of Quantities (BOQ) in project estimation?
   a. To document design preferences
   b. To break down the estimate into work packages for clarity and transparency
   c. To provide the final project proposal
   d. To determine the project timeline

4. Which of the following roles is responsible for ensuring that the work is performed on-site according to the plan during a kitchen and residence project?
   a. Interior Designer
   b. Procurement Lead
   c. Site Engineer
   d. Client Liaison Officer

5. In the review and approval of a design docket, what is the first step?
   a. Preparing the preliminary design docket
   b. Internal design review
   c. Collecting client requirements and specifications
   d. Client presentation and review

6. Which of the following tools is most useful for documenting client preferences during the initial consultation?
   a. Mood board
   b. Verbal discussion only
   c. Client requirement capture template
   d. WhatsApp messages

7. Why is it important to perform a site visit before finalizing the layout?
   a. To confirm brand preferences
   b. To compare competitor pricing
   c. To assess space constraints and natural light
   d. To install base cabinets

8. What does the contingency percentage in a project estimate typically account for?
   a. Decoration and interior styling
   b. Delays or unexpected changes in cost
   c. Discounts from vendors
   d. Fixed profit margins

9. During a client inspection visit, what should the your carry for documentation and quality checks?
   a. Only a smartphone
   b. Camera, PPE kit, checklist forms, notepad
   c. Wallpaper catalog
   d. Tool bag and drill machine

10. What is the purpose of maintaining a live tracker during project execution?
    a. To record client testimonials
    b. To plan marketing campaigns
    c. To monitor task progress, deadlines, and responsibilities
    d. To store design images

Notes

Scan the QR codes or click on the link to watch the related videos

https://www.youtube.com/watch?v=yLpNZEwMlWs

Kitchen Design: Layout, Materials & Dimensions | Lighting, Countertops & Appliances | Color Combo

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

15. Technicalities in a Commercial Project

UNIT 15.1: Business Development and Client Requirement Analysis for Academic Institution Project

UNIT 15.2: Project Execution, Estimation and Task Demarcation for Commercial project

FFS/N0216

Key Learning Outcomes

At the end of this module, the participant will be able to:

1. Analyse and prepare a business development plan based on specified marketing and development strategies for commercial project.
2. Identify client requirements in terms of layouts, blueprints, product types, etc. for commercial project.
3. Identify the scope of work for the project by analyzing the client requirement and specifications.
4. Identify the process of preparing a project estimate and related documents in consultation with internal teams.
5. Explain the guidelines for performing client visits, inspection, and reporting of assigned commercial project.
6. Identify and demark tasks and responsibilities based on technicalities of the assigned commercial project.
7. Identify design docket and specifications based on client requirements and project execution parameters for commercial project.

UNIT 15.1: Business Development and Client Requirement Analysis for Academic Institution Project

Unit Objectives

At the end of this unit, the participants will be able to:

1. Analyse and prepare a business development plan based on specified marketing and development strategies for commercial project.
2. Identify client requirements in terms of layouts, blueprints, product types, etc. for commercial project.
3. Identify the scope of work for the project by analyzing the client requirement and specifications.

Case Study: Commercial and Hospital Interior Design Project

Background

A multidisciplinary interior design firm received a contract to design and execute the interiors of a new multi-Specialty hospital. The client required:

- A modern reception and waiting area
- OPD (Outpatient) rooms and diagnostic zones
- Administrative offices and a training room for staff
- ICU
- Strict compliance with healthcare safety standards and ergonomic commercial workspaces

1. Business Development Plan

The firm developed a strategy targeting the healthcare sector:

- **Project Objective:** Deliver a dual-zone design that meets patient comfort and commercial functionality.
- **Market Research:** Benchmarked clinic interiors, sustainable hospital flooring options, and corporate office zones.
- **USP Highlighted:** Use of antimicrobial materials, ergonomic office setups, digital patient flow zones, and modular furniture.
- **Marketing Channels:** Social media ads, doctor-network partnerships, SEO targeting "clinic + office interiors," collaborations with MEP and HVAC partners.
- **Financial Projections:** ROI model based on cost/sqft benchmarks and repeat client potential in the healthcare sector.

2. **Client Requirement Analysis**
   - **Initial Client Meeting: Identified key deliverables:**
     - Antibacterial vinyl flooring
     - High-durability furniture
     - Clearly demarcated OPD, diagnostics, waiting, and admin zones
   - **Layout & Drawings Required:**
     - 2D Zoning Plans
     - 3D renders of reception and OPD
   - **Product Preferences:**
     - **Hospital:** PVC wall guards, anti-fungal ceilings, epoxy in labs
     - **Commercial:** Ergonomic workstations, soundproof cabins



Fig. 15.1.1:



Fig.15.1.2: RCP



Fig.15.1.3: Fire Safety

- **Product Preferences:**
  - **Hospital:** PVC wall guards, anti-fungal ceilings, epoxy in labs
  - **Commercial:** Ergonomic workstations, soundproof cabins

3. Scope of Work (SOW) Preparation

Key components:

- **Flooring:** Vinyl (hospital) + carpet tiles (office)
- **Wall finish:** Washable paints and digital branding in reception
- **Modular furniture:** Consultation tables, nurse stations, acoustic panels
- **Lighting:** Functional + sensor-based
- **HVAC & MEP:** Zoning for clinic and admin

Milestones set:

- **Design Finalization:** 2 weeks
- **Material Finalization:** 3 days
- **Execution:** 6 weeks
- **Mid-stage Review:** 3 weeks

4. Project Estimation & BOQ

Internal Team Coordination:

Team	Input
Design	Final layout + material specs
MEP	Switchboard, plumbing, HVAC plans
Procurement	Vendor rates, brands, delivery
Execution	Labor + site readiness
Finance	Tax rates, contingency

Table 15.1.1:

Sample BOQ Summary:

Category	Description	Qty	Rate (₹)	Total (₹)
Vinyl Flooring	Hospital grade	2000 sft	120	₹2,40,000
Workstations	Modular (commercial)	50	15,000	₹7,50,000
False Ceiling	Gypsum & Grid combo	1500 sft	95	₹1,42,500
HVAC System	Ductable AC	10 tons	55,000	₹5,50,000
Light & Electricals	Fixtures + wiring	L.S.	-	₹2,00,000

Table 15.1.2:

5. Client Visit, Inspection & Reporting Guidelines

Visit Protocol:

- Walkthrough of reception, OPD, ICU zones
- Use visual inspection checklist:
  - Alignment of cabinets, handrails, safety signage
  - Lighting positioning and MEP fitments
- Document issues with photos
- Client signs off on status and requests

Inspection Report Includes:

- Completion % by zone
- Client feedback
- Next steps with deadlines

6. Task Demarcation

Team Structure:

Team	Input
Project Manager and Assistant Project manager	Master coordination, cost, and client review
Designer	Layouts, finish schedules, 3D visuals
Site Engineer	Daily monitoring, reporting, site safety
MEP Coordinator	HVAC, plumbing, electrical inspections
Procurement Lead	Material tracking, vendor approvals
QC Officer	Snag lists, spec checks
Client Liaison	Reports, feedback follow-up
Safety Officer	Fire safety, hygiene in critical zones

Table 15.1.3:

Tracker Tool Used: Google Sheets with RACI matrix + Gantt timeline

Example Task:

- HVAC duct install → Responsible: MEP → Accountable: PM → Informed: Client

Sample RACI Matrix

Task	Assigned To	Start Date	End Date	R	A	C	I	Status
HVAC duct install	MEP Lead	2025-06-01	2025-06-04	MEP Lead	Project Manager	Interior Designer	Client	Scheduled
Modular furniture delivery	Procurement Lead	2025-06-02	2025-06-06	Procurement Lead	Project Manager	Procurement Lead	Client	In Progress
Vinyl flooring - OPD	Flooring Contractor	2025-06-04	2025-06-07	Flooring Contractor	Project Manager	Site Engineer	Client	Not Started
3D Design Finalization	Interior Designer	2025-05-28	2025-05-30	Interior Designer	Project Manager	Client Liaison	Client	Completed
Fire Safety System Setup	Safety Officer	2025-06-05	2025-06-09	Safety Officer	Project Manager	MEP Coordinator	Client	Not Started

Table 15.1.4:

Sample Gantt Chart



Fig.15.1.4:

7. Review and Approval of Design Docket

Final Docket Included:

- 2D & 3D layouts
- Finish boards and material samples
- Fire safety & acoustic treatment plans
- Approval form signed by: Client, PM, Design Head

Watermarked with “Approved for Execution” and distributed to:

- Site teams
- Vendor partners
- MEP contractors

Kick-off meeting conducted to align everyone.

15.1.1 Developing a Business Development Plan

When creating a business development plan for commercial and hospital interior design projects, technical components are crucial in harmonizing strategy and execution. These features cover more than just design aesthetics; they also include compliance, functional planning, infrastructural preparation, and complicated system integration. These technical aspects include:

- Space Planning & Zoning Requirements – Technical Focus should be on functional flow, privacy zones, patient/visitor/staff movement, circulation paths.



Fig. 15.1.5: Space Planning and Zoning Requirements

- Building Codes & Compliance



Fig. 15.1.6: Building Code and Compliance

- HVAC and Air Quality Design – Consider ventilation rates, filtration level, temperature zoning, infection control (in hospitals)



Fig. 15.1.7: HVAC and Air Quality Design

- Electrical & Lighting Systems

Load calculations for high-demand areas (server rooms, OT equipment)

Emergency backup systems (UPS, inverters, gensets)

Task and ambient lighting based on lux levels

Smart automation (energy-saving controls, occupancy sensors)

Fig. 15.1.8: Electrical and Lighting Systems

- Data, Security & Technology Integration – Plan cabling paths, switchboards, and safety protocols in early design stage



Fig. 15.1.9: Data, Security and Technology Integration

- Acoustics and Soundproofing – Use acoustic panels, double-glazed partitions, noise-isolation flooring



Fig. 15.1.10: Acoustics and Soundproofing

- Materials, Finishes and Durability – Consider maintenance, hygiene, and traffic load while selecting materials



Fig. 15.1.11: Materials, Finishes and Durability

- Modular & Custom Furniture Design

Ergonomics for workstations (commercial)	Patient beds, nursing stations, storage trolleys (hospital)	Should be durable, easy to disinfect, and functionally designed

Fig. 15.1.12: Modular and Custom Furniture Design

- MEP Coordination (Mechanical, Electrical, Plumbing)

Tight coordination needed to avoid on-site clashes

Early-stage planning for concealed services

Important in hospitals with medical gas lines, drainage, sterile water systems

Fig. 15.1.13: MEP Coordination

15.1.2 Analysing Client Requirements

A structured overview of typical client requirements for commercial and hospital interior design projects, focusing on layouts, blueprints, product types, finishes and more is shown as follows:

Layout & Spatial Requirements



Fig. 15.1.14: Layout and Spatial Requirements

Blueprint & Drawing Expectations

- **2D Layouts:** With zoning, service points, furniture placement
- **3D Views:** Renders or walkthroughs for visual validation
- **MEP Drawings:** Electrical, plumbing, HVAC marked clearly
- **Reflected Ceiling Plans (RCP):** For lighting, false ceiling, sensors
- **Fire & Safety Plans:** Fire exits, extinguisher points, smoke detectors
- **Furniture Details:** Custom or modular drawings with dimensions
- **Material Mapping:** On wall elevations, flooring types, false ceiling

Product Types & Materials

Commercial	**Workstations:** Modular desks, height-adjustable tables
	Partitions: Glass, gypsum, acoustic panels
	Seating: Ergonomic chairs, lounge seating, bar stools
	Storage: Mobile pedestals, file cabinets, server racks
	Lighting: Task lighting, ambient lights, suspended fixtures
	Flooring: Carpet tiles, vinyl, wooden laminate
	Tech Integration: Smart boards, video conferencing, LAN ports
Hospital	**Patient Beds & Medical Furniture:** Motorized beds, overbed tables
	Reception & Waiting Furniture: Durable and sanitized seating
	Storage Units: Medication cabinets, records storage, waste bins
	Flooring: Anti-bacterial vinyl, epoxy, non-slip tiles
	Wall Protection: PVC wall guards, bumpers
	Lighting: Anti-glare LEDs, surgical lights (in OTs)
	Special Fixtures: Medical gas units, nurse call systems, sterile sinks
	Acoustic Panels: In wards, ICU, operation zones
	Sanitary Fittings: Sensor-based taps, foot-operated doors

Fig. 15.1.15: Product Types and Material

15.1.3 Preparing Scope of Work

The scope of work includes the following details:

Scope of Services



Fig. 15.1.16: Scope of Services

Execution Phase

- Civil modifications (if applicable)
- Partitioning: Glass, drywall, modular
- False ceiling installation
- Electrical wiring & fixtures
- Plumbing fittings
- HVAC ducting and AC installation
- Modular furniture and storage
- Workstations, beds, counters, cabins
- Lighting & automation systems
- Flooring (vinyl, carpet, epoxy, etc.)
- Painting, wallpaper, wall treatments
- Branding graphics & signage
- Safety systems: Fire, CCTV, access control
- Deep cleaning & site handover

Fig. 15.1.17: Execution Phase

Materials & Product Categories

Category	Commercial	Hospital
Furniture	Modular, ergonomic	Anti-bacterial, medical-grade
Flooring	Carpet, laminate, vinyl	Vinyl, epoxy, non-slip tiles
Wall Finish	Paint, panels, branding	Washable paint, PVC wall guards
Ceiling	Grid, gypsum, baffle	Grid, anti-fungal tiles
Lighting	LED, sensor-based	Functional + medical-grade lighting
Fixtures	Electrical & plumbing	Hands-free, safe fixtures

Table 15.1.5:

Milestone	Timeline
Design Finalization	_____
Material Selection	_____
Site Execution Start	_____
Mid-Stage Review	_____
Final Completion	_____
Handover	_____

Table 15.1.6:

UNIT 15.2: Project Execution, Estimation and Task Demarcation for Commercial project

Unit Objectives

At the end of this unit, the participants will be able to:

1. Identify the process of preparing a project estimate and related documents in consultation with internal teams.
2. Explain the guidelines for performing client visits, inspection, and reporting of assigned commercial project.
3. Identify and demark tasks and responsibilities based on technicalities of the assigned commercial project.
4. Identify design docket and specifications based on client requirements and project execution parameters for commercial project.

15.2.1 Project Estimates for Commercial projects

Internal Coordination Before Estimation

Team	Inputs Required
Design Team	Final layouts, 3D renders, material schedule
MEP Team	Electrical, HVAC, and plumbing scope & BOQs
Procurement	Vendor rates, material brands, delivery timelines
Execution/Project Team	Site work scope, labor costs, timelines
Finance Team	Tax structure, contingencies, costing structure

Table 15.2.1:

Prepare the Project Estimate Bill of Quantities (BOQ) Template

S. No.	Category	Description	Unit	Qty	Rate (INR)	Total (INR)
1	Flooring	Vinyl Flooring – Hospital Grade	Sqft	2,000	120	2,40,000
2	Furniture	Modular Workstations (Commercial)	Nos	50	15,000	7,50,000
3	HVAC	Ductable AC Installation	Tons	10	55,000	5,50,000
4	False Ceiling	Gypsum Board + Grid Ceiling	Sqft	1,500	95	1,42,500
5	Electrical Works	Light Fixtures & Wiring	L.S.	1	2,00,000	2,00,000

Table 15.2.2:

15.2.2 Guidelines for Client Visits, Inspections and Reporting

The guidelines are same as covered in Module 15. Some specifics for commercial projects include:

- **Client Interaction:**
  - Welcome the client and introduce accompanying team members
  - Briefly state what will be reviewed today
  - Walk through each key area as per project zoning (e.g., ICU, reception, conference rooms)
- **Site Walkthrough Focus:**

Area	What to Inspect
Commercial	Furniture alignment, ceiling work, lighting points, branding zones
Hospital	Wall treatments, vinyl flooring, OT wall paneling, nurse stations
MEP	Placement of switches, ducting, water points, gas lines (hospital)
Safety	Fire safety points, emergency exit visibility, CCTV, alarms
Cleanliness	Dust-free areas, organized material placement, waste disposal

Table 15.2.3:

15.2.3 Delegating Tasks

To delegate tasks and responsibilities for commercial and hospital interior design projects, most of the activities are same as covered in Module 15. Some different aspects include:

1. Break the entire project into manageable work zones and technical categories, such as:

Zone/Component	Examples
Commercial	Workstations, conference rooms, reception, pantry
Hospital	ICU, OPD, diagnostics, waiting areas, nurse stations
Core Categories	Layout planning, MEP, HVAC, civil work, modular furniture, finishes

Table 15.2.4:

2. Identify the teams and then give them the responsibilities:

Role	Responsibility
Project Manager	Overall coordination, budget tracking, team alignment
Interior Designer	Design development, material selection, client presentation
Site Engineer	Day-to-day execution monitoring, site safety
MEP Coordinator	Electrical, plumbing, HVAC planning and inspection
Procurement Lead	Material sourcing, vendor management, delivery tracking
Quality Controller (QC)	Inspections, snag lists, adherence to specifications
Client Liaison Officer	Communication bridge between client and internal team
Safety Officer (Hospital)	Ensures infection control, fire safety, access standards

Table 15.2.5:

3. Use RACI matrix-which defines who is Responsible, Accountable, Consulted and Informed.

Task	Designer	PM	Site Engineer	Client
Finalize layout	R	A	C	I
Approve materials	C	A	C	R
HVAC coordination	C	A	R	I
Modular furniture install	C	A	R	I
Client walkthroughs	C	A	C	R

Table 15.2.6:

4. **Use Excel, Google Sheets or Trello to keep track:**

Task	Assigned To	Start Date	Deadline	Status	Priority
3D design submission	Designer	Apr 2	Apr 5	In Progress	High
Electrical rough-in	MEP Lead	Apr 6	Apr 10	Not Started	High
Material delivery – ICU flooring	Procurement	Apr 3	Apr 8	Pending	Medium
Brand wall graphics	Graphics Vendor	Apr 10	Apr 12	Scheduled	Low

Table 15.2.7:

15.2.4 Design Docket-Review and Approval

Reviewing and approving a Design Docket for a commercial or hospital interior design project is a critical milestone that ensures the design aligns with client requirements, functional needs and execution feasibility. The flow of tasks for review and approval is as follows:



Fig. 15.2.1: Flow of Tasks for Review and Approval

Though most of the activities are same as covered in Module 15, few different aspects include:

1. The design team must compile a complete docket. Ensure critical hospital zones (OT, ICU, labs) are designed with hygiene, pressure control, and zoning principles.

2. Create a formal approval document signed by:

Name	Role	Signature	Date
Client			
Project Manager			
Design Head			

Table 15.2.8:

Add a “Status: Approved for Execution” watermark or header on finalized design documents

3. Distribute the approved design docket to:
   - Site Engineers
   - Vendors
   - Contractors
   - Supervisors
4. Conduct a kickoff meeting for execution briefing

Summary

- A business development plan for commercial and hospital interior design projects involves space planning, compliance with building codes, HVAC systems, and integration of data and security technologies.
- Client requirements are analyzed by reviewing layouts, blueprints, MEP drawings, and specific product preferences like furniture, materials, and finishes for both commercial projects.
- The scope of work for the project includes clear categorization of materials and product types, with a focus on functionality and durability in commercial and hospital settings.
- The scope of services includes furniture and flooring categories specific to each sector (commercial vs. hospital), with different standards for finishes, lighting, and safety features.
- Project estimates for commercial projects require internal coordination, with inputs from the design, MEP, procurement, and execution teams to prepare a detailed Bill of Quantities (BOQ).
- Client visits and inspections for these projects involve a walkthrough of key areas, inspecting furniture, finishes, MEP systems, and safety protocols, with client feedback documented for follow-up.
- Task delegation is critical in both commercial projects, and the RACI matrix is used to clarify roles and responsibilities for each team member to ensure smooth execution.
- The design docket review and approval process includes finalizing designs, obtaining client sign-off, and ensuring that functional requirements, such as hygiene and safety standards for hospital areas, are met.

Exercise

A. Multiple Choice Questions (MCQs)

1. Which technical aspect is crucial when developing a business development plan for commercial projects?
   a. Space planning and zoning requirements
   b. Decoration and aesthetics
   c. Product branding and marketing
   d. Social media advertising

2. What is included in the scope of work for a hospital project?
   a. Furniture only
   b. Modular furniture, anti-bacterial materials, and medical-grade finishes
   c. Only flooring and wall finishes
   d. Brand wall graphics

3. What is the primary focus during client visits for commercial projects?
   a. Discussing project budget
   b. Inspecting furniture, finishes, and MEP installations
   c. Organizing promotional materials
   d. Scheduling client meetings

4. Which role is responsible for ensuring that the design adheres to functional and hygiene requirements in hospital areas like the ICU?
   a. Interior Designer
   b. Site Engineer
   c. Safety Officer (Hospital)
   d. Procurement Lead

5. What is the purpose of the RACI matrix in task delegation for commercial projects?
   a. To assign tasks based on the budget
   b. To clarify roles and responsibilities among team members
   c. To track client feedback
   d. To estimate project costs

Hands-on Activity: Simulated Hospital Project Brief – Client Requirement to Execution

Objective:

Participants will apply the process of analyzing client requirements, developing a business development plan, creating scope of work, estimating the project, assigning responsibilities, and preparing a design docket — all for a fictitious multi-specialty hospital interior project.

Activity Steps:

Step 1: Project Brief Allocation (Group Work)

Each group receives a simulated hospital client brief including:

- Project type: 50-bed multi-specialty hospital
- Requirements: Reception, OPD, ICU, Diagnostic Zone, Staff Room, Admin Office
- Budget: ₹2.5 Crore
- Timeline: 6 months

Step 2: Business Development Plan

Each group prepares a plan that includes:

- Target stakeholders
- Marketing strategy
- Key technical differentiators (e.g., hygiene-compliant materials, MEP coordination)

Step 3: Client Requirement Analysis

Using the given brief, groups will:

- Draw a 2D sketch/layout showing functional zoning
- Identify space allocations (OPD, ICU, etc.)
- List required drawings: 3D, MEP, RCP, Fire Safety, Material Mapping

Step 4: Scope of Work

Each group drafts:

- Defined zones and services (e.g., HVAC, furniture, flooring)
- Product categories based on hospital compliance

Step 5: Project Estimation

Groups use a BOQ template to:

- Estimate 5 key items (flooring, furniture, HVAC, ceiling, electrical)
- Calculate total cost using assumed rates

Step 6: Task Demarcation (RACI Matrix)

Using the simulated team (PM, Designer, Engineer, MEP Lead, Client):

- Fill out a RACI table for 5 project tasks (layout finalization, material approval, HVAC, walkthroughs, furniture)

Step 7: Design Docket Submission

Each group prepares:

- One-page final design docket summary
- Approval sheet with roles and simulated signatures

Notes

Scan the QR codes or click on the link to watch the related videos

https://www.youtube.com/watch?v=nfN1p0GzQ5g

Hospital Interior Design

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

16. Technicalities in Academic Institution Project

UNIT 16.1: Business Development and Client Requirement Analysis for Academic Institution Project

UNIT 16.2: Project Execution, Estimation and Task Demarcation for Academic Institution Project

FFS/N0218

Key Learning Outcomes

At the end of this module, the participant will be able to:

1. Analyse and prepare a business development plan based on specified marketing and development strategies for academic institution project.
2. Identify client requirements in terms of layouts, blueprints, product types, etc. for academic institution project.
3. Identify the scope of work for the project by analyzing the client requirement and specifications.
4. Explain the process of preparing a project estimate and related documents in consultation with internal teams.
5. Explain the guidelines for performing client visits, inspection, and reporting of assigned academic institution project.
6. Identify and demark tasks and responsibilities based on technicalities of the assigned academic institution project.
7. Identify design docket and specifications based on client requirements and project execution parameters for academic institution project.

UNIT 16.1: Business Development and Client Requirement Analysis for Academic Institution Project

Unit Objectives

At the end of this unit, the participants will be able to:

1. Analyse and prepare a business development plan based on specified marketing and development strategies for academic institution project.
2. Identify client requirements in terms of layouts, blueprints, product types, etc. for academic institution project.
3. Identify the scope of work for the project by analyzing the client requirement and specifications.

Case Study: Academic Institution Interior Design Project

Background

A reputed academic trust commissioned a multidisciplinary interior design firm to redesign the interiors of its newly constructed college. The objective was to create:

- Smart and ergonomic learning environments
- A modern, tech-enabled library and AV room
- Faculty spaces, administrative block, and compliant washrooms
- All while maintaining safety, durability, and phased execution during the school term

1. Business Development Plan

Target Client: Mid-size educational institutions (CBSE/IB/State Board)

Plan Components:

- Space planning for classrooms, LRC, admin, AV room, and washrooms
- Compliance with fire exits, ramps, accessible washrooms
- Furniture ergonomics for different student age groups
- Technology integration: smart boards, Wi-Fi, PA system

Marketing Strategy:

- SEO-optimized content around “smart classrooms India”
- Education fair showcases
- Partnerships with EdTech companies

Risk Planning: Vendor delays, live campus safety, academic calendar alignment

2. Client Requirement Analysis

- **Consultation Points:**
  - 25–30 students/classroom

- Mixed traditional and digital teaching
- Use of space during full-day academic sessions
- Library to double as seminar room
- Furniture must support quick reconfiguration

- **Zoning Decisions:**
  - Admin Block → Entry
  - Classrooms → Flanking central corridor
  - AV Room + LRC → Rear wing (quiet zone)
  - Washrooms at corridor ends



Fig.16.1.1:

3. Scope of Work (SOW)

Zone	Scope Details
Classrooms	Anti-tip desks, smart boards, marker walls, soft floor tiles
Admin Office	Reception, principal's cabin, visitor lounge
Library	Acoustic ceiling, Wi-Fi, soft seating, wall shelving
AV Room	Tiered seating, projector mount, blackout panels
Washrooms	Sensor taps, partitions, signage
Circulation Area	Wayfinding signage, student-safe lighting

Table 16.1.1:

Material Specs:

- Vinyl flooring in classrooms (LG Hausys)
- Modular desks (Featherlite)
- Acoustic ceiling tiles (Armstrong)
- Sanitary fittings (Jaquar)

4. Estimation and BOQ

Category	Description	Unit	Qty	Rate (₹)	Total (₹)
Desks & Chairs	Classrooms + Faculty Rooms	Nos	200	₹3,500	₹7,00,000
AV System	AV Room, LRC	L.S.	1	₹2,50,000	₹2,50,000
Flooring	Vinyl (classrooms) + Tiles (admin)	Sft	5,000	₹120	₹6,00,000
Ceiling	Acoustic + Gypsum Combo	Sft	2,000	₹100	₹2,00,000
Washrooms	Fixtures + partitions	L.S.	1	₹1,75,000	₹1,75,000
Electrical	Cabling, switches, lighting	L.S.	1	₹2,00,000	₹2,00,000

Table 16.1.2:

5. Client Visits & Inspection Guidelines

Site Walkthrough Checklist:

Area	What to Inspect
Classrooms	Smart board alignment, finish quality
Library	Shelving height, seating comfort
Washrooms	Sensor functionality, cleanliness
AV Room	Lighting control, projector testing

Table 16.1.3:

Sample - Site Visit & Inspection Report

Project Name: K-12 School Interior Development

Date of Visit: 21 June 2025

Purpose of Visit: Mid-phase inspection of classrooms and library.

Work Completed

- Classroom furniture installed (100%)
- Library shelving complete (90%)
- AV room wiring in progress (50%)

Issues Found

- Loose panel edge in AV cabinet.
- Library table installation pending due to vendor delay.

Client Feedback

- Requested soft board on back wall of classrooms.

Recommendations / Next Steps

- Complete AV wiring by 24 June.
- Vendor follow-up for library tables.
- Add soft board requirement to BOQ.

Fig.16.1.2:

6. Task Delegation

Zone	Responsible Teams
Classrooms	Designer A + Furniture Vendor
Library	Designer B + AV Technician
AV Room	AV Vendor + MEP Coordinator
Washrooms	Site Engineer + QC Lead

Table 16.1.4:

Sample Tracker with RACI Matrix:

Task	Assigned To	Start Date	End Date	R	A	C	I	Status
Classroom furniture install	Furniture Vendor	2025-06-01	2025-06-03	Furniture Vendor	Project Manager	Designer	Client	Completed
Library AV setup	AV Technician	2025-06-03	2025-06-05	AV Technician	Project Manager	IT Coordinator	Client	In Progress
Washroom fixture fitting	Plumbing Contractor	2025-06-05	2025-06-08	Plumbing Contractor	Project Manager	Site Engineer	Client	Not Started
Admin block painting	Painting Contractor	2025-06-07	2025-06-10	Painting Contractor	Project Manager	QC Lead	Client	Scheduled
AV Room wiring	Electrician	2025-06-09	2025-06-12	Electrician	Project Manager	AV Coordinator	Client	Not Started

Table 16.1.5:

Gantt Chart:



Fig.16.1.3:

7. Design Docket – Review & Approval

Final Docket Includes:

- Zoning layout plans
- 3D renders of LRC and classroom
- Product data sheets
- Client sign-off page (Principal + Admin Head)

Status: Approved for Execution

16.1.1 Developing a Business Development Plan

A business development plan for an academic institution interior design project (e.g., schools, colleges, universities, training centers) must include specific technical aspects that go beyond aesthetics-focusing on functionality, compliance, durability, technology integration and safety. The different aspects of a business development plan for an academic institution interior design project are:

- **Space Planning & Functional Zoning:**
  - Classrooms, labs, libraries, faculty areas, administrative zones
  - Multipurpose halls, seminar rooms, auditoriums
  - Cafeteria, recreational spaces, washrooms
  - Circulation and student movement paths

  Take care of:

Age-specific ergonomics	Noise control in study zones	Accessibility (ADA-compliant routes, ramps, wide corridors)

Fig. 16.1.4: Space Planning & Functional Zoning

- **Building Code & Regulatory Compliance**
  - Fire safety: Fire exits, extinguishers, signage, alarms
  - Disability access: Ramps, elevators, accessible washrooms
  - Health & safety: Non-toxic materials, safe wiring, non-slip flooring
  - Educational standards: As per UGC, AICTE, CBSE, IB, or state board guidelines
- **HVAC and Ventilation Systems**
  - Efficient cooling/heating in large classrooms and auditoriums
  - Proper air circulation in labs and libraries
  - Fresh air intake in high-occupancy areas (e.g., hostels, dining halls)
  - Energy-efficient systems and zoning controls
- **Electrical & Lighting Design**
  - Lux levels based on space (e.g., 300–500 lux in classrooms)
  - Emergency backup systems for labs and offices
  - Task lighting for reading/study areas
  - Motion-sensor or energy-saving lighting in corridors/toilets
- **IT & AV Infrastructure**
  - LAN cabling for digital learning
  - Smart boards and projectors in classrooms
  - Server rooms with appropriate cooling and security
  - Audio-visual systems for auditoriums and seminar halls
  - Wi-Fi routers and switches (placement for strong coverage)

- **Furniture & Ergonomics**
  - Durable, age-appropriate desks and chairs
  - Teacher podiums, storage lockers, lab counters
  - Modular and flexible furniture for multi-use spaces
  - Anti-tip, rounded-edge design for safety
  - Stackable or collapsible furniture for dynamic zones
- **Acoustics and Soundproofing**
  - Acoustic ceiling tiles in classrooms and libraries
  - Sound insulation in seminar rooms, music rooms, and auditoriums
  - Noise-reducing partitions between classrooms
- **Material & Finish Specifications**
  - **Durability:** High footfall = wear-resistant flooring (vinyl, SPC, vitrified tiles)
  - **Cleanability:** Easy-to-maintain paints, laminates, and surfaces
  - **Safety:** Anti-skid floors, low-VOC materials, flame-retardant fabrics
  - **Color psychology:** Use of calm, motivational, or focused colors based on room function
- **Sustainability Goals**
  - Use of green-certified materials (LEED/IGBC)
  - Daylight optimization
  - Water-saving fixtures
  - Solar integration if part of infrastructure
- **Phased Execution Planning**
  - Plan for minimal disruption to academic calendar
  - Prioritize holidays/weekends for noisy work
  - Define deliverables per block/phase (e.g., Classroom Block A → Library → Admin)
- **Technology Integration**
  - Digital learning infrastructure
  - Central PA system integration
  - Fire and security system interface
  - RFID access (hostels/labs/library)
  - CCTV & smart campus systems
- **Risk & Contingency Management**
  - Site safety plans (especially with students around)
  - Dust and debris control during renovation
  - Vendor performance tracking and substitution plans
  - Buffer timelines for inspection and approvals

16.1.2 Analysing Client Requirements

Analyzing and interpreting client requirements for an academic institution interior design project involves understanding their educational objectives, user demographics (students, faculty, admin), functionality needs and infrastructure constraints. While most requirements and analyzing techniques remain same as covered in Moule 19, some specific steps in this process typically involves the following steps:

- **Conduct Initial Client Consultation –** Understand vision, mission, and values of the institution and discuss academic levels, e.g. preschool, K-12, college, skill training, etc.

  Find out about:

  - Number of students per class
  - Type of learning (digital, collaborative, traditional)
  - Hours of usage (day school, residential)
  - Future expansion plans
- **Analyze their Layout Requirements**
  - **Zoning:** Academic vs. admin vs. recreational vs. residential
  - **Circulation:** Student flow, emergency exits, accessibility
  - **Sunlight & ventilation:** Optimize learning environments
  - **Services layout:** Placement of washrooms, electrical shafts, HVAC zones
- **Review Functional Requirements Per Zone**

Zone	Typical Requirements
Classrooms	Ergonomic desks, whiteboards, smart tech integration, storage
Labs	Plumbing/electrical points, chemical-safe furniture, exhaust systems
Library	Soft seating, shelving, quiet zones, task lighting
Admin Office	Reception, cabins, storage, waiting area
Auditorium	Stage, AV systems, tiered seating, acoustic panels
Hostels	Durable furniture, bunk beds, storage units, study desks
Washrooms	Sensor taps, partitions, anti-slip flooring
Cafeteria	Easy-to-clean surfaces, seating capacity, food counter design

Table 16.1.6: Review Functional Requirements Per Zone

- **Consider Technology & AV Requirements**
  - Smart boards, projectors, Wi-Fi coverage
  - Charging points at desks or podiums
  - PA systems, CCTV integration
  - Centralized control rooms (for campuses)

- **Review Compliance & Safety Needs**
  - Fire exits, extinguisher points, alarms
  - Ramps, tactile flooring, accessible washrooms
  - Non-toxic finishes, rounded corners (child safety)
  - Other compliance requirements where applicable

16.1.3 Preparing Scope of Work

The scope of work is similar as covered in Module 15, but some specific templates or documents required are:

- **Areas Covered**

Area	Elements Included
Classrooms	Desks, chairs, boards, lighting, charging points
Labs	Specialized counters, plumbing, electrical points, stools
Library	Book shelving, reading desks, soft seating, lighting
Administrative Offices	Cabins, reception, meeting rooms, storage
Auditorium/Seminar Rooms	Stage, seating, lighting, AV system
Cafeteria	Tables, food counters, washable surfaces
Washrooms	Anti-skid flooring, partitions, sanitary fittings
Hostels (if any)	Beds, desks, wardrobes, lighting
Corridors/Reception	Branding, signage, lighting, seating (if needed)

Table 16.1.7: Areas Covered

- **Material & Product Specifications**
  - Child-safe and anti-tip furniture
  - Low-VOC, eco-friendly paints
  - Fire-rated and anti-bacterial wall panels (as needed)
  - Non-slip, high-traffic flooring
  - Durable modular classroom furniture
  - AV integration-ready smart classroom components
  - Acoustic ceilings and partitions

- **Timeline & Milestones**

Phase	Task	Timeframe
Phase 1	Design finalization	___ weeks
Phase 2	Material selection & approval	___ weeks
Phase 3	Mobilization & execution start	___
Phase 4	Mid-project walkthrough & snag rectification	___
Phase 5	Final handover	___

Table 16.1.8: Timeline & Milestones

UNIT 16.2: Project Execution, Estimation and Task Demarcation for Academic Institution Project

Unit Objectives

At the end of this unit, the participants will be able to:

1. Explain the process of preparing a project estimate and related documents in consultation with internal teams.
2. Explain the guidelines for performing client visits, inspection, and reporting of assigned academic institution project.
3. Identify and demark tasks and responsibilities based on technicalities of the assigned academic institution project.
4. Identify design docket and specifications based on client requirements and project execution parameters for academic institution project.

16.2.1 Project Estimates for Academic Institution Project

Some specific templates for preparing a project estimate and related documents for an academic institution project in consultation with internal teams are:

- **Bill of Quantities (BOQ) Format –** Include brand names, specifications, and warranty coverage in remarks.
- **Detailed Project Proposal:**
  - Summary of work
  - Room-wise scope
  - Grand total with taxes
  - Offer validity
  - Payment terms & timeline
- **Gantt Chart or Project Timeline –** Break the project into clear phases:

Phase	Activities	Duration
Phase 1	Design Finalization	1 Week
Phase 2	Material Procurement	2 Weeks
Phase 3	Execution	6 Weeks
Phase 4	Final Inspection & Handover	1 Week

Table 16.2.1: Gantt Chart or Project Timeline

- **Material Specification Sheet**

Area	Material Type	Brand	Remarks
Classrooms	Desks & Chairs	Featherlite	Anti-tip, metal base
Library	Flooring	LG Hausys	Acoustic vinyl
Washrooms	Sanitary Fixtures	Jaquar	Sensor taps

Table 16.2.2: Material Specification Sheet

16.2.2 Guidelines for Client Visits, Inspections and Reporting

The guidelines are same as covered in Module 15. Some specifics for academic institution project include:

- **Client Engagement:**
  - Welcome and brief them on the status and purpose of the visit
  - Provide printed site layouts or tablet visuals for reference
  - Walk through each major area (e.g., classrooms, labs, library, washrooms)
- **Site Inspection Focus Points:**

Area	What to Inspect
Classrooms	Furniture layout, finish quality, lighting & ventilation
Labs	Bench positioning, plumbing/electrical provision, safety fittings
Library	Shelving, acoustics, seating arrangement
Admin/Faculty Zones	Reception, partitions, storage layout
AV/Tech Areas	Smart board installation, cabling, server/AV rooms
Washrooms	Cleanliness, fixtures, accessibility
Compliance Areas	Fire exits, ramp installation, signage, safety barriers

Table 16.2.3: Site Inspection Focus Points

Take photos of finished zones and incomplete areas for documentation.

Some best practices for Client Visits and Inspection are:



Fig. 16.2.1: Best Practices for Client Visits and Inspection

16.2.3 Delegating Tasks

To delegate tasks and responsibilities for commercial and hospital interior design projects, most of the activities are same as covered in Module 15. Some different aspects include:

- Create Task Buckets by Zone or Phase – For example:

a. Block A Classrooms → Site Engineer 1 + Designer A

b. Library → Designer B + Furniture Vendor

c. Science Labs → MEP + QC Engineer

d. Washrooms & Common Areas → Civil + QC Team

Example by Phase:

Phase	Task Type	Assigned Team
Phase 1	Site measurements, layout finalization	Design Team
Phase 2	MEP rough-in & civil work	Site + MEP
Phase 3	Ceiling & flooring	Site + Vendor
Phase 4	Furniture & AV install	Vendor + AV Team
Phase 5	Final snagging & client handover	QC + PM

Table 16.2.4: Example by Phase

- **Communicate Clearly**

  Create a responsibility matrix (RACI): Example – Smart Classroom Setup

  a. **Responsible:** AV Technician

  b. **Accountable:** PM

  c. **Consulted:** IT Lead

  d. **Informed:** Client

16.2.4 Design Docket—Review and Approval

Reviewing and approving a Design Docket for an academic institution interior design project is similar to the aspects and documents covered in Module 15.

The flow of tasks for review and approval is as follows:



Fig. 16.2.2: Flow of Tasks for Review and Approval

Summary

- A business development plan for academic institution projects includes space planning, compliance with building codes, HVAC, IT infrastructure, and safety features, all tailored to educational needs and functionality.
- Client requirements are analyzed by understanding the institution's educational objectives, user demographics, and specific needs for each functional zone (e.g., classrooms, labs, administrative areas).
- The scope of work for an academic institution project includes detailed specifications for furniture, materials, finishes, and AV/IT infrastructure, as well as compliance with safety and educational standards.
- The execution of the project is phased to ensure minimal disruption to the academic calendar, with clear milestones for design finalization, material selection, and execution.
- Project estimates for academic institution projects involve coordination between internal teams (design, MEP, procurement, and execution) to create a comprehensive Bill of Quantities (BOQ) and project proposal.
- Client visits and inspections involve a detailed walkthrough of major areas (e.g., classrooms, labs, library) to inspect functionality, quality, and compliance, with issues documented for follow-up.
- Task delegation is organized by zones or phases, ensuring that each aspect of the project (e.g., classrooms, labs, washrooms) has a designated team responsible for its execution.
- The design docket review and approval process includes internal team reviews, client presentations, and final approval before proceeding to project execution.

Exercise

A. Multiple Choice Questions (MCQs)

1. Which of the following is a key component of the business development plan for an academic institution project?
   a. Focus on aesthetic design alone
   b. Building code and regulatory compliance
   c. Ignoring safety and HVAC considerations
   d. Using only traditional teaching methods

2. What is a key consideration when analyzing client requirements for an academic institution project?
   a. Ignoring the client's educational objectives
   b. Understanding the institutional vision, academic levels, and user demographics
   c. Focusing only on exterior design features
   d. Prioritizing the aesthetics of recreational spaces over functionality

3. What is included in the scope of work for an academic institution project?
   a. Only the classroom furniture
   b. Furniture, flooring, ceiling, AV systems, and safety features for all functional zones
   c. Only administrative office furniture
   d. Just the outdoor landscaping and parking areas

4. Why is a phased execution plan important for an academic institution project?
   a. To prioritize the design aesthetics over functionality
   b. To ensure minimal disruption to the academic calendar and optimize work during holidays/ weekends
   c. To avoid compliance checks during the execution
   d. To delay the construction process

5. What is the purpose of the RACI matrix in delegating tasks for an academic institution project?
   a. To assign the project budget
   b. To clarify roles and responsibilities, ensuring clear accountability and communication
   c. To ignore the project timeline
   d. To reduce the number of workers involved

Hands-On Exercise: Design & Execution Plan for a Vocational Training Centre

Background Scenario:

Your design firm has received a request from a state-funded skill development authority to design the interiors of a Vocational Training Centre (VTC) aimed at youth aged 18–30. The VTC will offer courses in tailoring, electrical work, and basic computer literacy. The facility is located in a semi-urban area and must be designed to be durable, accessible, technology-integrated, and student-friendly.

Task Overview:

You are assigned a task to prepare and present the interior project documentation covering client analysis, planning, execution, and review.

Exercise Steps

Step 1: Develop a Business Development Plan

Prepare a 1-page plan covering:

- Space planning zones (labs, classrooms, admin, breakout space)
- Regulatory compliance for skill institutions
- Technology integration (computer labs, AV, network)
- Cost-efficiency and modularity strategy
- Proposed marketing/partnership ideas for future outreach

Step 2: Analyze Client Requirements

Prepare a client requirement sheet including:

- Number of students per trade
- Hours of training usage
- Layout preferences for lab-based vs. theory-based rooms
- Washroom and breakout zone locations
- Special instructions (e.g., safe tool storage, quiet reading room)

Step 3: Create a Functional Zoning Layout (Sketch or Verbal)

Manually or digitally sketch a layout with the following:

- 2 labs (Tailoring + Electrical)
- 1 Computer lab
- 2 Classrooms
- 1 Admin Office + Reception
- Male & Female Washrooms
- Storage + Breakout area

Label clearly with doors, circulation, and orientation.

Step 4: Prepare a Scope of Work and Estimation Sheet

Use a simple table format:

Zone	Item	Quantity	Estimated Cost (₹)
Electrical Lab	Workbenches	10	₹1,00,000
Computer Lab	Desks + Chairs	15	₹1,05,000
Classrooms	Whiteboards, Fans	2 sets	₹50,000
Washrooms	Fixtures + Cubicles	2 units	₹70,000

Also include:

- Gantt chart for 4 phases (Design, Procurement, Execution, Handover)
- 5% contingency
- Payment terms suggestion

Step 5: Conduct a Mock Client Inspection

Create a checklist for site inspection including:

- Safety checks (non-slip, signage)
- Equipment/furniture installation
- Ventilation and lighting
- AV/projector setups

Step 6: Create a Task Demarcation Table

Zone	Responsible	Accountable	Consulted	Informed
Tailoring Lab	Furniture Vendor	Project Manager	Designer	Client
AV Setup	AV Technician	PM	IT Consultant	Client
Admin Block	Civil Contractor	PM	Architect	Admin Head

Step 7: Design Docket Checklist

Attach or list the following:

- Final approved layout
- Material specification sheet
- Lighting & electrical plan
- AV equipment details
- Furniture style samples

Submission Format:

Participants should compile the output as a PDF/Word document or present it as:

- A client pitch
- A team debrief
- A final execution kit

Notes

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

17. Conduct Client Deliberation and Defining Scope of Work for Hospitality Project

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

UNIT 17.1: Business Development and Client Requirement Analysis for Hospitality Project

UNIT 17.2: Project Execution, Estimation and Task Demarcation for Hospitality Project

FFS/N0217

Key Learning Outcomes

At the end of this module, the participant will be able to:

1. Analyse and prepare a business development plan based on specified marketing and development strategies for hospitality project.
2. Identify client requirements in terms of layouts, blueprints, product types, etc. for hospitality project.
3. Identify the scope of work for the project by analyzing the client requirement and specifications.
4. Explain the process of preparing a project estimate and related documents in consultation with internal teams.
5. Explain the guidelines for performing client visits, inspection, and reporting of assigned hospitality project.
6. Identify and demark tasks and responsibilities based on technicalities of the assigned hospitality project.
7. Identify design docket and specifications based on client requirements and project execution parameters for hospitality project.

UNIT 17.1: Business Development and Client Requirement Analysis for Hospitality Project

Unit Objectives

At the end of this unit, the participants will be able to:

1. Analyse and prepare a business development plan based on specified marketing and development strategies for hospitality project.
2. Identify client requirements in terms of layouts, blueprints, product types, etc. for hospitality project.
3. Identify the scope of work for the project by analyzing the client requirement and specifications.

Case Study: Hospitality Interior Design Project – Boutique Hotel

Background

An independent hospitality investor has commissioned an interior design firm to conceptualize and execute the interiors of a 30-room boutique hotel located in a heritage urban district. The hotel must balance modern functionality with cultural aesthetics and cater to both leisure and business travelers.

The design scope includes:

- Guest rooms & suites
- Reception & lobby area
- All-day dining restaurant
- Rooftop bar
- Meeting rooms
- Staff/service areas
- Restrooms, corridors, and lift lobbies

Project Solution

1. **Business Development Plan**

   Target Segment:

   Boutique hotels in urban leisure and business districts

Proposal Strategy:

- Cultural storytelling through design
- Use of sustainable, low-maintenance materials
- Revenue-enhancing spaces like rooftop bar and flexible meeting rooms
- USP: Locally inspired interiors with modern comfort

Marketing Tactic:

Concept deck with mood boards, brand story, ROI estimate based on room rate × occupancy × guest satisfaction metrics

2. Client Requirement Analysis

Initial Client Brief:

- Blend of luxury and local heritage
- Mix of standard rooms, deluxe suites, and one penthouse
- Vibrant but not overpowering color palette
- Soundproof rooms and well-lit public areas
- Flexible seating in restaurant & bar
- Preference for Indian craftsmanship where feasible

Design Team Process:

- Site visits and structure measurements
- Interviews with client's operations consultant and chef
- Study of guest flow, sunlight patterns, service core placement
- Evaluation of acoustic, lighting, and HVAC systems per space type

3. Space Planning & Layout

Zone	Design Considerations
Reception + Lobby	Double-height ceiling, art wall, seating clusters
Guest Rooms	Soundproofing, warm lights, platform beds, work desk
Restaurant	Semi-open kitchen, buffet zone, flexible seating, local motifs
Rooftop Bar	Pergola, low seating, bar island, lighting & acoustic zoning
Meeting Rooms	Modular furniture, projection wall, acoustic panels
Service Core	Hidden behind walls, direct vertical access to service lift

Table 17.1.1:



Fig.17.1.1:

4. Scope of Work

Includes:

- Interior demolition of previous structure
- Civil partitioning and MEP alignment
- Ceiling, flooring, paneling, furniture
- Loose furniture procurement
- Lighting and automation installation
- FF&E (Furniture, Fixtures & Equipment) coordination
- Wayfinding and signage

Execution Plan in Phases:

1. Design Finalization
2. Material Selection
3. MEP + Civil
4. Furniture & Fit-outs
5. Soft furnishing & accessories
6. Final snag list & handover

5. **Estimation and BOQ Summary**

Zone	Item	Quantity	Rate (₹)	Total (₹)
Guest Rooms	Bed + Wardrobe + Desk	30 sets	₹90,000	₹27,00,000
Lobby Area	Seating cluster (sofa, chairs)	5 clusters	₹1,20,000	₹6,00,000
Rooftop Bar	Bar counter, seating, lights	L.S.	-	₹7,50,000
Restaurant	Tables, buffet counter	L.S.	-	₹5,00,000
Meeting Room	Acoustic walls, AV setup	2 rooms	₹2,50,000	₹5,00,000
Common Areas	Lighting, signage, décor	L.S.	-	₹3,00,000
Subtotal				₹53,50,000
GST + Contingency				₹9,00,000
Total				₹62,50,000

Table 17.1.2:

6. **Task Demarcation**

Zone	Responsible	Accountable	Consulted	Informed
Guest Rooms	Carpenter Team	PM	Designer	Client
MEP	MEP Contractor	Site Engineer	Architect	Client
Restaurant	Interior Designer	PM	Chef + Ops Lead	Client
Rooftop Bar	Vendor + Lighting Team	PM	Acoustic Engineer	Client

Table 17.1.3:

Task	Assigned To	Start Date	End Date	R	A	C	I	Status
Guest Room Furniture Installation	Furniture Vendor	2025-07-01	2025-07-04	Furniture Vendor	Project Manager	Interior Designer	Client	Completed
Lobby Seating Setup	Lobby Furniture Contractor	2025-07-03	2025-07-06	Lobby Furniture Contractor	Project Manager	Client Liaison	Client	In Progress
Rooftop Bar Constr-uction	Civil Contractor	2025-07-05	2025-07-12	Civil Contractor	Project Manager	Architect	Client	Scheduled
Restaurant Lighting & Décor	Lighting Designer	2025-07-08	2025-07-14	Lighting Designer	Project Manager	Lighting Consultant	Client	Scheduled
Meeting Room AV Setup	AV Technician	2025-07-10	2025-07-16	AV Technician	Project Manager	IT Specialist	Client	Not Started

Table 17.1.4:

Gantt chart



Fig.17.1.2:

7. Client Visit & Inspection Guidelines

At each milestone:

- Present finishes, layouts, and lighting samples
- Walkthrough with visual checklist
- Site report with % completion, issues, revised schedule

Focus on:

- Room acoustics
- Ventilation in restaurant
- Bar height and lighting
- Lighting zones in meeting room

8. Review & Approval of Design Docket

Docket includes:

- 2D layout + zoning plan
- Room mock-up images and 3D renders
- Finish board
- Furniture spec sheet
- Signage and branding integration
- Approvals signed by client and operations consultant

Project Outcome

- Project completed in 90 days
- Hotel opened in time for peak season
- Client feedback: High functionality, guest satisfaction, and design-brand match
- Published in a hospitality design magazine

17.1.1 Developing a Business Development Plan

A hospitality project needs to be focussed on areas such as guest experience, operational efficiency, sustainability, and compliance. The different aspects of a business development plan for a hospitality interior design project (e.g. hotels, resorts, boutique stays, serviced apartments) interior design project are:

- **Functional Zoning & Space Optimization –** You need to maximize revenue per square foot without compromising comfort.

Room types (standard, deluxe, suites) with efficient layouts	Reception/lobby, dining, banquet, kitchen, spa, corridors	Service and back-of-house zones (laundry, staff rooms, pantry)	Circulation flow of guests vs. staff

Fig. 17.1.3: Functional Zoning and Space Optimization

- **Building Code & Regulatory Compliance**



Fig. 17.1.4: Building Code and Regulatory Compliance

- **HVAC & Ventilation Systems**

Zoning for rooms, lobby, kitchen, banquet halls	Split/VRF systems with centralized control	Ventilation and exhaust for wet areas (kitchens, bathrooms, spa)	Energy efficiency (green building norms, inverter tech)

Fig. 17.1.5: HVAC and Ventilation Systems

- **MEP (Mechanical, Electrical, Plumbing) Coordination**



Fig. 17.1.6: MEP Coordination

- **Lighting Design & Electrical Layout**

Layered lighting - ambient, task, accent, emergency	Dimming & automation (DALI/ KNX systems in luxury segments)	Energy-efficient fixtures (LED, motion sensors)	Electrical layout per room category (charging, reading lights, etc.)

Fig. 17.1.7: Lighting Design and Electrical Layout

- **Material Selection and Finishing Standards**



Fig. 17.1.8: Material Selection and Finding Standards

- **Acoustics & Soundproofing**

Soundproofing between rooms and corridors	Acoustic ceilings in lobbies, banquet halls	Soft surfaces in restaurants for speech clarity	STC-rated partitions or windows in premium rooms

Fig. 17.1.9: Acoustics and Soundproofing

- **Furniture, Fixtures & Equipment (FF&E)**

Custom-made beds, wardrobes, desks, minibars, headboards	Bathroom vanities and mirror units	Integrated lighting and tech into furniture (USB ports, wireless charging)	Compliance with hospitality-grade durability and finish

Fig. 17.1.10: Furniture, Fixtures and Equipment (FF&E)

- **Smart Technology Integration**



Fig. 17.1.11: Smart Technology Integration

- **Safety, Hygiene & Waste Management**

Clean zones in kitchens and housekeeping	Proper bin layouts and garbage chute design	Pest control access points and trap areas	Anti-fungal and anti-odor treatments for finishes

Fig. 17.1.12: Safety, Hygiene & Waste Management

- **Energy & Sustainability Goals**



Fig. 17.1.13: Energy & Sustainability Goals

- **Execution Phasing & Risk Control**

Plan around running operations (for renovations)	Separate guest/ public areas from work zones	Logistics planning for material movement	Procurement buffers for imported finishes/ furniture

Fig. 17.1.14: Execution Phasing and Risk Control

17.1.2 Analysing Client Requirements

Analyzing and interpreting client requirements for a hospitality interior design project involves understanding the guest experience, operational flow, branding goals, and compliance standards. While most requirements and analyzing techniques remain same as covered in Module 15, some specific steps in this process typically involves the following steps:

- **Review and Interpret Layouts & Blueprints**

Area	Interpretation Goals
Guest Rooms	Verify room sizes vs. brand standards (min. 180–300 sq.ft.)
Bathrooms	Plumbing shaft placement, wet/dry zoning, waterproofing scope
Lobby & Reception	Space for front desk, waiting lounge, concierge
F&B Outlets	Seating layouts, kitchen linkage, POS point placement
Back-of-House	Circulation for staff vs. guest, service elevators
Vertical Circulation	Elevator capacity, fire stairs, service vs. guest zones
Common Areas	Pool, gym, banquet, corridors – flow and zoning check

Table 17.1.5: Review and Interpret Layouts & Blueprints

Cross-reference layouts with client-provided space programs or area charts.

- **Analyze Room-wise Functional Requirements**

Room Type	Elements to Verify
Standard Room	Bed size, writing desk, wardrobe, minibar, AV panel
Suite	Living area, partition, dual vanities, storage
Accessible Room	Wider doorways, grab bars, lower switches
Bathroom	Mirror lighting, exhaust fan, non-slip floor, shower cubicle
Restaurant	Dining capacity, walkways, bar area
Spa & Gym	Locker areas, zoning, HVAC, acoustics

Table 17.1.6: Analyze Room-wise Functional Requirements

Match these elements with luxury level (budget, midscale, premium, luxury).

- **Identify Product Type Requirements –** FF&E (Furniture, Fixtures & Equipment):
  - **Beds & Mattresses:** Size, softness level, frame type
  - **Desks, Wardrobes, Headboards:** Finish, utility (in-built lighting, charging)
  - **Bathroom Fixtures:** Brands, water-saving preference
  - **Lighting:** Dimmable bedside lights, backlit mirrors, ambient lobby lighting

- **Tech Integration:** Smart TV, charging docks, Wi-Fi points
- **Common Area Furniture:** Lounge chairs, dining tables, banquet seating

- **Study Brand Guidelines (if chain hotel or franchise) –** Review brand manuals for:
  - Design vocabulary (color palette, material tone)
  - Artwork and signage rules
  - FF&E specifications
  - Operational layout guidelines (reception height, minibar placement, etc.)
- **Create a Client Requirement Document**

Section	Details
Project Overview	Property type, star rating, number of keys
Room Types	Size, amenities, finishes
Public Areas	Lobby, F&B, spa, banquet – function and look
BOH Areas	Storage, staff flow, kitchen zoning
Material Preferences	Brand specs, sustainability goals
Technology	Automation, AV, guest Wi-Fi, security needs
Sustainability Goals	LEED/IGBC guidelines, solar, water-saving

Table 17.1.7: Elements of Client Requirement Document

17.1.3 Preparing Scope of Work

The scope of work is similar as covered in Module 15, and the flow of the tasks are as follows:



Fig. 17.1.15: Scope of Work for Hospitality Project

UNIT 17.2: Project Execution, Estimation and Task Demarcation for Hospitality Project

Unit Objectives

At the end of this unit, the participants will be able to:

1. Explain the process of preparing a project estimate and related documents in consultation with internal teams.
2. Explain the guidelines for performing client visits, inspection, and reporting of assigned hospitality project.
3. Identify and demark tasks and responsibilities based on technicalities of the assigned hospitality project.
4. Identify design docket and specifications based on client requirements and project execution parameters for hospitality project.

17.2.1 Project Estimates for Hospitality Projects

While most of the estimates involve same documents preparation as described in Module 15, the gist of estimates is:

- Internal Coordination Checklist
- Project Estimate (BOQ Format)
- Supporting Documents
  - Cost Proposal Summary
  - Material & Brand Specification Sheet
  - Vendor & Rate Mapping Sheet
  - Execution Timeline (Gantt Chart or Table Format)
  - Work Contract / Agreement Draft
  - Internal Approval & Review Log
- Room Mock-Up Costing (RMC)

17.2.2 Guidelines for Client Visits, Inspections and Reporting

The guidelines for Client Visits, Inspections and Reporting in a hospitality interior design project are same as covered in Module 15.

17.2.3 Delegating Tasks

To delegate tasks and responsibilities for commercial and hospital interior design projects, the activities are same as covered in Module 15.

17.2.4 Design Docket-Review and Approval

Reviewing and approving a Design Docket for an academic institution interior design project is similar to the aspects and documents covered in Module 15.

Summary

- A business development plan for a hospitality interior design project focuses on maximizing space utilization, ensuring operational efficiency, and integrating smart technology, while adhering to building codes and safety regulations.
- Client requirements for hospitality projects are analyzed by reviewing space layouts, guest room sizes, bathroom designs, and public areas (e.g., lobby, F&B outlets) to align with luxury level standards and operational flow.
- Product type requirements (FF&E) are critical for the design, including specifications for furniture, fixtures, equipment, and smart technology integration to enhance guest experience.
- The scope of work for hospitality projects is detailed, covering all functional areas such as guest rooms, public areas, back-of-house spaces, and incorporating client-specific preferences like sustainability goals and brand guidelines.
- Project estimates for hospitality projects involve coordination among various teams (design, procurement, execution) to create a comprehensive Bill of Quantities (BOQ) and cost proposal summary, alongside vendor rate mapping.
- Client visits and inspections for hospitality projects focus on reviewing the quality of construction, functionality, and compliance with design specifications, with a focus on guest experience and operational efficiency.
- Task delegation for hospitality projects follows a similar approach as commercial or academic projects, with clear assignments based on specific zones (e.g., guest rooms, public areas, kitchen).
- The design docket review and approval process ensures that all client requirements and technical specifications are met before proceeding with project execution.

Exercise

A. Multiple Choice Questions (MCQs)

1. What is a key focus of the business development plan for hospitality interior design projects?
   a. Only aesthetic appeal
   b. Maximizing revenue per square foot and integrating smart technology
   c. Ignoring operational flow
   d. Avoiding compliance with safety standards

2. Which of the following is a critical element in analyzing client requirements for a hospitality project?
   a. Reviewing only the aesthetic preferences of the client
   b. Analyzing functional flow, guest room sizes, and amenities in public areas
   c. Focusing only on material selection
   d. Ignoring technology integration

3. What should the scope of work for a hospitality project include?
   a. Only furniture specifications
   b. Details for all functional areas like guest rooms, public areas, and back-of-house spaces
   c. No mention of sustainability goals
   d. Only the aesthetic aspects of the design

4. What is the role of the smart technology integration in hospitality interior design projects?
   a. It enhances guest experience through automation, AV systems, and guest Wi-Fi
   b. It focuses only on aesthetics
   c. It ignores the guest experience
   d. It is irrelevant to the design process

5. What is the purpose of reviewing and approving a design docket in hospitality projects?
   a. To finalize only the aesthetic design
   b. To ensure that all client requirements and technical specifications are met before execution
   c. To delay the project execution
   d. To bypass client input

Hands-On Activity: Interior Planning for a Bed & Breakfast (B&B)

Objectives:

- Business development planning for a hospitality space
- Client requirement analysis and interpretation
- Scope of work creation for small-scale execution
- Budgeting using BOQ format
- Task delegation with RACI
- Mock client inspection & feedback
- Review of a simple design docket

Scenario:

A couple is converting their 2-storey residential property into a 5-room Bed & Breakfast (B&B) targeting solo travelers and couples. They want a cozy, functional space that reflects local culture, is sustainable, and complies with fire and safety norms.

Your task is to prepare the core project documentation and simulated deliverables for this assignment.

Tasks

Task 1: Business Development Brief

Write a 1-page business development outline:

- Target audience (tourists, remote workers, couples)
- Interior theme (minimalist, rustic, local arts)
- Functional zones: 5 rooms, lounge, breakfast area, reception
- Cost-effective design strategies
- Sustainability plan (e.g., LED lights, reclaimed wood furniture)

Deliverable: "B&B Business Development Plan"

Task 2: Client Requirement Sheet

Draft a requirement analysis table covering:

Space	Client Needs
Guest Rooms	Double bed, work desk, reading lights, warm colors
Lounge Area	Bookshelf, coffee table, board games
Breakfast Room	4–6 person seating, toaster/coffee area
Bathrooms	Instant water heater, anti-skid tiles
Reception Corner	Openable desk, storage, local artwork display

Deliverable: "Client Requirement Sheet – B&B Project"

Task 3: Space Zoning Sketch

Sketch (hand-drawn or digital) a zoning plan for:

- Guest rooms on 1st and 2nd floor
- Breakfast and lounge on ground floor
- Reception at entry
- Utility areas and staircases

Label key zones clearly.

Deliverable: "B&B Functional Layout Sketch"

Task 4: Scope of Work Summary

Create a simple scope of work covering:

Zone	Work Description
Guest Rooms	Paint, wardrobe, bed, lights
Lounge Area	Bookshelf, wall paint, seating setup
Breakfast Room	Table setup, wall art, pantry counter
Bathrooms	Plumbing, mirror, accessories
Reception	Desk, background panel, branding

Deliverable: "Scope of Work – B&B Interior"

Task 5: Project Estimation Table (BOQ Format)

Item	Quantity	Unit Rate (₹)	Total (₹)
Double Beds	5	₹15,000	₹75,000
Desks & Chairs	5 sets	₹6,000	₹30,000
Lounge Sofa + Shelf	1 set	₹25,000	₹25,000
Breakfast Table + 6 Chairs	1 set	₹18,000	₹18,000
Reception Counter	1	₹12,000	₹12,000
Bathroom Fixtures	5 bathrooms	₹5,000	₹25,000

Add 5% contingency and GST (12%).

Deliverable: "B&B BOQ Estimate Sheet"

Task 6: RACI Matrix (Small Team)

Task	R	A	C	I
Furniture Installation	Carpenter Team	Project Manager	Designer	Client
Paint & Décor	Paint Vendor	Site Supervisor	Client	Client
Pantry Setup	Modular Vendor	Project Manager	Chef Consultant	Client
Lighting & Electrical	Electrician	Project Manager	MEP Consultant	Client

Deliverable: "Task Delegation – RACI Matrix (B&B)"

Task 7: Mock Site Visit Report

Prepare a short inspection report covering:

- Site progress zone-wise
- Any issues raised (e.g., misaligned shelf, paint mismatch)
- Client comments and requests
- Recommended actions and updated timeline

Deliverable: "Client Inspection Summary – B&B Site Visit"

Task 8: Design Docket Compilation

Compile:

- Zoning sketch
- Mood board or finish board samples (color + materials)
- Final FF&E selections
- Approval signature block

Deliverable: "Design Docket – B&B Final Submission"

Submission Format:

Deliverables can be submitted in one PDF or as part of a team presentation. This is ideal for:

- Portfolio building
- Assessment or capstone
- Presentation to simulated client (peer review)

Notes

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

18. Technicalities in a Retail Fit-out and Exhibition Project

UNIT 18.1: Business Development & Client Requirement Analysis for Retail Fit-out and Exhibition Project

UNIT 18.2: Project Execution, Estimation and Task Demarcation for Retail Fit-out and Exhibition Project

FFS/N0219

Key Learning Outcomes

At the end of this module, the participant will be able to:

1. Analyse and prepare a business development plan based on specified marketing and development strategies for Retail Fit-out and Exhibition project.
2. Identify and interpret client requirements in terms of layouts, blueprints, product types, etc. for Retail Fit-out and Exhibition project.
3. Identify the scope of work for the project by analyzing the client requirement and specifications.
4. Explain the process of preparing a project estimate and related documents in consultation with internal teams.
5. Explain the guidelines for performing client visits, inspection, and reporting of assigned Retail Fit-out and Exhibition project.
6. Identify and demark tasks and responsibilities based on technicalities of the assigned Retail Fit-out and Exhibition project.
7. Identify design docket and specifications based on client requirements and project execution parameters for Retail Fit-out and Exhibition project.

UNIT 18.1: Business Development & Client Requirement Analysis for Retail Fit-out and Exhibition Project

Unit Objectives

At the end of this unit, the participants will be able to:

1. Analyse and prepare a business development plan based on specified marketing and development strategies for Retail Fit-out and Exhibition project.
2. Identify and interpret client requirements in terms of layouts, blueprints, product types, etc. for Retail Fit-out and Exhibition project.
3. Identify the scope of work for the project by analyzing the client requirement and specifications.

Case Study: Retail Fit-out and Exhibition Project – Luxury Watch Brand

Background

A global luxury watch brand, "Témpos," has commissioned a design firm to deliver two key interiors:

1. A 250 sqm high-end retail store in a premium shopping mall.
2. A 50 sqm exhibition booth for the upcoming international horology expo.

The project requires blending the brand's heritage with cutting-edge display and experiential design. The Assistant Project Manager (Interior Design) is responsible for end-to-end coordination — from business development to handover.

Mapped Project Execution

1. **Business Development Plan**
   - **Services Offered:**
     - Turnkey retail fit-out, custom joinery, exhibition booth design, and AV integration
   - **Target Market:**
     - **Retail:** High-luxury brands in mall-based locations
     - **Exhibition:** International watch expos, recurring brand activations
   - **Execution Strategy:**
     - Fast-track fit-out using modular joinery
     - Pre-built booth components manufactured off-site for quick setup
     - Separate on-site and workshop teams
   - **Compliance Focus:**
     - Mall and fire safety approvals
     - Electrical load mapping and Wi-Fi readiness for exhibition

- **Tech Tools:**
  - AR mock-up of booth
  - Gantt chart planning in MS Project
  - CRM tool to track brand approvals
- **Risk Mitigation:**
  - Vendor backups for imported glass and LEDs
  - Buffer timelines for international shipping delays

2. Client Requirement Analysis

- **Retail Fit-out Brief:**
  - Create a warm, museum-like feel
  - Showcasing watches with concealed lighting, modular POS counters, and acoustic wall panels
- **Exhibition Booth Brief:**
  - Open booth with curved wall, rotating hero display, and digital touch panels
  - Light, modular and compliant with venue rules
- **Layout Review:**
  - Ceiling height checks for false ceiling + AC ducts
  - MEP location verification, fire exit compliance
- **Zoning Requirements:**
  - **Retail:** Entry, display islands, lounge, storage
  - **Booth:** Welcome zone, AV wall, engagement zone
- **Technical Preferences:**
  - Track lighting, acoustic ceiling tiles, minimal signage
- **Brand Identity:**
  - Corporate identity standards (CIS) for fonts, finishes, and layouts followed strictly

3. Scope of Work

Area	Key Work Items
Retail Store	Flooring, display counters, custom backlit walls, AV setup, MEP coordination
Booth	Structural setup, vinyl wrap branding, AV screens, LED lighting, collapsible shelves
Shared Tasks	Design coordination, material submittals, mock-ups, compliance documentation

Table 18.1.1:

- **Exclusions:** Civil works, video content production, event logistics, mall deposits

4. Project Estimate (BOQ Format)

Item	Quantity	Unit Rate (₹)	Total (₹)
Display Counters (Retail)	6	₹65,000	₹3,90,000
Acoustic Paneling	30 sqm	₹2,500	₹75,000
Exhibition Wall Structure	1	₹1,50,000	₹1,50,000
AV Setup (Screens + Wiring)	L.S.	-	₹2,20,000
Track Lights (Retail + Booth)	40 nos	₹2,000	₹80,000
Branding + Vinyl Wrap	L.S.	-	₹1,00,000

Table 18.1.2:

Total Estimate (incl. contingency & GST): ₹10,50,000

- **Support Docs:**
  - Drawing Register
  - Risk Register (delays in MEP clearances, shipping risks)
  - Material Spec Sheets
  - Timeline: Gantt chart with 6 phases

5. Client Site Visits & Reporting

Frequency: Weekly site visits during execution

- **Focus Areas:** Finishes, lighting alignment, signage placement, storage access
- **Reporting Includes:**
  - % completion
  - Deviations from approved layout
  - Visual report with 5–6 photos
  - Action plan for next week
  - Client remarks

Sample - Client Site Visit & Inspection Report

Project: Retail Store Fit-out & Exhibition Booth for Témpos Luxury Watches

Client: Témpos Global

Date of Visit: 14 August 2025

Visited By: Project Manager, Client Representative, Branding Consultant

1. Work Progress Summary

- Retail joinery installation completed (100%)

- Booth fabrication on-site (90%)

- Lighting fixtures installed (75%)

- Vinyl branding pending final artwork approval (Scheduled for 16 Aug)

2. Observations / Issues Found

- AV screen wiring behind main display counter not aligned with approved location.

- Light intensity in booth too high—dimming circuit needs adjustment.

3. Client Feedback

- Appreciated wall finish quality in retail space.

- Requested real-time video demonstration of booth rotating display during final setup.

4. Recommendations / Next Steps

- Re-align AV cable trunking by 15 August.

- Complete branding installation after artwork clearance (ETA: 16 August).

- Conduct mock-up test of rotating feature and submit video for client sign-off.

5. Site Images / Attachments

(Attach photos of completed counters, lighting alignment, booth frame structure)

Fig.18.1.1:

6. Task Delegation

Task	Responsible	Accountable	Consulted	Informed
Retail Joinery Works	Carpenter Vendor	PM	Interior Designer	Client
AV Integration	Tech Vendor	PM	Brand Rep	Client
Booth Assembly & Setup	Fabrication Team	Project Lead	Event Manager	Client
Branding & Signage	Graphics Vendor	PM	Marketing Team	Client

Table 18.1.3:

7. Tracker Used

RACI Matrix

Task	Assigned To	Start Date	End Date	R	A	C	I	Status
Retail Store Joinery Installation	Carpentry Vendor	2025-08-01	2025-08-05	Carpentry Vendor	Project Manager	Interior Designer	Client	Completed
Exhibition Booth Fabrication	Booth Fabrication Team	2025-08-03	2025-08-06	Booth Fabrication Team	Project Manager	Event Coordinator	Client	In Progress
Lighting & AV Setup	AV Contractor	2025-08-07	2025-08-09	AV Contractor	Project Manager	Tech Consultant	Client	Scheduled
Vinyl Branding & Signage	Branding Vendor	2025-08-10	2025-08-11	Branding Vendor	Project Manager	Marketing Lead	Client	Not Started
Client Inspection Walkthrough	Project Manager	2025-08-15	2025-08-16	Project Manager	Client	Design Lead	Client	Pending

Table 18.1.4:

Gantt Chart



Fig.18.1.2:

8. Design Docket Review

Final docket submitted to client for approval included:

- General arrangement (GA) drawings
- MEP integration plan
- AV & lighting layout
- Material samples

- Mock-up photos
- Project timeline
- Sign-off form with comments

Status: Approved for Execution

Fig.18.1.3:

18.1.1 Developing a Business Development Plan

A business development plan for a Retail Fit-out and Exhibition project needs to blend strategy with strong technical and operational insight. The key technical aspects you should cover to make the plan robust and execution-ready:

- **Service Portfolio & Capabilities –** Clearly outline what services you provide:
  - Turnkey fit-out
  - Interior design & build
  - Custom joinery
  - Exhibition booth design & setup
  - Temporary and permanent installations
  - Lighting and AV integration

In-house vs. Outsourced Capabilities – Clarify which parts are done in-house (e.g., joinery, MEP) and what's subcontracted.

- **Target Market Segmentation**
  - **Retail**
    - Luxury brands, fashion, electronics, F&B, showrooms
    - Malls, standalone stores, kiosks/pop-ups
  - **Exhibitions**
    - Trade shows, expos, corporate events
    - Local vs. international participation
    - One-time vs. recurring booth design clients
- **Project Delivery Methodologies**
  - **Fast-Track Fit-outs –** Often required for retail – Outline how you manage tight deadlines with phased execution and parallel workflows.
  - **Modular & Prefab Techniques –** Especially useful in exhibition design where reusability matters.
  - **On-Site vs. Off-Site Execution Plan –** Define how much prep is done off-site in workshops vs. on-site installation.
- **Compliance & Technical Standards**
  - **Retail Fit-out Guidelines**
    - Mall management standards
    - MEP coordination requirements
    - Fire safety and accessibility compliance
  - **Exhibition Venue Requirements**
    - Load capacities
    - Temporary structure permits
    - Electrical/Wifi/AV systems
  - **Sustainability Certifications –** LEED, WELL, or local equivalents (especially important for international brands)
- **Vendor & Supply Chain Management**
  - Approved Material List (AML)
  - Lead Times for Imported Items
  - **Logistics for International Exhibitions –** Shipping, customs, on-site handling
- **Contingency Planning**
  - Backup suppliers for critical items
  - Last-minute fabrication capability
- **Technical Proposal & Tendering Framework**
  - Bill of Quantities (BoQ) Development
  - Value Engineering Options
  - Design Intent vs. As-Built Feasibility
  - Mock-up Presentations and Prototypes

- **Quality Control and Handover Protocols**
  - Snagging and De-snagging Process
  - Client Approval Milestones
  - Maintenance Manuals & Warranty Documentation
  - Post-Event Dismantling (for Exhibitions)
- **Digital Tools & Innovation**
  - **Use of Project Management Tools –** (Asana, Trello, MS Project, Procore)
  - **3D and AR/VR Presentations –** For pitching concepts, mock-ups, and final designs.
  - **CRM and Client Tracking –** For follow-ups, repeat business, and feedback analysis.

18.1.2 Analysing Client Requirements

Analyzing and interpreting client requirements for a hospitality interior design project involves understanding the guest experience, operational flow, branding goals, and compliance standards. While most requirements and analyzing techniques remain same as covered in Module 15, some specific steps in this process typically involves the following steps:

- **Client Briefing & Requirement Gathering**

  a. Initial Discussion
  - Understand the business type (luxury, tech, F&B, fashion, etc.).
  - Identify project goals – branding, visibility, footfall, experience.
  - Get clarity on:
    - Target audience
    - Timeline and budget
    - Specific brand guidelines

  b. Ask the Right Questions
  - What's the desired look and feel?
  - Any existing corporate identity standards (CIS)?
  - Are there technical preferences for lighting, signage, materials?
- **Reviewing Layouts & Blueprints**

  a. Analyze Layouts
  - Confirm usable floor area, ceiling height, and column grid.
  - Review MEP (Mechanical, Electrical, Plumbing) points – especially critical for F&B.
  - Note emergency exits, fire suppression systems, and air conditioning layout.

  b. Verify Against Requirements
  - Does the proposed layout match the functionality needed?
  - Fitting rooms?

- Storage or back-of-house?
- Demo areas or POS stations?

c. Zoning & Space Planning

- Break the space into:
- Display zones
- Interaction or experience areas
- Service/support zones

- **Branding & Visual Identity Alignment – Align with:**

Color palettes	Typography	Lighting ambiance (cool/warm tones)	Signage requirements

Fig. 18.1.4: Branding & Visual Identity Alignment

For exhibitions: integrate AV elements, motion graphics, and interactive screens if required.

- **Technical and Regulatory Compliance**
  - Mall/venue-specific fit-out guidelines
  - Local building codes (fire exits, occupancy limits)
  - Electrical loading and equipment safety
  - Accessibility (ADA-compliance, ramps, etc.)

18.1.3 Preparing Scope of Work

defines deliverables, roles, timelines and expectations—keeping everyone aligned from concept to handover. The SOW is similar as covered in Module 15, some different aspects are as follows:

- **Project Overview –** Briefly describe the project background and objective, for example "The project involves the interior design, detailing and execution support for a 250 square meters luxury watch retail store located in ABC Mall. It also includes the design and branding integration of a 50 square meters exhibition booth for the upcoming XYZ Trade Show.
- **Project Objectives**



Fig. 18.1.5: Project Objectives

- **Scope of Services**

  Retail:



Fig. 18.1.6: Retail

Exhibition:



Fig. 18.1.7: Exhibition

- **Client Inputs**
  - Provide brand guidelines and marketing material
  - Timely feedback and approvals
  - Appoint point-of-contact for decision-making
  - Provide site access and relevant permissions

- **Exclusions**
  - Civil/structural engineering
  - AV content creation (videos, animations)
  - Fit-out execution or construction (unless bundled)
  - Permit fees, mall deposits

UNIT 18.2: Project Execution, Estimation and Task Demarcation for Retail Fit-out and Exhibition Project

Unit Objectives

At the end of this unit, the participants will be able to:

1. Explain the process of preparing a project estimate and related documents in consultation with internal teams.
2. Explain the guidelines for performing client visits, inspection, and reporting of assigned Retail Fit-out and Exhibition project.
3. Identify and demark tasks and responsibilities based on technicalities of the assigned Retail Fit-out and Exhibition project.
4. Identify design docket and specifications based on client requirements and project execution parameters for Retail Fit-out and Exhibition project.

18.2.1 Project Estimates for Retail Fit-out/Exhibition Projects

When preparing a project estimate and related documentation with internal team for use on Retail Fit-out and Exhibition interior design projects, it is important to be structured, transparent and aligned with your execution and procurement strategies.

While most of the estimates involve same documents preparation as described in Module 15, some additional aspects for preparing project estimates are:

- **Project Estimate Summary (Cost Plan) –** Costs involved include:

Fig. 18.2.1: Project Estimates – Cost Plan

- **Drawing Register / Design Package Tracker –** Keep track of drawing status and versions, such as:
  - Drawing Name/Code
  - Description
  - Status (In progress, Final, Issued for Construction, etc.)
  - Responsible Designer
  - Issue Date
  - Client Comments
- **Time Schedule / Gantt Chart –** High-level view of design and fit-out timelines. The phases may include:
  - Concept Design
  - Client Approval Cycles
  - Schematic Development
  - Detail & IFC Drawings
  - Material Submittals
  - Fit-Out Duration
  - Snagging & Handover
  - Exhibition Set-up/Breakdown
- **Risk Register (Optional) –** Helps the team pre-empt issues before they impact timelines or budgets, risks may include:
  - Client delay in approvals
  - Long-lead items (custom lights, imports)
  - Exhibition venue access issues
  - Budget cuts or changes

18.2.2 Guidelines for Client Visits, Inspections and Reporting

The guidelines for Client Visits, Inspections and Reporting in a hospitality interior design project are same as covered in Module 15.

18.2.3 Delegating Tasks

To delegate tasks and responsibilities for commercial and hospital interior design projects, the activities are same as covered in Module 15.

18.2.4 Design Docket—Review and Approval

Reviewing and approving a Design Docket for an academic institution interior design project is similar to the aspects and documents covered in Module 15.

Summary

- A business development plan for retail fit-out and exhibition projects includes outlining services offered, market segmentation (e.g., retail brands, trade shows), compliance with building codes and technical standards, and integrating sustainability goals.
- Client requirements are analyzed by understanding the project type (luxury, tech, F&B), reviewing layouts, and aligning designs with branding and visual identity, while ensuring compliance with regulatory guidelines.
- The scope of work (SOW) for retail fit-out and exhibition projects defines deliverables, timelines, client inputs, and exclusions (e.g., civil engineering, AV content creation), ensuring all parties are aligned from design to handover.
- The process includes detailed planning for service execution, vendor management, contingency planning, and quality control, including post-event dismantling for exhibitions.
- Project estimates for retail fit-out and exhibition projects are structured and transparent, with a focus on alignment with procurement strategies and execution timelines, including cost plans and risk registers.
- Client visits, inspections, and reporting for these projects involve ensuring that the design meets the client's functional, aesthetic, and regulatory requirements, with a focus on brand guidelines and layout functionality.
- Task delegation is based on project phases, and roles and responsibilities are clarified to ensure smooth execution. The process includes preparing Gantt charts and maintaining a drawing register.
- The review and approval process for design dockets ensures that the project design aligns with client requirements and technical feasibility before moving forward to the next phases.

Exercise

A. Multiple Choice Questions (MCQs)

1. What should a business development plan for a retail fit-out and exhibition project include?
   a. Only aesthetic design features
   b. Services offered, market segmentation, compliance with standards, and sustainability goals
   c. Ignoring compliance standards
   d. Focus on interior decoration only

2. How should client requirements be analyzed for a retail fit-out or exhibition project?
   a. By reviewing layouts and ensuring alignment with branding and visual identity
   b. Focusing only on the budget without considering other factors
   c. Ignoring regulatory requirements
   d. Only considering customer preferences without technical standards

3. What is typically included in the scope of work (SOW) for retail fit-out and exhibition projects?
   a. Only the aesthetic aspects
   b. Deliverables, client inputs, timelines, and exclusions like civil engineering
   c. Just the furniture specifications
   d. Only the technical aspects of the design

4. Which of the following is a key element in the project estimate for retail fit-out and exhibition projects?
   a. Only the design costs
   b. Project Estimate Summary, Gantt chart, and Risk Register
   c. Only material costs
   d. Ignoring timelines

5. What does the review and approval process for a design docket ensure?
   a. That the project design aligns with client requirements and is technically feasible
   b. That no client input is required
   c. That the project timeline is ignored
   d. That only aesthetic design elements are approved

Practical Activity: Retail Layout Planning and Zoning Optimization

Scenario

You are part of a design team hired by a mid-size retail chain that sells apparel, electronics, toys, and seasonal items. You have been provided with the store layout above. Your goal is to analyze the layout, identify improvement opportunities, and propose an updated layout plan to enhance both visual appeal and shopping efficiency.



Tasks

Task 1: Zone Evaluation Matrix

Create a table to assess the placement of each major department.

Zone	Placement Score (1–5)	Visibility	Footfall Expected	Is It Optimal? (Y/N)	Why / Why Not?
Women's Clothing					
Home Electronics					
Snack Bar					
Checkout					

Deliverable: Completed evaluation matrix with justification.

Task 2: Identify 3 Customer Journey Issues

- Based on the flow arrows and placement, identify at least three problem areas in the customer path (e.g., crowding, low engagement zones, unclear transitions).
- Suggest improvements for each issue.

Deliverable: Written response with bullet points.

Task 3: Re-Zoning Proposal

Using the same layout structure:

- **Propose one major improvement in each of the following:**
  - Product Placement (e.g., Women's Clothing at front)
  - Checkout Experience
  - Restroom/Service Area Positioning

Deliverable: Sketch or re-labeled layout plan (can be drawn digitally or manually with labels).

Task 4: Justify Proposed Changes

Write a short note explaining the logic behind your new layout:

- Mention retail design principles like "Decompression Zone," "Right Turn Bias," "Power Wall," or "Destination Zones".
- Connect your justification with the customer journey and sales uplift.

Deliverable: 200–300 word write-up.

Final Submission

- Layout Evaluation Table
- Journey Issues + Suggestions
- Updated Zone Plan Sketch
- Justification Write-up

Notes

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

19. Annexure

Annexure-I

Module Name	Unit No.	Topic Name	Page No.	URL	QR code
Module 1: Introduction to the Role of Assistant Project Manager (Interior Design)	Unit 1.1: Interior Design Industry and Organizational Structure	Introduction to FFSSC	45	https://www.youtube.com/watch?v=QDdZ3P9IYf4	
Module 2: Introduction to Various Types of Interior Projects, Products, Materials, and Accessories Chain	Unit 2.1: Interior Design Basics and Process Flow	Elements of Interior Design	45	https://www.youtube.com/watch?v=OuOzTQZMD9s	
	Unit 2.2: Furniture Trends and Interior Projects	Interior Design Trends	**80**	https://www.youtube.com/watch?v=4rFxk8W9yUg	
		Integrating Modern Luxury Furniture with Natural Elements, Wood, and Stone	**80**	https://www.youtube.com/watch?v=2qssN68fNXI	
Module 3: Interpret and Analyze the Client Requirement	Unit 3.1: Themes, Styles, Layouts Associated with Interior Design Projects	Interior Design Style	**98**	https://www.youtube.com/watch?v=LfxxGgePA6w	
Module 4: Site survey/Recce for Interior Designing	Unit 4.1: Site Surveys	Interior Design - Site Analysis	**125**	https://www.youtube.com/watch?v=YX-3O82xEQ0	
	Unit 4.2 Measurement and Marking Activities	How to take Site Measurement		https://www.youtube.com/watch?v=xHY2fVTvITI	

Module Name	Unit No.	Topic Name	Page No.	URL	QR code
Module 5: Client Deliberations and Market Research	Unit 5.1: Conduct Market Research and Trend Analysis	AI for Interior Design	148	https://www.youtube.com/watch?v=FmM0Xj-urvc	
Module 6: Project Budgeting and Execution Planning	Unit 6.1: Project Planning and Timeline Management	Time Management	148	https://www.youtube.com/watch?v=1jAVFCH0Siw	
Module 7: Design Project Drafts, Mood Boards, and Models	Unit 7.1: Mood Boards, 3D Renders, and Miniature Models Development	Sketchup Tutorial for Beginners	195	https://www.youtube.com/watch?v=GOZkvQwtjZ4	
		Create a Mood Board Step by Step Easy Tutorial Using Canva	195	https://www.youtube.com/watch?v=EJRwAxdQyLM	
Module 8: Team and Task Management	Unit 8.2: Management and Monitoring	Boost Team Productivity	213	https://www.youtube.com/watch?v=l7Xqv6nzd6U	
		Performance Management	246	https://youtu.be/WYMr8NZdG54?si=MQSAFWWUhRM3jsJd	
Module 9: Prepare and Validate the Design Drafts and Drawings	Unit 9.1: Approval for Construction (AFC) Drawings	GFC, IFC, As Built, Concept, AFC, Design Drawings I Types of Drawings in Construction		https://www.youtube.com/watch?v=vHEq3bQNIj4	
Module 10: Procurement Management and Monitoring of on-Site Project Work	Unit 10.1: Procurement and Tender Documentation	Project Procurement Basics		https://www.youtube.com/watch?v=AxOeDE8cP8k	

Module Name	Unit No.	Topic Name	Page No.	URL	QR code
	Unit 10.3: Project Installation and Handover	Handover pack for your interior designers	246	https://youtu.be/mQUUs7MLDK8?si=dPrmlQ8NrRWyRtDc	
Module 11: Health, Safety and Hygiene Protocols while Designing	Unit 11.3: Emergency Preparedness and Response	Cardiopulmonary Resuscitation (CPR)	284	https://www.youtube.com/watch?v=hTS6gtaTHcI	
		How to Use a Fire Extinguisher		https://www.youtube.com/watch?v=w4jHpHoYZhk	
		Essential Safety Signs		https://www.youtube.com/watch?v=SqZ5np_lCr0	
Module 12: Material Conservation and Resources Optimization	Unit 12.2: Sources of Energy and Consumption	Materials and Resources		https://youtu.be/YaZ9tKBCJx8?si=7oQT1s63_BJQSw5U	
Module 13: Technicalities in a Residence and Kitchen Project	Unit 13.1: Business Development and Client Requirement Analysis for Residence and Kitchen Project	Kitchen Design: Layout, Materials & Dimensions | Lighting, Countertops & Appliances | Color Combo		https://www.youtube.com/watch?v=yLpNZEwMlWs	
Module 14: Technicalities in a Commercial and Hospital Project	Unit 14.1: Business Development and Client Requirement Analysis for Academic Institution Project	Hospital Interior Design		https://www.youtube.com/watch?v=nfN1p0GzQ5g	

NCVET
कौशल गुणवत्ता प्रगति

Skill India
कौशल भारत-कुशल भारत

सत्यमेव जयते
GOVERNMENT OF INDIA
MINISTRY OF SKILL DEVELOPMENT
& ENTREPRENEURSHIP

N·S·D·C
RE IMAGINE FUTURE

FFSC
FURNITURE
& FITTINGS
SKILL COUNCIL
कुशल • सक्षम • आत्मनिर्भर

Address: 407-408, 4th Floor, DLF City Court, Sikanderpur
Gurgaon 122002, Haryana, India
Email: info@ffsc.in
Web: www.ffsc.in
Phone: +91 124 4513900